IN THE ENVIRONMENT COURT AT CHRISTCHURCH

I TE KŌTI TAIAO O AOTEAROA KI ŌTAUTAHI

ENV-2023-CHC

Under The Resource Management Act 1991

(the Act)

In the Matter of an appeal pursuant to Clause 14 of

Schedule 1 of the Act concerning the

Dunedin City Council Second Generation District Plan (**2GP**) –

Variation 2

Between DDS PROPERTIES (2008) LIMITED

Appellant

And DUNEDIN CITY COUNCIL

Respondent

NOTICE OF APPEAL ON BEHALF OF DDS PROPERTIES (2008) LIMITED



GALLAWAY COOK ALLAN LAWYERS

Phil Page

Dunedin 9054 Ph: +64 (3) 477 7312

Fax: (03) 477 5564

PO Box 143

Phil.Page@gallawaycookallan.co.nz

NOTICE OF APPEAL ON BEHALF OF DDS PROPERTIES (2008) LIMITED

To: The Registrar

Environment Court

Christchurch Registry

- DDS Properties (2008) Limited (DDS) appeals against a decision of the Dunedin City Council on a decision of the 2GP – Variation 2 regarding the zoning of a site at 774 Allanton-Waihola Road (Decision).
- 2. DDS made a submission regarding the Decision.
- 3. DDS is not a trade competitor for the purposes of section 308D of the Resource Management Act 1991.
- 4. DDS received notice of the decision on 8 February 2023.
- 5. The decision was made by Dunedin City Council.
- 6. The decision DDS is appealing is Variation 2 Hearing Panels Report section 2.3.2.1 which refused to rezone property at 774 Allanton-Waihola Road (**Site**) to Township and Settlement Zone and Large Lot Residential 1 (**Decision**).
- 7. The reasons for this appeal are:
 - (a) The Site is currently zoned Rural Taieri Plain, the Site is adjacent to Township and Settlement, Rural Taieri Plain and Rural Coastal zones.
 - (b) The Decision does not fully realise the purpose of Variation 2 which is to enable Dunedin City Council to meet its residential capacity obligations under the National Policy Statement on Urban Development (2020) (Updated May 2022) (NPSUD). Due to this, the Decision unreasonably limits the extent to which Variation 2 can give effect to the NPSUD.

- (c) The Decision failed to place appropriate weight on the ability to provide additional medium-term greenfield housing development capacity.
- (d) The Decision does not provide adequate housing choices that will meet the needs of people and communities and future generations of a range of dwelling types and locations.
- (e) The Decision gave insufficient weight to ensuring there are resilient townships and failed to give effect to Objective 2.2.4 of the 2GP. Further development occurring in townships means they can maintain and improve resilience.
- (f) The Decision discounts Policy 2 in NPSUD and places insufficient weight on market demand for new development capacity in the Allanton township. Developing the Site is a logical extension of Allanton and improves the township's resilience.
- (g) The Decision failed to accept DDS's evidence on the potential 3Waters infrastructure and the extent to which constraints would be overcome by the submitter.
- (h) The Decision failed to give weight to the proposal's consistency with maintaining visual amenity.
- (i) The Decision gave little weight to the Site's potential to reduce carbon emissions by increasing housing availability for people employed locally.
- (j) The Decision disregarded the potential for acceptable access to be provided to the State Highway network.
- (k) There is no geotechnical or natural hazard reason to exclude the majority of the site for residential land use.
- (I) The Decision ignored or misunderstood DDS's evidence that no development is proposed in the Hazard 1A (flood) Overlay Zone and that the Geosolve report found that the Hazard 1 (flood) Overlay Zone can be designed around.

- (m) The Site is not subject to the National Policy Statement on Highly Productive Land 2022 (NPS-HPL) as Variation 2 is a Councilinitiated plan change and comes within clause 3.5(7)(b)(ii) of the NPS-HPL.
- 8. DDS seeks the following relief:
 - (a) Accept Appellants Original Submission.
 - (b) Any further, other, or consequential relief to give effect to the original submission or the grounds raised in this Notice.
- 9. The following documents are attached to this notice:
 - (a) A copy of the original submission.
 - (b) A copy of the Decision and
 - (c) A list of names and addresses of persons to be served with a copy of this notice.

Phil Page

Solicitor for the Appellant

DATED 17TH MARCH 2023

Address for service

for Appellant: Gallaway Cook Allan

Lawyers

123 Vogel Street

P O Box 143

Dunedin 9054

Telephone: (03) 477 7312

Fax: (03) 477 5564

Contact Person Phil Page

Advice to Recipients of Copy of Notice

How to Become a Party to Proceedings

You may be a party to the appeal if you made a submission on the matter of this appeal and you lodge a notice of your wish to be a party to the proceedings (in form 33) with the Environment Court, and serve copies on the other parties, within 15 working days after the period for lodging a notice of appeal ends. Your right to be a party to the proceedings in the Court may be limited by the trade competition provisions in section 274(1) and Part 11A of the Resource Management Act 1991.

You may apply to the Environment Court under section 281 of the Resource Management Act 1991 for a waiver of the above timing requirements (see form 38).

How to Obtain Copies of Documents Relating to Appeal

The copy of this notice served on you does not attach a copy of the relevant decision. These documents may be obtained, on request, from the Appellant.

Advice

If you have any questions about this notice, contact the Environment Court in Auckland, Wellington or Christchurch.

List of names of persons to be served with this notice

Name	Address	Email Address
Otago Regional Council		Warren.hanley@orc.govt.nz
Susan Alanna Browne		martin.alanna.browne@gmail.com
Alan and Leanne Coombs (A & L Coombs Contracting Ltd)		coombscontracting@outlook.com

Roxanne Davies

From:

Sent:

To: Subject:

Hi,
I've also just noticed that part of the submitter name is missing from the submitter form - see underlined in next sentence.
The correct submitter name is: DDS Properties (2008) Limited.
Do you need me to redo page 1 of the submission form? If so, I will need to complete on Monday 12th April 2021 as I am currently on holiday.
Cheers,
Emma Peters Consultant Sweep Consultancy Limited P.O. Box 5724 Dunedin 9054 Phone 0274822214 www.sweepconsultancy.co.nz
On 9/04/2021 9:01 am, emma wrote:
Hi,
Re part of form below that states: "Supporting documents (file name/s) No file uploaded"
Just double checking that the files attached to the two emails lodging the submission were uploaded? The documents to be uploaded are shown in the snips below.
Cheers,
Emma Peters Consultant Sweep Consultancy Limited P.O. Box 5724 Dunedin 9054 Phone 0274822214 www.sweepconsultancy.co.nz
Email 1:

Emma Peters <sweepconsultancy@gmail.com> on behalf of emma

<Emma@sweepconsultancy.co.nz>

Re: Variation 2 submission completed

Friday, 9 April 2021 09:23 a.m. District Plan Submissions

From Me
Subject Email 1 of 2: Submission of DDS Properties Ltd - Riverview: 774 Allanton-Waihola Reply to Me
To districtplansubmissions@dcc.govt.nz

Hi,

Please find attached the following documents forming the submission of D

- Completed Form 5;
- Submission Notes;
- Table 1; and
- · Structure Plan;
- · Landscape Figures; and
- Landscape Report.

The landscape figures and landscape report will be sent in a subsequent er Please confirm receipt of both emails.

Cheers,

Emma Peters Consultant Sweep Consultancy Limited P.O. Box 5724 Dunedi



Email 2:

From Me

Subject Email 2 of 2: Submission of DDS Properties Ltd - Riverview: 774 Allanton-Waihola F

Reply to Me


To districtplansubmissions@dcc.govt.nz

Attached:

Landscape Figures and Report

Cheers,

Emma Peters Consultant Sweep Consultancy Limited P.O. Box 5724 Dunedin S



On 9/03/2021 9:28 am, districtplansubmissions@dcc.govt.nz wrote:

Below is a copy of your submission: Reference number 809085 **Submitter name DDS Properties Ltd** Organisation Contact person/agent Emma Peters, Consultant, Sweep Consultancy Ltd **Postal address** PO Box 5721 Dunedin 9054 **Email** emma@sweepconsultancy.co.nz Contact phone number I could gain an advantage in trade competition through this submission No If you could gain an advantage in trade competition through this submission please select an answer Variation 2 change ID Rezone 774 Allanton - Waihola Road in accorance with the structure plan 4 apply a **SPMA** Provision name and number, or address and map layer name All provisions relating to New Development Mapped Area My submission seeks the following decision from the Council Accept the change with amendments outlined below **Details** See attatched submission notes Reasons for my views

Thank you for taking the time to submit on Variation 2

See attatched submission notes

Supporting documents (file name/s)

No file uploaded

Do you wish to speak in support of your submission at a hearing

Yes

If others make a similar submission, would you consider presenting a joint case at a hearing

Yes

From: Emma Peters on behalf of emma
To: District Plan Submissions

Subject: Email 1 of 2: Submission of DDS Properties Ltd - Riverview: 774 Allanton-Waihola Road (Residential Rezone

& Application of a Structure Plan Mapped Area

Date: Thursday, 4 March 2021 04:58:38 p.m.

Attachments: Submission Form 5 - DDS Properties Ltd - Riverview.PDF

Variation 2 Submission Notes - DDS Properties Ltd - Riverview 774 Allanton Waihola Road.pdf

Variation 2 Submission Notes - DDS Properties Ltd - Table 1.pdf

Riverview Structure Plan.pdf

Hi,

Please find attached the following documents forming the submission of DDS Properties Ltd in relation to the application of a SPMA for the residential rezone of 774 Allanton-Waihola Road.

- Completed Form 5;
- Submission Notes;
- Table 1; and
- Structure Plan;
- Landscape Figures; and
- Landscape Report.

The landscape figures and landscape report will be sent in a subsequent email.

Please confirm receipt of both emails.

Cheers,

Emma Peters Consultant Sweep Consultancy Limited P.O. Box 5724 Dunedin 9054 Phone 0274822214 www.sweepconsultancy.co.nz

From: Emma Peters on behalf of emma

To: District Plan Submissions

Subject: Email 2 of 2: Submission of DDS Properties Ltd - Riverview: 774 Allanton-Waihola Road (Residential Rezone

& Application of a Structure Plan Mapped Area

Date:Thursday, 4 March 2021 04:58:27 p.m.Attachments:744 Allanton Waihola Lndscp figs final.pdf

774 Allanton Waihola Rd Var Two landscape rpt final.pdf

Attached:

Landscape Figures and Report

Cheers,

Emma Peters Consultant Sweep Consultancy Limited P.O. Box 5724 Dunedin 9054 Phone 0274822214 www.sweepconsultancy.co.nz

VARIATION 2 - ADDITIONAL HOUSING CAPACITY



SUBMISSION FORM 5

CLAUSE 6 OF FIRST SCHEDULE, RESOURCE MANAGEMENT ACT 1991

This is a submission on Variation 2 to the Second Generation Dunedin City District Plan (2GP), Your submission must be lodged with the Dunedin City Council by midnight on 4 March 2021. All parts of the form must be completed.

Privacy

Please note that submissions are public. Your name, organisation, contact details and submission will be included in papers that are available to the media and the public, including publication on the DCC website, and will be used for processes associated with Variation 2. This information may also be used for statistical and reporting purposes. If you would like a copy of the personal information we hold about you, or to have the information corrected, please contact us at dcc@dcc.govt.nz.or 03 477 4000.

Make your submission

Online: www.dunedin.govt.nz/2GP-variation-2 | Email: districtplansubmissions@dcc.govt.nz

Post to: Submission on Variation 2, Dunedin City Council, PO Box 5045, Dunedin 9054

Deliver to: Customer Services Agency, Dunedin City Council, Ground Floor, 50 The Octagon, Dunedin

Submitter details (You must supply a postal and/or electronic address for service)

First name: 0 K) S properties	Ltd			
Last name:					
Organisation (if a	pplicable):				
Contact person/a	gent (if different to submitter):	Emma 5724	Peters, consulta	nt, Sweep Co	nsultancy Ltd
Suburb:					
City/town:	Dunedin			, P.	ostcode: 9054
Email address:	emma e swee	plonsu	Itancy, co.nz		
Trada same					

Trade competition

Please note: If you are a person who could gain an advantage in trade competition through your submission, your right to make a submission may be limited by clause 6(4), Schedule 1 of the Resource Management Act.

I could gain an advantage in trade competition through this submission:

Yes N

If you answered yes, you could gain an advantage in trade competition through this submission please select an answer:

Yes No

My submission relates to an effect that I am directly affected by and that:

a. adversely affects the environment; and

b. does not relate to trade competition or the effects of trade competition.

Submission

Submissions on Variation 2 can only be made on the provisions or mapping, which are proposed to change or alternatives that are clearly within the scope of the 'purpose of the proposals', as stated in the Section 32 report. Submissions on other aspects of the 2GP are not allowed as part of this process.

You must indicate which parts of the variation your submission relates to. You can do this by either:

- making a submission on the Variation Change ID (in which case we will treat your submission as applying to all changes related to that change topic or alternatives within the scope of the purpose of that proposal); or
- · on specific provisions that are being amended.



The specific aspects of Variation 2 that my submission relates to are:

www.dunedin.govt.nz/2GP-variation-2)

Variation 2 change ID (please see accompanying Variation 2 – Summary of Changes document or find the list on

Rezone 774 Allanton - Waihola Road in accordance with the For example: D2 Structure plan a apply a SPMA.

Provision name and number, or address and map layer name (where submitting on a specific proposed amendment):

For example: Rule 15.5.2 Density or zoning of 123 street name.	
My submission seeks the following decision from the Council: (Please give precise details, such as what you would like u retain or remove, or suggest amended wording.)	ıs to
✓ Accept the change	
Reject the change Reject the change	
If the change is not rejected, amend as outlined below	
See attached submission note,	
Reasons for my views (you may attach supporting documents):	
If you wish to make multiple submissions, you can use the submission table on page 3 or attach additional pages.	
see attached submission notes	
The attacked submission notes	
Hearings Do you wish to speak in support of your submission at a hearing: Yes No	
If others make a similar submission, would you consider presenting a joint case at a hearing: Ves No	
Signature: M. Emma Peter, Consultant, Sweep Consultancy Date: 4/3/	21

Notified Policy / Kule	vuie		Issue	Potential Solutions
CHANGE F2-6 Policy 9.2.1.AA			Limit the extent of Policy 9.2.1.AA and related	Delete the words 'on adjoining or nearby sites
Policy 9.2.1,44 Only al infrast infrast nearby	llow subdivision in a new ructure is designed to con sites that are zoned for ur	Only allow subdivision in a new development mapped area where any new public or private 3-waters infrastructure is designed to connect to, and provide capacity for future urban development on adjoining or nearby sites that are zoned for urban development, where necessary, (Change F2-6)	lower order provisions to provision of capacity of infrastructure within the specific new	that are zoned for urban development and insert the words 'within the subject new development mapped
Rule 9.5.3.Z			development mapped area.	
9.5.3 Assessment of per	9.5.3 Assessment of performance standard contraventions	aventions		AND Similarly in Rule 9.5.3.Z.a.iii
Performance standard	Matters of discretion	Guidance on the assessment of resource consents		delete the words 'on adjoining or nearby sites
development effluit mapped area of store connections of store stormwater (Rue 9.3.7.As) (Change F2-2)	a Effectiveness and filling and additional of stormwater management and effects of stormwater from future ceverlopment	iii. Only allow subdivision in a new development mapped area where any new public or private 3-waters infrastructure is designed to connect to, and provide capacity for future urban development on adjoining or nearby sites that are zoned for urban development, where necessary (Policy 8.2.1.44), (Change F2.6)		that are zoned for urban development' and insert the words 'within the subject new development mapped area' before 'where necessary'. AND
Rule 9.6.2.X				delete the words 'on adjoining or nearby sites
9.6.2 Assessment of restricted discretionary activities	tricted discretionary activ	rities	1	that are zoned for urban
Activity	Matters of discretion	Guidance for the assessment of resource consents	T	words 'within the subject new development mapped
In a new development mapped area. All subdivision activities (Change F2-2)	a. Effectiveness and efficiency of stormwater management and effects of stormwater from inture development	it. Only allow subdivision in a new development mapped area where any new public or private 3-waters infrastructure is designed to connect to and provide capacity for future urban development on adjoining of nearby sites that are zoned for urban development, where necessary (Policy 9.2.1.44). (Change F2-6):		area' before 'where necessary'.

	15.10.4 Assessment of development performance standard contraventions	standard contraventions	
Performance standard	Matters of discretion	Guidance on the assessment of resource consents	ource consents
Site coverage and impermeable surfaces	c. Effects on efficiency and affordability of Infrastructure (stormwater) (Change F2-3)	See Rule 9.5.	
Rule 15.11.5.Z	a. Effects of stomwater from future development (Change F2-3)		
15,11.5 Assessment of rescheduled heritage item	restricted discretionary ac	15.11.5 Assessment of restricted discretionary activities in an overlay zone, mapped area, heritage precinct or affecting a scheduled heritage item	, heritage precinct or affecting a
Activity		Matters of discretion	Guidance on the assessment of resource consents
ı			
areas, all subdivision activities, in development, and supported livin (Change F3-2) Kaikorai Valley Road (Change Colum Change F777)	areas, all subdivision activities, multi-unit development, and supported living facilities (Change F3-2) Kalkoral Valley Road (Change IN07)	a Effectiveness and efficiency of wastewater management and effects of wastewater from future development (Change F3-2)	See Rule 9.6 (Change F3-2)
Watte Fox Lane (Change RTZ1)	(Change RTZ1)		

I have the capacity to detain wastewater for a 24-hour period, prior to releasing to the wastewater via a connection to the wastewater public infrastructure network. The volume of wastewater to be detained will be calculated with reference to iii. have a minimum 20 year expected life for all electrical / mechanical components and a minimum 50 year expected life whave components and materials that comply with the DCC's 3-Waters Approved Product and Manufacturers List and a Specify the design and location of one or more communal wastewater detention systems to detain wastewater from the specified in Rule 9.6.2 Y must include a proposed wastewater management plan that ensures that all wastewater from the infrastructure network via the use of a communal wastewater detention system, unless such a system has already been 1. Any application for subdivision, multi-unit development or supported living facilities in a new development mapped area juture development of the entire new development mapped area does not exceed the capacity of the wastewater public 3. The wastewater management plan must be submitted along with the written approval of all landowners within the new where practicable, be located such that all flow goes to one communal wastewater detention system with no 2. The wastewater management plan must be prepared by a chartered engineer and meet the following requirements. Part 5 of the Dunedin Code of Subdivision and Development 2010 ('Code of Subdivision' Part 5 of the Dunedin Gode of Subdivision and Development 2010 (Code of Subdivision) ii. be compatible with DCC's Supervisory Control and Data Acquisition (SCADA) system development mapped area unless they are the applicants. (Change F3-2) b. The communal wastewater detention systems must. approved for the site and will be connected to entire new development mapped area for all civil components 5.9 Y Wastewater management plans Rule 9.9.Y

of wastewater from future management and effects efficiency of wastewater a Effectiveness and development new development mapped areas all Y. In the following subdivision

activities multi-unit facilities: (Change development and supported living

Road (Change Kaikorai valley Selwyn Street (LONI

F3-23

- (Change RTZ2)
- Wattie Fox Lane (Change RTZ1)

Relevant objectives and policies (in addition to those outlined in 9.6.2.2 and

i Objective 9.2.1

connect to a communal wastewater detention system that ensures that facilities in specified new development mapped areas to provide or wastewater public infrastructure network (Policy 9.2.1 BB), (Change ii Require subdivision, multi-unit development or supported living development mapped area does not exceed the capacity of the all wastewater from the future development of the entire new

Several assessment quidance

resolved or a communal on-site wastewater detertion system that is designed for and associated with subdivision and/or development of 50 or more residential units is integrated into the public networkand create wastewater will be required to connect to the system until it is facility or subdivision that will lead to development that will require a wastewater but new connections to the network will not be allowed and consequentially any multi-unit development supported living vested in the DCC After installation of the system, all activities that ii. The identified new development mapped areas are serviced for connection will likely be declined) until capacity constraints are no longer reguired.

iv in assessing the appropriateness of a proposed communal on-site wastewater management plan submitted with the application (see wastewater derention system. Council will consider the proposed Special Information Requirement - Rule 9.9 Y), (Change F3-2)

Conditions that may be imposed.

- A requirement for the communal on-site wastewater detention system to be installed prior to certification of the survey plan pursuant to section 223 of the RIMA
- in A requirement for the communal on-site wastewater detention system to be vested in the DCC, along with a site containing it which is of a minimum 500m² in area and sultable for residential development.
- defect period agreement to be in place prior to vesting the communal on-site wastewater detention system and associated land. (Change vii A requirement for necessary easements and a fired maintenance or

CHANGE F3-2 Policy 2.7.1.2.Y Ensure areas of new urban development provide for publicinfrastructure networks that represent the least possible long term cost to example the networks.		
w urban development provide for public infrastructure networks that represent the least possible long term cost to	1. Potential difficulties 1. with NDMA being in med multiple ownership for the	1. Provide a claw-back mechanism whereby when the developer
	dample, if there is / are luctant or recalcitrant	astructure in a NDN multiple owners ve
owner(owner(s) within the	that infrastructure in DCC,
1 policies and assessment rules that require wastewater detention for specified sites in the new development mapped area to allow urban expansion while ensuring any impacts on the wastewater public infrastructure network are no more than minor. (Change F3-2)		the infrastructure (less the developer for developer's pro rata share) and DCC claws-back the cost
Policy 9.2.1.BB		of that infrastructure vis development contributions
Policy 9.2.1.BB Require subdivision, multi-unit development or supported living facilities in specified new development mapped areas to provide or connect to a communal wastewater detention system that ensures that all wastewater from the future development of the entire new development mapped area does not exceed the capacity of the wastewater public infrastructure network. (Change F3-2)		as the other land within that NDMA comes online. AND Provide a mechanism
Note 9.3.7.ZA General Advice		rily acq is in NDMA for ture.
b. In new development mapped areas specified in Rule 9.6.2 Y, immediate connections to the wastewater public infrastructure network will not be available due to network capacity constraints. In these cases, subdivision consent may be refused even if this standard is met where an on-site communal wastewater detention system that serves 50 or more residential units is yet to be approved as a solution to capacity constraints. (Change F3-2)		
 Rule 9.6.2.Y		
9.6.2 Assessment of restricted discretionary activities		
Activity Matters of discretion Guidance for the assessment of resource consents.		

		ea, heritage precinct or affecting a	Guidance on the assessment of resource consents	See Rule 9.6 (Change F2-2)
See Rule 9.5. (Change F2-2)		15.11.5 Assessment of restricted discretionary activities in an overlay zone, mapped area, heritage precinct or affecting a scheduled heritage item	Matters of discretion	f. Effectiveness and efficiency of stormwater management and effects of stormwater from future development (Change F2-2)
a. Effectiveness and efficiency of stormwater management and effects of stormwater from future development.		stricted discretionary activi	2	D1 &
development mapped area Service connections stornwater (Change F2-2)	Rule 15.11.5.Y	15.11.5 Assessment of rescheduled heritage item	Activity	In a new development mapped area All subdivision activities (Change D1 & Change F2-2)

consider the use of detention tanks, In for larger subdivisions, the design should incorporate consideration of how stormwater management areas, can be integrated into reserves and recreation spaces. Integrated into reserves and recreation spaces. In for larger subdivisions, the design proposal should demonstrate how the integrity of the stormwater mitigation and management measures will not be compromised during and after subdivision (for example, avoiding premature contamination of devices during the construction of houses and ensuring that open drains that form part of the system will not be blocked or altered. (Change F2-2 & Change F2-3)	a. Natural Hazards Performance Standards b. Maximum building site coverage and impermeable surfaces c. Setback from scheduled tree d. Structure plan mapped area performance standards (where relevant) W. Service connections - stormwater (in a new development mapped area) (Change F2-2)	be added {Change F2-2}	in a new development mapped area, all development that creates an impermeable surface must comply with Rule 9.3.7.4A. (Change P2-2)		
Rule 15.3.4.1 Development Activity Status Table	Performance standards that apply to all development activities	Rule 15.6.X 15.6.X Service Connections - Stormwater - to be added {Change F2-2}	development mapped area, all development that creates a	Rule 15.10.4.Y	15.10.4 Assessment of development performance standard contraventions

- v for the purposes of this requirement, primary infrastructure, includes both open and closed conduits designed to contain the flows generated by the 10% AEP rainfall event
- the primary flow path becomes overloaded or inoperative and consists of overland flow paths with sufficient capacity to transfer the flows, generated by rainfall events up to 1% AEP. Secondary flow paths, should be aligned with natural flow for the purposes of this requirement, secondar flow paths, means the flow path over which surface water will flow If paths and located on public land where possible. If located in private property, 1% AEP secondary flows should be through primar, infrastructure unless protected by an easement.
- impermeable surfaces permitted in the underlying zone and any proposed roading or accessways for the subdivision area e, assess the difference between pre-development flows and post-development flows, taking into account the maximum or in a new development mapped area, for the entire NDMA)
- f specify the design and location of any on-site stormwater management systems to accommodate the calculated difference in flows.
- g where relevant, specify the design and location of secondary flow paths,
- h specify any upgrades to stormwater public infrastructure, or other infrastructure, that will be used to add capacity, where it is required
- I the stormwater management system design should allow for stormwater quality treatment to reduce potential contaminants that the site and development may generate.
- building areas should not require stormwater quality treatment providing they are constructed with Inert building products areas requiring stormwater quality treatment include trafficked areas such as roads, driveways and carparks. Roof and which avoid exposed metal surfaces;
- stormwater quality treatment devices shall larget the removal of 75% total suspended solids (TSS) on a long-term average basis and consider the avoidance or minimisation of thermal loading effects
- I the stormwater management design should consider the use of low impact design features, for example, it grassed/landscaped swales and other vegetation areas,
 - Tongstoff I allowed in the state of the stat
 - ii. infiltration trenches/bioretention systems,
- ii. storage ponds/wetlands/sediment ponds;
- iv, rainwater tanks harvesting and reuse
- v. rain gardens, green roofs; or
- vi. porous surface treatments;

CVE	dfor into
Relevant objectives and policies (in addition to those outlined in 9.6.2.2 above). I. Objective 9.2.1.	1. Only allow subdivision activities in a new development mapped area where. 1. an on-site stormwater management system that is designed for the whole NDIMA and is installed in full or in planned stages prior to development will ensure there is no increase in the predevelopment will ensure there is no increase in the predevelopment will ensure there is no increase in the predevelopment while increase in the predevelopment of the stormwater public infrastructure at any point, or 2 where this is not practicable any adverse effects from an increase in discharge on the stormwater public infrastructure are no more than minor (Policy 9.2.1.). (Change F2-2)
a Effectiveness and efficiency of stormwater management and effects	development
development mapped area	activities (Change F2-2)

Special Information Requirement Rule 9.9.X

9.9 X Stormwater management plans

1. Application for subdivision in a new development mapped area must include a proposed stormwater management plan that demonstrates how Policy 9.2.1.Y will be achieved, unless such a plan has already been approved as part of an earlier Subdivision, (Change F2-2)

- 3. Stormwater management plans must
- a. be prepared by a chartered engineer or other suitably qualified person.
- o, be of a level of detail commensurate with the scale of the activity, complexity of stormwater management issues, and potential for adverse effects from stormwater. (Change F2-2 & Change F2-3)
- approval of all owners of land within the new development mapped area unless they are the applicantle. (Change F2-2) c. for a new development mapped area (NDMA), address the whole NDMA area, and be submitted along with the written
- d. assess pre-developmentflows and post-developmentflows, generally based on the following rainfall events:
- i for primary infrastructure, a 10% annual exceedance probability (AEP) for the critical storm duration for the NDMA and the critical storm duration and the catchment upstream of the point of discharge, and
- II. for secondary flow paths, a 1% AEP for the chilical storm duration for the NDMA and the chilical storm duration for the catchment upstream of the point of discharge,
- iii for the purposes of this requirement, critical storm duration, means the duration of rainfall event likely to cause the highest peak flows or water levels;

9.5.3 Assessment of per	9.5.3 Assessment of performance standard contraventions	ventions
Performance standard	Matters of discretion	Guidance on the assessment of resource consents
2 in a new development mapped area • Service cennections - slomwater	a Effectiveness and efficiency of stormwater management and effects of stormwater from future development	Relevant objectives and policies 1. Objective 92.1 III. Require development in a new development mapped area that creates impermeable surfaces to be connected to the integrated communal on-site stormwater management system that meets Policy 9.2.1.Y (Policy 9.2.1.X). (Change P2.2)
(Ghange F2-2)		General assessment guidance. ** Council will consider how stormwater will be managed and may require a stormwater manage ment plan to be submitted with the application (see Special information Requirement - Rule 9.9.X). (Change F2-2)
		Conditions that may be imposed include. V. A requirement for essements, covenants, consent notices, or bonds to ensure future development will be in accordance with a stormwater management plan.
		A requirement for on-site stormwater management, such as the installation of detention devices. In accordance with the approved stormwater management plan. (Change F2-2)
Rule 9.6.2.X		
9.6.2 Assessment of rest	9.6.2 Assessment of restricted discretionary activities	ies
Activity	Matters of discretion	Guidance for the assessment of resource consents

Rule 9.3.7.AA

mapped area' to the end of

Rule

the sentence at

9.3.7 AA Stormwater (Change F2-2)

- a in a new development mapped area, all development that creates an impermeable surface must
- 1 procto the communal stormwater management system being installed, any development that creates less than 60m I connect to a communal stormwater management system that services the new development mapped area, except of impermeable surface is exempt from this standard
- o Activities that contravene this performance standard are restricted discretionary activities. (Change F2-2)

Note 9.3.7.AAA

lote 9.1.1.AAA - General advice and other requirements outside of the District Plan (Change F2-2)

- prior to development as part of the assessment of a subdivision consent. The requirements for stormwater management in a new development mapped area. Policy 9.2.1.Y requires installation of a communal stormwater management system. 9.X (Change F2-2) are set out in the Special Information Requirements - Rule 9 ro
- equirements regarding buildings and sitework in relation to managing surface water and effects on other property Clause E1 - Surface Water of the New Zealand Building Code (Building Requiations 1992, Schedule 1) contains ò
- Development that will divert surface water may require resource consent under the Otago Regional Plan. Water
- d. Discharge of stormwater to any Otago Regional Council scheduled drain or overland flow path is managed by the Otago fection Management Bylaw 2012 Council Flood Pro
- relopment affects the flow of surface water, this effect is also subject to the common law principle of natural sendude.

a)

- except as amended by the Code of Subdivision. This includes a requirement that stormwater systems be provided so that construction of stormwater systems be undertainen in accordance with NZS 4404 2004 (now replaced by NZS 4404 2010) Part 4 of the Dunedin Code of Subdivision and Development 2010 (Code of Subdivision) requires that design and any new development results in an instantificant increase of runoff wherever possible (Clause 4.2.8).
- stormwater management systems, please contact DCC 3 Waters on 03 477 4000 at the earliest opportunity, (Change F2-4) For further information on connections to the public stormwater network and for assistance with design requirements for

Notified Policy / Rule	Issue	Potential Solutions
CHANGE F2-2	1. Potential difficulties	1. Provide a claw-back
Policy 2.2.2.Y	With NUMIA being in med multiple ownership – for the	with NDIMA being in mechanism whereby when multiple ownership – for the developer of
Policy 2.2.2.Y - to be added (Change F2-2)	example, if there is a	infrastructure in a NDMA
Enable and encourage on-site low impact design stormwater management through policies and assessment rules that require stormwater management in new development mapped areas. (Change F2.2)	reluctant or recalcitrant	with multiple owners vests that infrastructure in DCC,
Delete Policy 2.2.5.2 Policy 2.7.1.2.X	2. Requirement to install infrastructure prior to obtaining subdivision	
Ensure areas of new urban development provide for public infrastructure networks that represent the least possible long ferm cost to the public through.	(s)	and DCC claws-back the cost of that infrastructure vis development contributions
x policies and assessment rules that require on-site stormwater management in the new development mapped area. (Change	development process is for resource consent to	as the other land within that NDMA comes online.
62-2)	be obtained prior to installation occuring so	Provide
Policy 9.2.1.Y	that all matters can be whereby	the DC
Objective 9.2.1	assessed together. Focus	assessed together. Focus compulsorily acquire
Land use, development and subdivision activities maintain or enhance the efficiency and affordability of public water supply, wastewater and stormwater infrastructure	of infrastructre at this stage of the consent / development process.	new infrastructure. AND Delete from Rule 9.9.X.3.C
Policy 9.2.1.Y a. an on-site stormwater management system that is designed for the whole NDMA and is installed in full or in planned stages, prior to development will ensure there is no increase in the pre-development peak stormwater discharge rate from the site into the stormwater public infrastructure (all any point), or b. where this is not practicable, any adverse effects from an increase in discharge on the stormwater public infrastructure are no more than minor. (Change F2-2)	3. Limiting the extent o' Rule 9.5.3.2.	3. Limiting the extent of submitted along with the Rule 9.5.3.Z. written approval of all owners of land within the new development mapped area unless they are the applicant/s'.
Policy 9.2.1.X		2. Delete requirement for
Policy 9.2.1.X Require development in a new development mapped area that creates impermeable surfaces to be connected to the integrated communal on-site stormwater management system that meets Policy 9.2.1.Y (Change F2-2)		infrastructure to be installed prior to subdivision consent.
		3. Add the words 'within the subject new development

Ħ	General assessment durdance. III. Council will generally require subdivision in a NDMA to enable the maximum develorately require subdivision in a NDMA to enable the parameters are subjected while self achieving the other objectives and colleges of the Plan (e.g. as many sites suitable for residential development as practicable or through other means of maximising development capacity. (Change 188)	iv Where a supplication proposes a residential yield less than what is allowed by the coning and where this is not required to achieve other plant objectives, or politics. Council will conside. 1. how this might affect the afordability and officient delivery of public utilizationing.	2: how this might affect the ability to proude a reasonable amount of affordable housing in the development, and 3: the potential cumulative effects of inefficient development on loss of rural land. (Change DS).	15.11.5 Assessment of restricted discretionary activities in an overlay zone, mapped area, heritage precinct or affecting a scheduled heritage item	Matters of discretion Guidance on the assessment of resource consents		e. Whether subdivision design See Rule 12.X (Change D8) supports efficient use of land (Change D8)
o, whence spoots efficient use offend (Change 188)				ricted discretionary activit	Ě	record bonness the meaning of the	a di subdivision activities (Change D1 & Change F2-2)

HANGE D8 Olicy 2.7.1.2 Olicy 2.7.1.3 Olicy 2.7.1.2 Olicy 2.7.1.3 Olicy 2.7.1	Notified Policy / Rule	Issue	Potential Solutions
Is use areas of new unan development provide for public infrastructure networks that represent the least possible long term cost in a reason to be public through. Least season the public through. Least season through a season tribe and assessment rules for new development mapped areas that encourage efficient use of land as a way to maintie and assessment rules for new development mapped area where the subdivision design ensures the area of contractions for (Change D4). Lefficient public infrastructure, Objective 2.7.1. (Change D8) Lefficient public infrastructure of land, while also achieving the other elements of Objective 12.2.X. (Change D8) Lefficient use of land, while also achieving the other elements of Objective 12.2.X. (Change D8) Lefficient use of land, while also achieving the other elements of Objective 12.2.X. (Change D8) Lefficient of restricted discretionary activities in a Transition Overlay Zone or mapped area	CHANGE D8 Policy 2.7.1.2	12.X.2 –	
policies and assessmentrules for new development mapped areas that encourage efficient use of land as a way to maximise ne cost effectiveness of public infrastructure delivery (Change D8) pjective 12.2.X (Change D1) uture residential growth areas are developed in a way that achieves the Plan's strategic directions for (Change D1) is a compact and accessible city, (Objective 2.2.4), and (Change D8) is efficient public infrastructure, (Objective 2.7.1), if Change D8) licy 12.2.X.5 licy 12.2.X.5 let 12.X.2.5.e. 12.X.2.5.e.	Ensure areas of new urban development provide for public infrastructure networks that represent the least possible long ferm cost to the public through:	assessment ly	
policies and assessment rules for new development mapped areas that encourage efficient use of land as a way to maximise tects effectiveness of public infrastructure delivery. (Change D8) Jective 12.2.X {Change D1} Luture residential growth areas are developed in a way that achieves the Plan's strategic directions for. {Change D1} e. a compact and accessible city (Objective 2.2.4), and (Change D8) f. efficient public infrastructure. (Objective 2.7.1). {Change D8} f. efficient public infrastructure. (Objective 2.7.1). {Change D8} licy 12.2.X.5 Only allow subclivision in a new development mapped area where the subclivision design ensures the efficient use of land, while also achieving the other elements of Objective 12.2.X. {Change D8} 12.X.2.3.5.e.		undertaken in rezoning	
olective 12.2.X {Change D1} uture residential growth areas are developed in a way that achieves the Plan's strategic directions for. {Change D1} e. a compact and accessible city.(Objective 2.2.4), and {Change D8} f. efficient public infrastructure. (Objective 2.7.1), {Change D8} licy 12.2.X.5 olicy 12.2.X.5 let 12.X.5. 12.X.2.Assessment of restricted discretionary activities in a Transition Overlay Zone or mapped area	 policies and assessment rules for new development mapped areas that encourage efficient use of land as a way to maximise the cost effectiveness of public infrastructure delivery. (Change D8) 	placement of Transition	
e. a compact an frefficient public for 12.2.X.5 offo, 12.2.X.5 offo, 12.2.X.5 offo, 12.2.X.5 offo, 12.X.2.5.e	Objective 12.2.X {Change D1}	area).	
e. a compact and frefficient public licy 12.2.X.5 olicy 12.2.X.5 olicy 12.2.X.5.e	Future residential growth areas are developed in a way that achieves the Plan's strategic directions for. (Change D1)		
DI DI			
Jan San San San San San San San San San S	e. a compact and accessible city (Objective 2.2.4), and (Change D8) f. efficient public infrastructure (Objective 2.7.1), (Change D8)		
mer	Policy 12.2.X.5		
ule 12.X.2.5.e 12.X.2 Assessment of restricted discretionary activities in a Transition Overlay Zone or mapped area	Policy 12.2 X.5 Only allow subdivision in a new development mapped area where the subdivision design ensures the efficient use of land, while also achieving the other elements of Objective 12.2 X. (Change D8)		
12.X.2 Assessment of restricted discretionary activities in a Transition Overlay Zone or mapped area	Rule 12.X.2.5.e		
	12.X.2 Assessment of restricted discretionary activities in a Transition Overlay Zone or mapped area		

See Rule 12 X (Change D7) b Provision for amenity planting and public amenities (Change D7) In a new development mapped area.
 All Subdivision activities (Change D1 & Change F2-2)

Notified Policy / Rule	Rule			Issue	Potential Solutions
CHANGE D7 Objective 12.2.X {Change D1}	e D1}			What is the threshold for the requirement?	
Future residential growth a	reas are developed in a We	sy that achieves the Plan	Future residential growth areas are developed in a way that achieves the Plan's strategic directions for, (Change D1)		development area). AND / OR
d form and structure	d form and structure of the environment (Objective 2.4.1); {Change D7}	ive 2.4.1); {Change D7}		What constitutes a 'adequate' area?	an Provide guidance on what constitutes 'adequate' areas
Policy 12.2.X.4					of amenity planting and
Policy 12.2 X.4 Only area area attract	Only allow subdivision in a new development mareas of amenity planting (including but not limit attractive residential environment, (Change D7)	v development mapped iding but not limited to star (Change D7)	Only allow subdivision in a new development mapped area where the subdivision will provide adequate areas of amenity blanting (including but not limited to street trees) and public amenities to ensure an attractive residential environment. (Change D7)		מחבר שוויים מוויים מווי
Rule 12.X.2.5.b					
12.X.2 Assessment of re	stricted discretionary activ	vities in a Transition Ove	12.X.2 Assessment of restricted discretionary activities in a Transition Overlay Zone or mapped area		
Activity.	Matters of discretion	Guidance on the asses:	Guidance on the assessment of resource consents		
5. In a new development mapped strea; • All subdivision activities (Change D1);	b. Provision for amenity planting and public amenities (Change DT)	Relevant objectives and policies: 1 Objective 12.2.X If The subdivision provides adequate a (including but not limited to street tree ensure an attractive residential environments in Requirements for street tree and other change 11.1.	I Objectives and policies: 1 Objective 12.2.X. If The subdivision provides adequate areas of amenity planting (including out not limited to street trees) and public amenites to ensure an attractive residential environment (Policy 12.2.X.4). Conditions that may be imposed include. If Requirements for street tree and other subdivision amenity planting. (Change U.).		
Rule 15.11.5.Y					
15.11.5 Assessment of resti scheduled heritage item	ricted discretionary activities	s in an overfay zone, mapp	15.11.5 Assessment of restricted discretionary activities in an overlay zone, mapped area, heritage precinct or affecting a scheduled heritage item		
Activity	Matte	Natters of discretion	Guidance on the assessment of resource consorts		

15.11.5 Assessment of restricted discretionary activities in an overlay zone, manned area, heritage precinct or affecting a		
scheduled heritage item	es în an overlay zone, mapped ar	a, heritage precinct or affecting a
Activity	Matters of discretion	Guidance on the assessment of resource consents
Y In a new development mapped area. • All subdivision activities (Change D1 & mal Change F2-2)	d Whether subdivision design maintains or enhances areas with significant natural environment values. (Change D6)	See Ruls 12 X (Change D6)

Notified Policy / Rule		Issue	Potential Solutions
CHANGE D6 Objective 12.2.X and Policy 12.2.X.2		What is the threshold for 'significant natural	Provide a definition for this term.
Objective 12.2.X (Change D1)		environment values :	
Future residential growth areas are developed in a w	Future residential growth areas are developed in a way that achieves the Plan's strategic directions for (Change D1)		
b. Indigenous biodiversity (Objective 2.2.3); (Change D6)	(Change D6)		
Policy 12.2.X.2 Only allow subdivision in a new de any future land use and developm important indigenous vegetation a environment values. (Change D6)	Only allow subdivision in a new development mapped area where the subdivision is designed to ensure any future land use and development will protect, and where necessary restore, any waterways, areas of important indigenous vegetation and habitats of indigenous fauna, or other areas with significant natural environment values. (Change D6)		
Rule 12.X.2.5.d 12.X.2 Assessment of restricted discretionary	ule 12.X.2.5.d 12.X.2 Assessment of restricted discretionary activities in a Transition Overlay Zone or mapped area		
Activity Matters of discretion	Guidance on the assessment of resource consents		
d. Whether subdivision gest on maintains or enhances areas with significant natural environment values (Change D6).	sion Relevant objectives and policies. 1. Objective 12.2.X 1. In Esubdivision is designed to ensure any future land use and development will protect, and where necessary restore, any waterways, areas of Important indigenous vegetation and habitats of indigenous fauna, or other areas with significant natural environment values. (Policy 12.2.X.2). (Change D6), Conditions that may be imposed include. Iii. A requirement to protect areas through reserve status or other legal mechanisms. Iv. A requirement to undertake conservation activity. (Change D6).		

1. Objectives and policies: 1. Objective 12.2.X. 1i. The subdivision layout and orientation provides for houses to be designed with good solar access to living areas and outdoor living spaces (Policy 12.2.X.3), (Change D5)		rea, heritage precinct or affecting a	Guidance on the assessment of resource consents	See Rule 12 X (Change D5)
Relevant objectives and policies 1. Objective 12.2.X ii. The subdivision layout and orientation i designed with good solar access to livi spaces (Policy 12.2.X.3), (Change D5)		15.11.5 Assessment of restricted discretionary activities in an overlay zone, mapped area, heritage precinct or affecting a scheduled heritage item	Matters of discretion	a Whether subdivision design supports energy-efficient housing (Change D5)
a. Whether subdivision design supports energyefficient housing (Change D5).		of restricted discretionary ac		n a new development mapped area: • All subdivision activities (Change D1 & Change F2-2)
5. In a new development mapped area. • All subdivision activities (Change D1).	 Rule 15.11.5.Y	15.11.5 Assessment of n scheduled heritage item	Activity	Y In a new developm • All subdivision : Change F2-2

Notified Policy / Rule	Issue	Potential Solutions
CHANGE D5 Delete Policies 2.2.2.5.b and 2.2.5.3.a and replace with new clause in Policy 2.2.2.X.a	No issues.	N/A
Policy 2.2.2.X to be added {Change D5 & Change E4}		
Encourage improvements to the environmental performance of new housing by. (Change E4) a. use of policies and assessment rules for subdivision, including in new development mapped areas, that encourage		
subdivisions to be designed to maximise the potential for bassive solar besign in notating to be protected for its heritage by encouraging new medium density housing in parts of the city that have old housing stock that is not protected for its heritage believe.	aber	
c. rules that require outdoor living space to be on the sunny side of buildings, and requiring principal living areas to connect to	d10	
use support mings pace, and a long to boundary to facilitate access to sunlight in outdoor areas. (Change E4)		
Objective 12.2.X & Policy 12.2.X.3		
Objective 12,2.X (Change D1)		-
Future residential growth areas are developed in a way that achieves the Plan's strategic directions for, (Change D1)		
c. environmental performance and energy resilience (Objective 2.2.2); {Change D5}		
Policy 12.2.X.3 Only allow subdivision in a new development mapped area where the subdivision layout and orientation provides for houses to be designed with good solar access to living areas and outdoor living spaces. (Change D5)	El .	
Rule 12.X.2.5.a		
12.X.2 Assessment of restricted discretionary activities in a Transition Overlay Zone or mapped area		
Activity Matters of discretion Guidance on the assessment of resource consents		

### Relevant cojectives and policies. 1 Objective 12.2.X If The subdivision provides or otherwise ensures good access to outdoor-recreation opportunities (including playgrounds) and, where possible opportunities for official cycling and walking tracks within and between different residential developments and connecting to community facilities and services (Folisy 12.2.X.1), (Change D4).	Conditions that may be imposed include. ii Location size and shape of recreation reserves, including a minimum length of road frontage.	waredurementalises to be included in a recreation reserve.	A. A requiremention the recreation space to be developed prior to vesting in BCC. (Change DA).		15.11.5 Assessment of restricted discretionary activities in an overlay zone, mapped area, heritage precinct or affecting a scheduled heritage item	Matters of discretion Guidance on the assessment of resource consents	© Provision of recreation spaces See Rule 12.X (Change D4)
5. In a new c Provision of regression development mapped area existence of second of s				Rule 15.11.5.Y	15.11.5 Assessment of restricted discretionary activities scheduled heritage item	Activity	In a new development mapped area. All subdivision activities (Chango D1 &

Table 1: NDMA Issues and Potential Mechanisms For Solutions

CHANGE D4			
Policy 2.3.3.1.X		How will this operate in NDMA where land is in	How will this operate in A trigger mechanism for NDMA where land is in requirement of formal
Support community and leisure	Support community and leisure activity sport and recreation, and essential community facilities in Dunedin through:	development is likely to	development is likely to recreation, sporting, social
		occur over time and	occur over time and and cultural activities, and
X policies and assessment formal and/or informal space for	 Dollcles and assessment rules for subdivision in a new development mapped area that require consideration of the need for formal and/or informal space for recreation, sporting, social and cultural activities, and community facilities. (Change D4) 	operation between	between is, over so many lots /
Delete Polcy 2.6.1.6.b		S32 report talks about greenspac	e is required.
Objective 12.2.X		large greenileld areas	AND ON
Eulure residential growth areas a a facilities and spaces that	Future residential growth areas are developed in a way that achieves the Plan's strategic directions for {Change D1} a, facilities and spaces that support social and cultural well-being (Objective 2.3.3); {Change D4}	Isee para 250J, nowever, Specify what gr many of the 'large is required as a greenfield areas' in which NDMAs	Isee para 290,, nowever, Specify what greenspace etc many of the large is required as a minimum for greenfield areas' in which NDMAs.
Policy 12.2.X.1		NDMA are in multiple	
Policy 12.2.X.1 Only allow access to off-road cy community	Only allow subdivision in a new development mapped area where it will provide or otherwise ensure good access to outdoor recreation opportunities (including playgrounds) and where possible, opportunities for off-road cycling and walking tracks within and between different residential developments and connecting to community facilities and services. (Change D4)	ownership.	
Rule 12.X.2.5.c			
12.X.2 Assessment of restric	12.X.2 Assessment of restricted discretionary activities in a Transition Overlay Zone or mapped area		
Activity, III8	Matters of discretion Guidance on the assessment of resource consents.		
:			

- performance standards in the 2GP and the subdivison and development process.
- The application of the Structure Plan Mapped Area provides the opportunity for Council to attach performance standards necessary to achieve desired outcomes for this specific site (e.g. attentuation onsite of stormwater and / or wastewater at time of subdivision if found to be necessary on assessment of infrastructure capacity). This is a more appropriate methodology than applying the NDMA to change area GF01.
- · The NDMA provisions will, in this case, act as an impediment to development.

In the alternative, the submitter requests changes to the NDMA provisions as set out in Table 1 of these submission notes. Table 1 contains the NDMA related provisions, issues and potential solutions.

On the submission form the submitter states that their submission relates to "All provisions relating to New Development Mapped Area". In the event that Table 1 is not a complete list of all such provisions, the submitter reserves the right to make comment in evidence on any other NDMA related provisions which are found to be missing from Table 1.

Submission:

This represents an exciting opportunity to create a special place to live and work which adds to the vibrancy of Allanton ensuring its continued resilence as a 'township and settlement'. The proposal makes provision for varying types of housing, working spaces and recreational uses, good transportation links for all modes of transport (including the opportunity to install a siding for use by passenger trains) as well as providing for ecological enhancement and conservation.

1. Rezone 774 Allanton – Waihola Road in Accordance with the Structure Plan and Apply a Structure Plan Mapped Area

Reasons:

- Experienced severe shortage of residential capacity in Dunedin, including in this locale, meaning Council cannot satisfy the short through to long term demand with sufficient capacity to meet Council's obligations pursuant to NPS-UD 2020. Rezoning this site residential helps Council meet its obligations pursuant to NPS-UD 2020 by ensuring available capacity to the market. The structure plan also provides the opportunity to acehieve other policy objectives such as conservation and ecological enhancement in an 'ecologically threatened' landsacpe.
- Rezone meets rezoning criteria specified in 2GP (see 2.6.2.1) in particular, it provides a
 logical extension of Allanton over an area which is close to infrastructure, services and public
 amenities. The rezone will ensure that Allanton grows in resilience. The site sits between
 two transportation corridors being SH1 and the main trunk line provision has been made
 for a future rail transportation link.
- The proposal has landscape support see attached landscape figures and report.
- Provides for flexibility of development in this locale for which there is experienced high
 demand for more residential capacity. Provides an opportunity to provide a residential
 community with recreation and conservation / ecological gains.
- The scale of this proposal provides the ability to tackle any infrastructure issues via agreement between Council and the site developer.
- The areas for residential activity are all located on ridges out of the flood hazard overlay zone.
- 2. Do not put a New Development Mapped Area over the Site and Instead use a Structure Plan Mapped Area

Reasons:

· Provision of infrastructure is adequately governed by existing subdivision and land use

Figure 4: Controls on Built Environment within Structure Plan Mapped Area

Table Two: Proposed conditions

Key: applies / permitted 🌘 does not apply / precluded 🧧

Condition	Town and Settlement	Large Lot Residential 1
250m² maximum residential unit FA¹	•	
300m ² maximum residential FA		•
Maximum building height of 5.5m from existing or modified ground level, per level	•	•
Maximum building height - 6m from existing or modified ground level		•
External wall length - maximum 20 m length	•	
External wall length - maximum 25m length		•
External materials: Wood, natural stone, concrete	•	•
Block, plaster, brick	•	•
Stainless steel (exposed) and mirror glass	•	•
Concrete paving: Tint to 50% LRV ²	•	•
External wall colours: 40% max. LRV	•	
Roof colours: 5% below LRV of walls	•	
External wall colours: 35% max. LRV		•
Roof colours: 5% below LRV of walls		•
Retaining walls: 2.0 m max. above existing or modified ground level. Colour - 50% or less LRV	•	•
Retaining offset: 2 m max, from house on all sides	•	
Retaining offset: 4 m max. from house on all sides		•
Water tanks: 40,000 litre tank, 1m above ground	•	•
Water tanks: 35% LRV max – locate from public view	•	•

- 1 FA means Floor Area. Maximum floor area for residential units excludes attached garages
- 2 LRV refers to light reflectivity values Resene Colour Chart BS5252

Water Services Map

Figure 3: Proximity of 3 Waters Infrastructure to the Site.

lotes:

- The eastern edge of the site abuts 3 waters infrastrcuture at Allanton.
- 3 waters will be provided by reticulated services either via Dunedin City Council 3 waters infrastructure, private, or a mixture of the two.
- The scale of the proposal and volume of residential lots at the proposed densities means that it is likely to be economically feasible for the site developer to put in 3 waters engineered solutions to any existing capacity constraints in the 3 waters infrastructure. It is also likely that some level of treatment will be occur on site.

Figure 2: Structure Plan for Site



LANDSCAPE PROPOSAI

774 Allanton-Waihola

DATE: 22-02-21 SCALE @A3: 1:5000 DWG: 003 REVISION #:






Note: Given the scale of the rezone, developmen locale for a reasonable period of time.

Note: Given the scale of the rezone, development will be staged over a course of time providing a contiuous stream of residential capacity in this

Variation 2 Submission Notes - DDS Properties Ltd - Riverview: 774 Allanton - Waihola Road



Notes:

- land will be subdivided from the balance of the site and sold to an adjoining land owner. The term 'site' in this submission refers to the area of The triangle of land by the river separated from the body of the site by the railway line does not form part of the structure plan. This piece of land covered by the structure plan and excludes the triange of land on the 'other' side of the railway line.
 - The site is within scope for Variation 2.





774 Allanton-Waihola

DATE: 22-02-21 SCALE @A3: 1:5000

REVISION #:

DWG: 003







	Elaeopcarpus hookerianus (pokaka)	***
	Griselinia littoralis (broadleaf)	***
•	Hoheria angustifolia (narrow-leaved lacebark)	***
•	Kunzea ericoides (kānuka)	***
	Leptospermum scoparium (mānuka)	****
	Myrsine australis (matipo)	***
	Myrsine divaricata (weeping matipo)	**
	Olearia odorata (scented tree daisy)	***
	Olearia lineata (twiggy tree daisy)	****
	Phormium tenax (harakeke/flax)	* **
	Plagianthus regius (ribbonwood)	**
	Pittosporum eugenioides (lemonwood)	***
	Pittosporum tenuifolium (kōhūhū)	***
•	Podocarpus hallii (Hall's totara)	***
•	Pseudopanax crassifolius (lancewood)	***
	Sophora microphylla (kōwhai)	***
	Veronica salicifolia (koromiko)	****

- suitable for long periods of inundation.
- ** suitable for areas which are water-free for the majority of time but become inundated with water during high rain and flood events.
- *** suitable for upper bank zone of riparian planting, in dry areas.
- **** tolerates having damp feet but does not like being water logged for long periods.

Amenity tree planting list

Small sized street trees:

- Cornus 'Eddies White Wonder' (white flowering dogwood)*
- Malus 'Arrows Gold' (yellow fruiting crabapple)*
- Prunus serrulata 'Shirotae' (Mount Fuji cherry tree)*
- Prunus yedoensis (Yoshino cherry)*
- Sorbus aucuparia 'Josephs Rock' (cream berry rowan)*
- Ulmus glabra 'Pendula' (weeping elm)*

Medium sized street trees:

- Arbutus unedo (Irish strawberry tree)
- Acer capillipes (snake bark maple tree)*
- Fraxinus ornus (flowering manna ash)*
- Magnolia kobus (white flowering yulan magnolia)*
- Magnolia grandiflora 'Blanchard' (evergreen magnolia)
- Pyrus calleryana 'Aristocrat' (ornamental pear)*
- Sophora microphylla (kôwhai)

Large sized street trees:

- Fraxinus excelsior 'Purple Spire' (purple ash tree)*
- Metrosideros 'umbellata' (southern rata)

Highway planting

- Coprosma cathamica (Chatham Island tree)
- Fraxinus excelsior (European Ash)*
- Hoheria angustifolia (narrow-leaved lacebark)
- Liquidambar styraciflua 'Worplesdon' (sweet gum)*
- Liriodendron tulipifera 'Fastigata' (upright tulip tree)*
- Olearia paniculata (akiraho)
- Pittosporum eugenioides (lemonwood)
- Plagianthus regius (ribbonwood)
- Tilia platyphyllos (European lime)*

Wetland and riparian planting list

•	Austroderia richardii (toetoe)	**
	Carex secta (purei)	*
	Carex virgata (swamp sedge)	* *
	Carpodetus serratus (marble leaf)	***
•	Copromsa lucida (shiny karamu)	***
	Coprosma propinqua (mingimingi)	**
	Coprosma rotundifolia (mikimiki)	* * 1
	Cordyline australis (cabbage tree)	**
	Dacrycarpus dacrydioides (kahikatea)	* *
	Dacrydium cupressinum (rimu)	***

^{*}deciduous.

Appendix Two

Provisional site planting list

Chantal Whitby
Hudson Associates, Landscape Architects

Adverse Visual Effects Rating Scale

Effect Rating	Use and Definition
Very High:	Total loss of key elements / features / characteristics, i.e. amounts to a very significant negative change in visual amenity.
High:	Major modification or loss of most key elements / features / characteristics, i.e. little of the predevelopment visual amenity remains and amounts to a significant negative change in visual amenity values. <u>Concise Oxford English Dictionary Definition</u> High: adjective - Great in amount, value, size, or intensity.
Moderate - High:	Modifications of several key elements / features / characteristics, i.e. the pre-developmen visual amenity remains evident but materially changed.
Moderate:	Partial loss of or modification to key elements / features / characteristics, i.e. the predevelopment visual amenity remains evident but is changed. <u>Concise Oxford English Dictionary Definition</u> Moderate: adjective - average in amount, intensity, quality or degree
Moderate - Low:	Minor loss of or modification to one or more key elements / features / characteristics, i.e. new elements are not uncharacteristic within the visual environment and do not disturb the prodevelopment visual amenity.
Low:	Very little material loss of or modification to key elements / features / characteristics. i.e. new elements integrate seamlessly into the pre-development visual environment. <u>Concise Oxford English Dictionary Definition</u> Low: adjective-1. Below average in amount, extent, or intensity.
Very Low:	Negligible loss of or modification to key elements/ features/ characteristics of the baseline, i.e visual influence of new elements is barely discernible.

Note:

The following assessment guidelines have been reproduced from the Queenstown Lakes District Council guidelines for assessment of landscape and visual effects, published April 2019 in response to an Environment Court request for some consistency of landscape expert evidence within the current District Plan review Appeals.

'Minor' Test

For the purposes of notification determination, an adverse effects rating of 'Moderate – Low' corresponds to a 'minor' adverse effects rating. An adverse effects rating of 'Low' or 'Very Low' corresponds to a 'less than minor' adverse effects rating.

Note: This determination applies to both landscape and visual effects.

Adverse Landscape Effects Rating Scale

Effect Rating	Use and Definition
Very High:	Total loss of key elements / features / characteristics / values, i.e. amounts to a very significan negative change in landscape character and / or landscape values.
High:	Major modification or loss of most key elements / features / characteristics / values, i.e. little of the pre-development landscape character remains and amounts to a significant negative change in landscape character and / or landscape values. <u>Concise Oxford English Dictionary Definition</u>
	High: adjective - Great in amount, value, size, or intensity.
Moderate - High:	Modifications of several key elements / features / characteristics / values, i.e. the pre- development landscape character and / or landscape values remains evident but materiall changed.
Moderate:	Partial loss of or modification to key elements / features / characteristics / values, i.e. the predevelopment landscape character and / or landscape values remains evident but is changed. <u>Concise Oxford English Dictionary Definition</u> Moderate: adjective - average in amount, intensity, quality or degree
Moderate - Low:	Minor loss of or modification to one or more key elements / features / characteristics / values i.e. new elements are not uncharacteristic within the receiving landscape and do not disturthe pre development landscape character and / or landscape values.
Low:	Very little material loss of or modification to key elements / features / characteristics / values i.e. new elements integrate seamlessly into the pre-development landscape character and / or landscape values. <u>Concise Oxford English Dictionary Definition</u>
	Low: adjective- 1. Below average in amount, extent, or intensity.
Very Low:	Negligible loss of or modification to key elements/ features/ characteristics / values of the baseline, i.e. influence of new elements on landscape character and / or landscape values is barely discernible.

Extracts from Que	enstown Lakes District Council Guideli	nes for Landscape and Visual Effects Assessment
April 2019		

- point on the slopes and looks over the south/west catchment. Trees line the entrance roadway and shelter planting surrounds the house.
- 7.17 The potential short term adverse visual effects are assessed as being 'moderate-high'. The medium-and long-term adverse landscape effects are assessed as being 'moderate-low'. The basis of this assessment is the short-term views available to passing motorists and the approach or exit to Allanton that is the primary focus on this section of busy highway. No roadside pull-overs exist at road level and there are few elements in the surrounding landscape that draw attention below road level.
- 7.18 The rise of the coastal hills to the south/east and the distant Maungatua Range are the visual 'highpoints' in this journey, and it is expected that the proposal will add to the present interest and
 character of this stretch of road through boundary and internal site planting.

8.0 Discussion and Conclusion

- 8.1 The proposal seeks to provide for several residential communities that have points of difference on the basis of location, lot size, planting, and topography within a structure of environmental measures. These include planted road boundary setbacks, protection and enhancement of existing wetland, reintroduction of native vegetation, internal work/life spaces and café and board walks, external retail for the wider community, and plans for rail connection to Dunedin.
- 8.3 At present a rural overlay applies to the farm area, which contains one residential house. If approved the development will provide for between 245 to 376 lots to be located on 36ha of the approximate 53ha of farmland on the south/east side of the railway line. A further 12.4ha is proposed for native and exotic planting, over both stages of development.
- 8.4 No overlays of significant landscape value apply to the site and there is no evidence of indigenous onsite vegetation apart from wetland species. The proposal will lead to a fundamental change in land use and character, but this is assessed as positive in the medium to long term, i.e., 10 20 years.
- 8.5 The development proposal is supported by this landscape scoping assessment and it is recommended that approval to rezone be given subject to a structure plan and conditions being submitted by the applicant that meets the approval of Regional and Territorial Authorities. Approval should rest on meeting technical performance and provisions for a management mechanism that provides certainty about implementation.

Hugh Forsyth Landscape architect

contribute positively to the visual environment or the ecological health of the surrounding catchment or receiving watershed. The proposal will remove the present adverse environmental effects and provide an extensive area of on-site vegetation that will benefit birds, insects, and lizards as well as providing elements of naturalness that are absent at present.

7.9 Viewsheds

Public views to the site are available from the Taieri River bridge on Centre Road and from Allanton-Waihola Road. Private views are limited to the three houses located mid slope on the south/east side of the highway. The site is screened from view from houses located within Allanton Village and for most of those on the slopes above, due to topography and screening provided by the shelter belt on the north/east site boundary of the site.

- 7.10 Views from Taieri River bridge are available to vehicles approaching from the western Moana Airport end and have the top headland area of the mid ridgeline as a focal point. The upper areas of the ridge are visible over the trees that line the riverbanks. The speed limit on the bridge is 80kph both views are fleeting (Fig.1 and Fig.2).
- 7.11 Allanton-Waihola Road provides the greatest opportunity for public views and over a longer duration.

 The common boundary is approximately 0.95km in length with traffic speeds ranging between 80 –

 100kph. At 80ph this length provides for a viewing period of approximately 43 seconds for both catchments.
- 7.12 When traveling southwards from Allanton views are initially screened by the shelter belt on the north/east boundary. Past this point the road alignment moves slightly to the south/east and away from the farm boundary, limiting views to the passenger and drivers as the road swings away from the site. The first focal point of this view is the shelter belt between the eastern and western catchments and then the existing farm buildings (Vpt 3).
- 7.13 Wider views can be gained at a glance and in between the small rises that result from where the carriageway cuts through the previous ridge, but these views can only be gained in full by using the stop over point, located off road to the east. Much wider and strategic views are then available by climbing to the road level or from stationary car views while cuing to rejoint the highway (Vpt.4).
- 7.14 When travelling northwards from Waihola traffic speed is mostly 100kph on approach. The shelterbelt of the south/west ridge screens views to the first section of the south/west catchment but the vista opens to motorists, once pass a slight embankment. Wider views include the ridge headland promontories, and distant wetland. The foreground of fields and small ridges and the mid ridge shelter belt is the most prominent in this view of approximately 260m (Vpt.6).
- 7.15 Three rural lifestyle neighbours overlook the farm from the slopes on the south/east side of the highway. These include numbers 759, 771, and 795 Allanton-Waihola Road. All are lifestyle blocks ranging from 5.3 to 10.4ha and located between 10 and 18m above the carriageway and a setback ranging between 90 and 140m.
- 7.16 Number 759 has the most direct and unimpeded view to the north/east catchment and set on the lower level relative to the highway. Number 771 also views the north/east catchment but its viewshed is restricted to the mid part of the site by gully planting between its location and number 759 and further roadside planting that screens lower site views. Number 795 is located at highest

7.0 Potential Landscape and Visual Effects

- 7.1 The present site has a rectangular form that is dissected south/east to north/west by series of broad ridges that run out to the Taieri river terraces from the hills above Allanton-Waihola Road. The route of the highway has modified these landforms, but they remain legible and fundamental to site structure. Three of the ridges are more prominent and provide the boundaries of two main site catchments and rise to form small promontories near the river boundary. Shelter planting near the roadside screens views across the initial site areas and further reinforces the site division and character.
- 7.2 Natural landscape elements include the hills that rise to the south/east of Allanton-Waihola Road and the ridges that flow from them, the wetland area in the south/west catchment, and the presence and influence of Taieri River and its associated terraces and floodplains. Significant infrastructure elements include the railway line and the highway with the road corridor dominant, due to elevation, excavation and formation embankments in construction, and ongoing noise and movement.
- 7.3 A fundamental change in land use and landcover will result from the consent and implementation of the development. It is considered that this change will bring short term adverse landscape effects and beneficial long-term effects. The potential short term adverse landscape effects are assessed as being 'moderate-high'. The medium- and long-term adverse landscape effects are assessed as being 'moderate-low'.
- 7.4 No landscape overlays apply to the full site or proposal area under the 2GP. On the basis of several site visits, during wet and fine periods, the overall impression is of a rural site that is cut off from the wider landscape context by a large road and the railway line, but which retains an individual sense of place and amenity in places.
- 7.5 The areas associated with the wetland, riparian gully near the north/west boundary, the river meadow to the north of the site, and the elevated ridge headlands towards the northwest boundary most reflect these higher levels. The consistent factor in these locations is distance from the road and an increase in the evidence of natural processes and unmodified riverscape landforms. Combined these provide a legible landscape structure and has a sense of place and topographical and geographic variation.
 - The proposal largely builds on these factors and places a low number of large lot residential sites on the ridge headlands and reinforces their form with extensive native planting on their lower northern slopes. This planting connects on the north/west boundary and continues back to the road boundary in the south/west. All of the present river meadow area has been included in the wetland planting regime. A passenger landing for a suburban train service is planned in this area but which floods annually. Any provision will need to provide for elevated access and will not affect this planting approach, which will further assist in mitigating the effects of run-off.
 - 7.7 The lower amenity areas of the north/east and south/west catchments that abut Allanton-Waihola Road will include native structure planting, separating the two catchments on the main centre ridge, and boundary planting of large trees below and alongside the road boundary. This will include a 10m set back along the road boundary and provide enclosure and privacy as the trees gain height. Riparian planting is included along the runoff areas and walkways are planned along these small gully areas.
 - 7.8 While the development will remove the land from rural production the soil is not considered to be off high value and the present land use pattern does not include many measures or land cover that

6.0 Mitigation measures

- There are several significant off-site effects that presently apply that are relevant to the mitigation measures proposed. These include flooding and infrastructure, and the by-products of farming. The Allanton-Waihola Road route is the primary infrastructure element in the adjacent landscape and brings movement, reflection, night-time lighting, and noise on an ongoing basis. Taieri River flood Plains extend back into the proposed site area. All of the site represents a bio-hazard in respect to farm run-off. At different times and climate conditions this may contain nitrogen, phosphorous, potassium, and e.coli. Lastly, three adjacent residents overlook the site, and will do in the future.
- 6.2 Water and waste mitigation measures include a development strategy that responds to the flood plain, through building on ridge and ridge slope areas, riparian set-backs and wetland planting along known and potential watercourse areas, and long-term planning for a sewerage treatment system for Stage Two that includes a wetland aspect as well as mechanical and chemical treatment.
- 6.3 The effect of increased on-site catchment is mitigated through the compulsory use of water storage tanks on all residential sites. Street drainage will be collected in swale drains and then channelled to small holding ponds to further mitigate peak runoff. The south/west catchment wetland will be increased in size and this increase in area and biomass will help retain runoff and assist in retention of sediment.
- 6.4 The expected roadside, boundary and wetland planting includes approximately 12.4ha in the following areas:
 - Wetland area: 77,441m² / 7.7 ha
 - Native structure planting: 19,940m² / 2 ha or 741m in length
 - Future gully riparian wetland: 6,475m² / 0.6 ha or 270m in length
 - Highway boundary trees: 21,348m² / 2.1ha or 928m in length
- 6.5 Boundary treatment of the Allanton-Waihola Road route will involve a double avenue of exotic field trees. The bridging of the present ridge landscape by the road has left some areas with high embankments that cannot be addressed by earth mounding or noise attenuation walls, and which are considered inappropriate.
- 6.6 The tree planting is expected to provide an amenity factor for motorists, as they deaccelerate and accelerate to and from Allanton 80kph area, and to screen or filter the effects of light and sound that vehicles emit on the roadway for residents. Some of the trees will be evergreen but the overall effect will be greater visibility of the site and received light in the winter period. Long term noise mitigation is anticipated through the policy adoption of electric vehicles. An associated decrease in noise will be experienced, on the site and in the wider NZ environment.
- 6.7 The roadside planting is also expected to lessen the potential adverse visual effects for the three residents on the up-hill side of Allanton-Waihola Road. Existing shelter planting restricts views from two of the dwellings and all are elevated by 10 to 18 metres above the road carriageway and a setback of between 90 and 140m. These houses have wide strategic views to the wider Taieri Plain and across to the Maungatua Range that will not be interrupted by the proposed development.
- 6.8 The change of use from stock to residential development will remove the source of most present potential off site biological effects.

5.11 The requirements for solar energy, sustainable building materials, and capture of storm water apply for each house site. Other conditions include restrictions of areas of impermeable site area outside the residential building, external colour for roof and wall, and restrictions on planting – refer Table Two. These seek to provide an environment that is not restrictive but also fits with the principles of the site and the amenity of other residents.

Table Two: Proposed conditions

Key: applies / permitted o does not apply / precluded

Condition	Town and Settlement	Large Lot Residential 1
250m² maximum residential unit FA¹	•	
300m² maximum residential FA		•
Maximum building height of 5.5m from existing or modified ground level, per level	•	•
Maximum building height - 6m from existing or modified ground level		•
External wall length - maximum 20 m length	•	
External wall length - maximum 25m length		•
External materials: Wood, natural stone, concrete	•	•
Block, plaster, brick	•	•
Stainless steel (exposed) and mirror glass	•	•
Concrete paving: Tint to 50% LRV ²	•	•
External wall colours: 40% max. LRV	•	
Roof colours: 5% below LRV of walls	•	
External wall colours: 35% max. LRV		•
Roof colours: 5% below LRV of walls		•
Retaining walls: 2.0 m max. above existing or modified ground level. Colour - 50% or less LRV	•	•
Retaining offset: 2 m max. from house on all sides	•	
Retaining offset: 4 m max. from house on all sides		•
Water tanks: 40,000 litre tank, 1m above ground	•	•
Water tanks: 35% LRV max – locate from public view	•	•

- FA means Floor Area. Maximum floor area for residential units excludes attached garages
- 2 LRV refers to light reflectivity values Resene Colour Chart BS5252

- 5.5 A new site access road is planned for connection to Centre Road and will cross at the north/west end of the present farm machinery business. The road will provide a collector function for a further hierarchy of streets, along the ridgelines, and lanes, that will provide access to many of the housing areas. A slip lane on the south/west side of Center Road will provide safe road access, for which NZTA provision. Outline permission has been gained for this intervention and potential purchase with the present owner.
- Parking areas will be provided in set locations on each street with general on-street parking discouraged. Cul-de-sac street patterns will not be part of the design unless the practical solution to corner sites. Access to Allanton-Waihola Road will be provided at the south/west corner site boundary for emergency and service vehicles but not for residential access.
- 5.7 A small office/business centre is proposed that will overlook the wetland. These units would be available for short- and long-term lease. They are intended to provide the opportunity for residents to bring an existing business to the site area or begin a new one. The units could be also be leased for a café, medical centre, day care, and other options.
- 5.8 Recreation opportunities are included in the structure of the structure plan. A walking/cycle track (approx.. 7km) and a pedestrian pathway (2.5km) pathway will provide access to the wider site and the wetland areas. These paths will provide return routes for recreational pedestrians, runners, and cyclists as well as those using public transport on daily basis. Play areas will be provided in the final concept development.
- Native tree and shrub species are proposed for the north/east and south/east boundaries and the northern sides of both main ridge headland areas. Protection of the existing wetland and an extension of its boundaries are proposed. A 10m wide band of exotic tree planting is proposed along the Allanton-Waihola Road boundary to both provide enclosure for future residents and amenity for road users. Overplanting of native wetland tree species are proposed to add to amenity and biodiversity of this area. Outline species for the different site areas are set out in Appendix Two.
- 5.10 The key principles of the development plan are to provide for a sense of place and space for each area within an evolving rural parkland structure. General and individual lot controls and conditions are proposed to reinforce this principle. At a site wide level this includes direction on the management of energy, rain and storm water, and waste-water while controls apply to height, building materials, impermeable area, colour, and vegetation for individual lot development.
- 5.11 Site wide development principles and conditions include:
 - All housing to meet the guidelines of the NZ Green Building Council, or similar code;
 - Building materials are to meet a sustainability standard;
 - Solar street lighting is to be incorporated and a 'night sky' standard adopted;
 - No residential gas is to be connected;
 - All storm water runoff is to be collected and treated on site prior to discharge;
 - All housing is to have a storm water collection tank for storm surge protection and irrigation;
 - Solar energy is required in all new housing; and
 - On site sewerage treatment is to be considered at 50% of full development capacity.

plants are growing across the floor but with many gaps and appear compromised by past stock access. The enhancement and protection of this area forms a significant part of the proposal.

5.0 The Proposal

- 5.1 The proposal builds on a detailed concept developed by Mr. Rogers that will provide for residential development of mixed scale within a semi-rural context and with the potential to increase amenities and transport options for existing and future Allanton residents. The working title of the proposal is 'Riverview' and has been developed to take advantage of the natural site topography and riparian and wetland pattern.
- 5.2 The proposal relies on the rezoning of the subject site area into areas of Township and Settlement and Large Lot Residential 1 under Variation Two, 2GP. The development will be staged with the north/east catchment being Stage One. The anticipated yield for both stages is set out in Table One:

Table One

Totals		36ha		245 - 376
14.	Large Lot Residential	11.6	2000 m ²	25
Total		24.4		220 - 351
13.	Township and Settlement	1.5	1000m ²	10
12.	Township and Settlement	9.9	450-750 m ²	70 - 139
11.	Township and Settlement	3.1	450m ²	48
10.	Township and Settlement	9.9	450-750m ²	92 - 154
Area	Proposed zone	На	Lot	Yield

5.3 Sustainable design and building principles underlie the concept and its anticipated development. The BRANZ website provides the following definition of sustainable building:

'Building sustainably is about using practices and systems that lessen impact on the environment, lower running costs and make homes healthy, accessible and comfortable. It includes energy efficiency, the move to a net zero-carbon economy and building resilience against hazards such as earthquakes, storms and flooding'

- 5.4 These principles are applied to the site wide plan and individual lots by:
 - Planning for public transport connections to Dunedin and Mosgiel, via bus and train;
 - On-site or adjacent retail to limit off-site shopping travel and to service Allanton Village;
 - On-site home office/business space for lease to support new or existing business;
 - A structure plan that builds on the natural topography and river flood cycle;
 - Conditions on the materials used for residential construction, energy supply, and stormwater treatment; and
 - Planning for on-site waste treatment, utilising natural biological as well as mechanical treatment, as the development reaches stage two.

- 4.2 The farm area is zoned Taieri Plain Rural zone under the Proposed Second-Generation Dunedin City District Plan (2GP). No landscape, heritage, archaeological or biodiversity overlays apply to the site but it is located at the base of the north/west slopes of Saddle Hill which is largely zoned as being 'Significant Natural Landscape'.
- 4.3 Areas of 'high class soil' apply to the margins of Taieri River but not to the main farm body that lies south/east of the railway line and is the subject proposal area. The site is subject to flooding from the Taieri River and overlays apply that indicate its potential extent on the land (Fig.2)
- 4.4 Mr. Rogers purchased the farm for four years from long term owners who had run a small deer farm. Since purchase the land has been retired from deer and managed for beef finishing and cropping for silage. Apart from fencing, gates, and a system of electric fences, other structures on site include a small farmhouse, several storage sheds, and feed storage tank. These are grouped near the highway, mid site.
- 4.5 The main farm road extends due north/west and continues along the centre farm ridge to eventually descend and provide a link to a portion of the farm on the river terrace on the far side of the railway line. The land includes approximately 7.5ha area and is primarily used for cropping.
- 4.6 The proposal area lies on the south/east side of the railway line and includes approximately 87% of the farm. The proposal area varies between 585m to 650m depth from Allanton-Waihola Road and has a road boundary of approximately 0.95km. The farm meets a strip of commercial activity, a horse grazing paddock, and Allanton Cemetery on its north/east boundary and farmland to the south/west. The western side of Center Road, to the north/east has provision for a future slip lane, which forms part of this proposal.
- 4.7 A short river terrace area on the upper north/west boundary and the existence of a wetland in the south/west farm margins reflect the influence of the Taieri River. However, the form and landscape structure of the majority of the proposal area reflect the influence of the northern slopes of the coastal hills that rise above the site and the highway to the south/east (Fig.1).
- 4.8 Three broad ridges extend from the lower slopes run out across the highway route and site, to terminate at the edge of the river terraces and divide the farm into two catchments, south/west and north/east. The ridges extend from the highway to mid site at more or less the same height. At this point the south/west and mid farm ridgelines gradually increase in height and width to form small headland areas that can be seen from Centre and Allanton-Waihola Road.
- 4.9 Conifer shelter belts extend from the road boundary until mid-point and restrict views to the separate catchments for passing motorists. This screening then ends and the experience on the headland ridges is of an open landscape that provides strategic views across the inner farm and river terrace areas.
- 4.10 The north/east catchment area contains several small but pronounced sub-ridges that divide the inner catchment land into areas of ridge, slope, and narrow semi-dry riparian drain channels. These are now fenced and discharge to a stream that runs out to the Taieri River along western end of a river meadow terrace that marks the river along the northern site boundary.
- 4.11 The south/west catchment has discharges to a wetland which in turn discharges to the Taieri River on the other side of the railway line. The wetland area extends approximately 330m back from the railway and widens to approximately 150m wide at its boundary with the inner catchment. Wetland

1. Introduction

- 1.1 This landscape report has been commissioned by Ms. Emma Peters, Sweep Consultancy Ltd, on behalf of Mr. Paul Rogers, owner of Roseberry Farm. Mr. Rogers is seeking to amend the zoning on his property at 744 Allanton-Waihola Road, Allanton, and to change it from Taieri Plain Rural to Township and Settlement and Large Lot Residential 1 under the Variation Two Plan Change to the Proposed Second-Generation Dunedin City District Plan. The balance of land will be used for planting, wetland enhancement, and stormwater mitigation and remain Taieri Plain Rural.
- 1.2 The report contains the following sections:
 - Methodology and Scope;
 - Site description;
 - Proposal;
 - Mitigation measures;
 - Landscape and visual effects; and
 - Discussion and conclusions.

2. Methodology and Scope

- 2.1 A site visit was made to the site with Ms. Peters and Mr. Rogers on February 15th, 2020. Subsequent visits were made to the site and its public boundaries to assess present landscape structure, the relationship of the site to surrounding land areas, and potential landscape and visual effects.
- 2.2 Where an assessment of effect is provided the New Zealand Landscape Architects seven-point scale is used: 'negligible/ very low/ low/moderate/ high/ very high/ extreme'. The application of this scale follows the Queenstown Lakes District Council Environment Court advisory note. The assessment scales for landscape and visual effects are attached as Appendix One.
- 2.3 A detailed assessment against the policies and objective of the 'Proposed Second-Generation Dunedin City District Plan' ('2GP') is not included and will be undertaken as is required by subsequent process.

3.0 Summary of Findings

- 3.1 This zone change would provide for residential development on the current farmland within an ecological and recreational living framework that will enhance present riparian patterns, restore wetland biodiversity and ecological value, and add return significant areas of native vegetation to the site. The development activity and associated mitigation measures will remove the potential for adverse environment effects from farm runoff to the Taieri River catchment.
- 3.2 The potential short term adverse landscape effects are assessed as being 'moderate-high'. The medium and long-term adverse landscape effects are assessed as being 'moderate-low'. The potential short term adverse visual effects are assessed as being 'moderate-high'. The medium- and long-term adverse landscape effects are assessed as being 'moderate-low'.

4.0 Site Description

4.1 The site is part of a 60.5473ha pastoral farm that lies approximately 22km from Central Dunedin and immediately west of Allanton Village and Centre Road, which links to Momona Airport. The land is aligned north/east to south/west and extends bounds Allanton-Waihola Road (SH1) (Fig.1).



Riverview

Proposed Rezoning and Residential Development 774 ALLANTON-WAIHOLA ROAD, ALLANTON








Vpt. 11 - Wetland



Vpt. 13. River meadow - North/East catchment



Vpt. 12. - Riparian gully - North/East catchment




View south/east to highway and Coastal Hill Range - 5m to bpundary fence - stitched image - no fixed focal length







03 March 2021 SITP. 774 Allanton-Waihola Road - Viewpoint 8 - Mid South boundary

7











5m to bpundary fence - 50mm focal length/full frame camera










774 Allanton-Waihola Road - Viewpoint 3 - Centre Road








0.75 km to Mid Ridge - 50mm focal length/full frame camera





0.76 km to Mid Ridge Healand - 50mm focal length/full frame camera



774 Allanton-Waihola Road - Viewpoint 1 - Mid Taieri Bridge



other non-residential activities if required, including cafe and retail

Residential Areas

10.

Walking/cycling/running track (approx 7km) Siding area for future passenger train stop

Main site collector road

Walking track (approx 2.5km)

Retail and Work/Life Infrastructure

subdivision

Existing rural machinery sales yard

Site Features

Slip way for new site access

Access

Fownship and settlement - 500m² - 1000m² lots

South-west mid site slopes:

Area: 3.1 ha

Potential yield: 48 lots

fownship and settlement - 450m2 lots

South-west ridges and gullies:

11

Area: 9.9 ha

Potential yield: 139 - 70 lots

Potential yield: 10 lots

Area: 1.5 ha

Township and settlement - 1000m2 lots

North-east plateau:

13.

Area: 9.9 ha

Area: 11.6 ha Potential yield: 41 lots

Large Lot Residential 1 - 2000m2 lots

Riverside ridges and headlands:

Riparian, Stormwater and Structure Planting

Potential yield: 154 - 92 lots

housing development/residential care

774 Allanton-Waihola

Native amenity mix - subcanopy and canopy trees

19.

height) and small trees

16.

Liriodendron, Liquid Amber)

DATE: 22-02-21 SCALE @A3: 1:5000

DWG: 003









774 Allanton-Waihola


DATE: 22-02-21 SCALE @A3: 1:5000 DWG: 002 REVISION #:





Waterways









access into this site will be required, given the large number of proposed lots. We note that Mr Bowen and Ms Peters suggested that to address this a connection could be provided along the paper road end of Abbotts Hill Road. However, there was limited cost or feasibility evidence presented for this option and we are not convinced that the proposed Abbotts Hill Road formation is feasible.

- 270. We consider it possible that a significantly smaller area of rezoning may have fewer transportation issues. However, we heard no specific expert evidence to support that conclusion The only expert transportation evidence we had before us urged us to be cautious about the transportation effects of rezoning any of this land.
- 271. At a more strategic level, we consider the proposed upgrade to Abbotts Hill Road of the scale proposed would be a significant undertaking and would have broad public interest. In our view this would take the rezoning requests outside of the ambit of an 'easy wins' variation as there may be much higher level effects on the broader community that have not been considered, and natural justice requires that an open process is followed. We consider that proposals of this scale are more appropriately considered through a Future Development Strategy (FDS) if this area were to be considered as being required for future growth.
- 272. We agree with the evidence from Mr Paterson, that rezoning 42A Lambert Street is not supported by the available evidence on hazards. Rezoning an area with a high natural hazards assessment is contrary to Policy 2.6.2.1.d.viii. For the other areas of the RS14 site, we accept Mr Paterson's evidence that these can be supported from a hazards perspective.
- 273. We adopt the evidence from Mr Oliver and Mr Saunders that significant water supply upgrades would be required to service this area, and that pumping would be required, which is contrary to DCC's goals of reducing the carbon footprint of the 3 waters network. We also agree with Mr Oliver and Mr Saunders regarding stormwater flooding risk, and their ongoing concerns relating to development in the high hazard area of the Mt Grand Raw Water Reservoir Flood Area. We accept the evidence of Mr Oliver and Mr Saunders that rezoning the site, both in part and as a whole, is not supported from a 3 Waters perspective.
- 274. With respect to rural productivity and the cumulative loss of productive rural land, which was a broad issue raised by Mr Miller and discussed in section 2.2.6, we note the NPS-HPL requires much greater attention to this issue, and we discuss this in section 3. This has not materially changed our decision with respect to the rezoning of this site however.
- 275. With respect to Ms Peters' proposal to apply an RTZ to part of 188 North Taieri Road, we understand that further investigations into hazards matters is not something that an RTZ can be used for, and further given that we find the site inappropriate for rezoning, an RTZ is inappropriate.
- 276. Overall, it is our view that the site, both as a whole and also in its various parts, does not satisfy or align well with the criteria outlined in Policy 2.6.2.1 and is therefore not appropriate to rezone to residential as part of this process.

2.3.2 Allanton

2.3.2.1 Part 774 Allanton - Waihola Rd, Allanton (RS195)

277. This section addresses the submissions covered in section 5.4.18 of the section 42A report.

- 278. RS195 is a 55.2ha site, currently zoned Rural Taieri Plain and surrounded by other Rural-zoned land (both Taieri Plain and Coastal). The site is located close to, but does not directly adjoin, Allanton Township and Settlement zoning, to the north of SH1. A small area of the site to the north is covered by a Hazard 1A (flood) Overlay Zone, and there are several areas of the site that are subject to a Hazard 1 (flood) Overlay Zone. A small part of the site lies within the Lower Taieri Flood Protection Scheme. The majority of the site lies within the Dunedin Airport Flight Fan.
- 279. The section 42A report notes the site was rejected in the section 32 report because some parts of the site were identified as being at high risk of flooding (and are subject to a Hazard 1 Overlay), In addition, there is existing residential capacity in Allanton, and rezoning would not support the compact form/city policies. The site also ranked poorly in relation to likely carbon emissions derived from commuting.

2.3.2.1.1 Submissions received

- 280. DDS Properties (2008) Limited (S242.001) sought to rezone the majority of the site to Township and Settlement Zone, with a smaller area of Large Lot Residential 1 and to apply a structure plan mapped area rather than a new development mapped area. A draft structure plan for the site was supplied with the submission along with a landscape assessment with approximately 245 376 dwellings. Residential activity is intended for the ridge areas, outside of the Hazard 1 (flood) Overlay Zone.
- 281. The *ORC (FS184.59) and others* opposed the rezoning due to concerns about the natural hazard risk and stormwater and wastewater management.
- 282. Susan Alanna Browne (FS233.1) and others opposed rezoning due to concerns about loss of productive land, biodiversity and rural character and amenity, including impacts on privacy and quality of life, effects on 3 waters infrastructure and existing services, increased traffic congestion and disruption from development adjacent to their existing property.

2.3.2.1.2 Submitters response to the section 42A recommendations

283. Mr Paul Rogers, a Director for DDS Properties Limited, outlined his vision for the site at the hearing. This included around 9km cycling/walking tracks through native plantings, a potential extension to the rail corridor alongside the Taieri River, low light emission/pollution through strategic placement of street lighting, a common building overlooking wetlands offering work from home office spaces and hot desks and the possibility for a small café and native plantings throughout the development. He noted that his proposal would encourage entry level housing for younger people, families and older people as he noted that locals wanted to stay in the area, but housing is limited.

2.3.2.1.3 Landscape, rural character and biodiversity

- 284. Some further submitters opposed the development due to loss of biodiversity and rural character and amenity, including impacts on privacy and quality of life.
- 285. Mr Hugh Forsyth, landscape architect for *DDS Properties (2008) Limited*, in evidence considered that rezoning would lead to a positive change of character over the medium term, given the extent of proposed planting, wetland and riparian protection and enhancement. He considered a general change from mostly open rural pastoral landscape to a rural/residential character of development and vegetation that would continue to develop and further define the eventual character of this landscape. He assessed the visible

- effect as 'moderate-high' in the short term and 'moderate-low' in the medium to long term on the basis of present public site visibility from SH1, as visibility effects will be reduced as the project develops.
- 286. In response, Mr McKinlay (DCC Landscape Architect) considered that while the visual change in character would be pronounced, the perception of this change would be largely restricted to the immediate surrounding area, including the approaches to the site on SH1. Overall, he considered the proposed rezoning would adversely affect existing rural character values to at least a moderate extent.

2.3.2.1.4 Transport

- 287. Several further submitters opposed rezoning due to concerns about increased traffic congestion.
- 288. Ms Peters, appearing for *DDS Properties (2008) Limited*, in her planning evidence considered the roads were capable of absorbing the additional traffic volume resulting from development. In a memorandum appended at Appendix 5 of Ms Peter's evidence, Mr Grant Fisher of Modal Consulting Limited provided preliminary design parameters for the intersection of the site road with SH1.
- 289. Ms Peters noted that any transport infrastructure upgrades, such as to the slip lane into the site from Centre Road and roading and pedestrian and cycleways within the site would be paid for by the developer, with the roading infrastructure vested with the Dunedin City Council.
- 290. Mr Paul Rogers noted that he had discussed the potential for rail connectivity with the site with NZ Rail. We queried Mr Rogers about the timing for any potential rail connectivity and he acknowledged discussions were in their early stages.
- 291. Mr Watson, for DCC Transport, said he did not support rezoning R195. He considered the site is in an unsustainable location from a traffic point of view and discussion of any potential rail access is in its early stages. If the site were to be developed, access via a roundabout would likely be required. This would require discussion with and agreement from *Waka Kotahi*.
- 292. In response to a request for further information, Mr Fisher considered that Waka Kotahi's concerns in relation to the safety and efficiency of access to RS195 could be addressed through appropriate intersection controls at the intersections of SH1/SH86 and SH1/Grey Street. This could be dealt with via a performance standard attached to the structure plan requiring either affected party consent from Waka Kotahi at the time of subdivision, or in the absence of affected party consent being provided, that Waka Kotahi receives limited notification of an application for subdivision.

2.3.2.1.5 3 waters

- 293. Several submitters opposed rezoning due to concerns about 3 waters infrastructure.
- 294. Ms Peters noted that the areas proposed to be zoned Large Lot Residential could be self-serviced with respect to wastewater. For the Township and Settlement zone she noted that treated wastewater could be discharged to a constructed wetland within the site, located out of any mapped flood hazard area, or be pumped via the existing reticulated wastewater system in Allanton, with the ability for the treated wastewater to be held to be pumped at

off-peak times. She noted that Allanton is self-serviced with respect to potable water, and she considered this is a feasible solution for this development. Stormwater would be detained from roof surfaces to tank for use as potable water. Overflow from tanks and stormwater from impermeable surfaces would be attenuated as shown in the structure plan. She anticipated that performance standards attached to the structure plan would require a stormwater management plan be provided at the time of subdivision.

- 295. DCC 3 Waters, through the evidence of Mr Saunders and Mr Oliver, considered RS195 a risky site from a 3 Waters perspective. Allanton is self-serviced for potable water but there are concerns about the adequacy of the water supply. Additionally, DCC 3 Waters considered that the submitter's proposal did not provide for water capacity for firefighting. Wastewater and stormwater servicing could be expensive and technically challenging. If wastewater disposal occurs on-site, a large area may be required, and if it is conveyed using the existing reticulated system, the rising main to the Mosgiel Wastewater Treatment Plan (WWTP) may not have capacity for the additional volumes. It also noted there is no stormwater network in the area, the site is adjacent to the Taieri River, and parts of the site are in a Hazard 1 (flood) Overlay Zone which require further investigation.
- 296. In his Reply Report, Mr Morrissey further outlined the 3 Water servicing situation in Allanton. Based on advice from 3 Waters, he noted that wastewater is serviced by a pressure sewer scheme, which requires a pumping unit installed at each property, which is pumped into the pressure sewer network to the Mosgiel WWTP. He noted there is some capacity in this scheme for additional flows. There is no 3 waters stormwater network in Allanton, and stormwater flows through open channel drains alongside roads and through culverts under roads, generally in a northwest direction, under the railway line to the Taieri River.

2.3.2.1.6 Hazards

- 297. Several submitters opposed rezoning due to concerns about flooding.
- 298. Mr Morrissey in the section 42A report considered there may be a high risk from flooding, as evidenced by the Hazard 1 (flood) Overlay Zone over large parts of the site. Residential development is a non-complying activity within this overlay. There is also a small area to the north of the site, adjacent to the Taieri River, which is covered by a Hazard 1A (flood) Overlay Zone. Residential development is a prohibited activity in a Hazard 1A (flood) Overlay Zone.
- 299. In her evidence, Ms Peters noted that no development is proposed in the Hazard 1A Overlay Zone.
- 300. In a geotechnical assessment for the *DDS Properties (2008) Limited,* Mr Mark Walrond of Geosolve considered there were no significant problems with developing the site for residential use. He also considered that the risk from the flood hazard had been addressed and that further detailed work would be provided at the time of subdivision.
- 301. In his response, Mr Paterson from Stantec noted that he had not previously reviewed this site. However, he had reviewed the nearby site RS200, which has similar geology and constraints. He noted RS195 is closer to the Taieri River and parts of the site are threatened by flood risk. The primary natural hazards on the site include flood, liquefaction and land stability. In general, Mr Paterson considered Mr Walrond's report adequately addressed the natural hazards on the site and agreed that the site is generally suitable for rezoning from a hazards perspective. Ms Paterson considered that, as with most sites, the structure of the subdivision and any future earthworks would likely be governed by the hazards present on

- the site. Management of overland flows and restrictions on slope angles, retaining features and earthworks would be required.
- 302. Mr Payan, Manager Natural Hazards at the Otago Regional Council, appeared at the hearing for the DCC and outlined the flood hazards affecting the broad Taieri Plain area. He provided information on the flood hazard mapping approach taken by the Otago Regional Council, the different flood hazard areas present on the Taieri Plain, and the potential impacts of climate change on extreme weather events. While his evidence covered the broader Taieri Plain and was not specific to this site, it provided useful information relating to the broad flooding hazards present on the Taieri Plain, including Allanton.

2.3.2.1.7 Compact city objectives and assessment against Policy 2.6.2.1

- 303. The section 42A report noted the site is distant from centres and facilities, requiring a significant commute for many, with limited public transport options. Mr Morrissey considered rezoning relatively remote pockets of land conflicts with Policy 2.6.2.1.d.xi, which requires that Dunedin stays a compact and accessible city. In his view, rezoning the site would result in inefficient and ineffective public infrastructure as network expansion would be required.
- 304. Ms Peters noted that the Outram Rural Centre Zone is approximately 8km away, and the Neighbourhood Convenience Centre Zone and Principle Centre Zone at Mosgiel are approximately 8.5 9.3km away. She noted that the site would include a retail / commercial area that would operate as a centre. She commented that people living in Allanton may commute to jobs in other locations south of Allanton, such as to the correctional facility and existing industrial activities at Milburn, to the Dunedin City Airport, or to nearby farming and forestry activities. Additionally, Ms Peters noted that, given the site's proximity to State Highway 1 and the gradient of the highway between Allanton and Dunedin and Allanton and Milburn, RS195 is well suited to commuting via electric vehicle.
- 305. In his Reply Report, Mr Morrisey noted that if the rezoning was to occur, associated commercial development as proposed to service the area, could lead to an area of Allanton becoming a 'Rural Centre Zone'. That is a realistic outcome and would not be within scope or intent of Variation 2.
- 306. We have addressed Ms Christmas' comments relating to resilient townships in section 2.1.2.4 of our decision.

2.3.2.1.8 Demand for Residential zoned land in Allanton

- 307. The section 42A report notes there is no evidence that Allanton requires additional development capacity on the scale proposed by this development.
- 308. At the hearing, Ms Peters noted that the DCC had not undertaken any data based assessment of the zone capacity within Allanton or other townships, despite these townships being crucial to the rural areas which dominate the area serviced by the Dunedin City District Plan. She considered there is an accepted difference between 'zoned capacity' and the 'market availability' of that capacity and referenced a letter from Mr Paul Thomson, a real estate agent at PGG Wrightson Real Estate, about the shortage of residential sections in the greater Dunedin and Taieri areas. Ms Peters argued there is a clear demand for more residential zoned land to be made available to the market in Allanton. Mr Thomson appeared at the hearing in support of his evidence.

309. Mr Morrissey, in his Reply Report, advised that assessing the need for additional development capacity in Allanton would most appropriately be considered as part of the Future Development Strategy process. We note Mr Stocker provided further information relating to housing capacity, including in relation to Allanton in his Memorandum on Residential Housing Capacity (dated 31 August 2022). He also addressed the 'theoretical capacity' issue noting that the modelling work had in fact made realistic assumptions about realistic development capacity of land to be rezoned. Our comments on the methodology for assessing capacity in townships and settlements is discussed in section 2.1.1 of this decision.

2.3.2.1.9 Rural productivity

- 310. We note that part way through out deliberations the National Policy Statement for Highly Productive Land (NPS-HPL) was released and came into effect. Mr Morrissey, in his response to Minute 15, 16, 17 from the Panel dated 6 October 2022, advised that 98% of this site meets the interim criteria for Highly Productive Land.
- 311. Due to the timing of the NPS-HPL, and for the sake of clarity, we have chosen to undertake an analysis of the NPS as a separate part of our decision and to focus on whether the consideration of it changes any of our conclusions and decisions. This analysis is given in section 3 of this decision. We note that the analysis in that section has not materially changed our overall decision on the rezoning of this site.

2.3.2.1.10 Reporting Officer's recommendation

- 312. The section 42A report notes that rezoning this site to residential has clear conflicts with Policy 2.6.2.1. Mr Morrissey considered that the site was currently unsuitable for residential rezoning and recommended that the site remain zoned as Rural Taieri Plain.
- 313. In his Reply Report, Mr Morrissey maintained his recommendation not to rezone the site, as it is distant from public transport, centres and facilities and there is a lack of evidence in relation to what is required to achieve a resilient township. There are also potential issues in relation to wastewater servicing, concerns about the ability to manage stormwater, and the site being partly located on a Flood 1A Hazard overlay. While houses are not proposed for these areas, the flood hazard may affect accessibility during times of flooding.
- 314. He considered that the need for additional development capacity in Allanton should most appropriately be considered through the Future Development Strategy and that the most appropriate location and overall design of access, (particularly in relation to access to SH1), be considered as part of the Future Development Strategy.

2.3.2.1.11 Decision and reasons

315. We reject *DDS Properties (2008) Limited's* submission to rezone the majority of RS195 to Township and Settlement Zone, with a smaller area of Large Lot Residential 1, for reasons relating to compact city, carbon emissions, access and flood hazard. We adopt the evidence of Mr Watson (DCC Transport) and Mr Saunders (DCC 3 Waters) that the site is not 'infrastructure ready'. We are unable to place any weight on a potential rail connection due to the very early stage of any discussions with Kiwi Rail. We are also concerned about the cumulative loss of productive rural land, particularly on the Taieri, which was a broad issue raised by Mr Miller and discussed in section 2.2.6. We note the new policy direction in the NPS-HPL requires much greater attention to that issue as discussed in section 3.

- 316. We were overall quite impressed with Mr Rogers' vision for the land, and the evidence of Mr Forsyth demonstrated that the proposed development is well-integrated internally in terms of cycleways, reserves and proposed amenities. However we consider that rezoning RS195 would be a substantial expansion of the Allanton settlement and agree with Mr Morrissey this should be more appropriately considered through the Future Development Strategy process rather than the much more limited scope of Variation 2.
- 317. There are many other factors that need to be considered with a development of this scale, including consultation with Waka Kotahi in relation to access onto SH1, whether centre zoning should be provided, and whether additional development capacity is needed in this location to service the Taieri Plain and areas to the south.
- 318. We consider that access to the site is paramount, as SH1 is a Limited Access Road in this location with open road speed limits in the vicinity. We take no comfort in Mr Fisher's recommendation that a structure plan can be conditioned to require Waka Kotahi's approval prior to development. We consider this is an issue that very much needed to be resolved prior to this rezoning request being made, especially as the rezoning would enable a substantial number of new dwellings on this land. We note that Waka Kotahi (\$235.008) also made a wider submission that has relevance to this site, that rules are added to greenfield rezoning areas adjacent to a state highway to require that access is achieved from roads other than a state highway.
- 319. Consequently, we accept the further submissions from *Susan Alanna Browne (FS233.1) and others* who opposed Change RS195 due to a range of concerns.

2.3.2.2 489 East Taieri-Allanton Road, Allanton (RS200)

- 320. This section addresses the submissions covered in section 5.4.19 of the section 42A report.
- 321. RS200 is located immediately adjacent to the eastern edge of Allanton, alongside and to the south of State Highway 1. It is located below and outside of the Saddle Hill Significant Natural Landscape Overlay Zone (SNL). A Hazard 3 (alluvial fan) Overlay Zone covers part of the site. The site is currently zoned Rural Coastal but adjoins Allanton (zoned Township and Settlement). The section 32 report states that that the site was rejected as there is existing capacity in Allanton, rezoning would not support the compact form/city policies, and parts of the site are very steep. The area proposed for rezoning is only part of the site originally assessed, and encompasses the lower, more gently sloping parts of the site.

2.3.2.2.1 Submissions received

- 322. Meats of New Zealand Limited (\$232.001) sought to rezone the site to a mixture of Township and Settlement and Large Lot Residential 1 with a structure plan mapped area over the site, rather than an NDMA. A draft structure plan provided with the submission identifies access to the site via Ralston Street (at the corner of Allanton-Scroggs Hill Road), the location of residential areas, two conservation and enhancement areas totalling 27ha in area, and a parkland /recreation area to be planted with exotic canopy trees. The proposed area of Township and Settlement zoning has a development capacity of approximately 41–61 sections, and a separate proposed Large Lot Residential 1 zoned area (minimum site size 2,000m²) would have capacity for approximately eight sections.
- 323. A number of further submitters opposed the submission from *Meats of New Zealand Limited*. *Kathryn Anne Simpson (FS132.1), Malcolm Joseph and Sharon Roslyn Thomson*