

Appendix 6: Geotechnical Factual Report



Dunedin City Council

Waste Futures Phase 2, Workstream 3 Smooth Hill Landfill Smooth Hill Consenting - Geotechnical Factual Report



August 2020 [\(updated May 2021\)](#)

Table of contents

1.	Introduction	3
1.1	Project background	3
1.2	Project Overview.....	4
1.3	Scope of geotechnical investigation	5
2.	Site Setting.....	6
2.1	Site description	6
2.2	Local geology.....	7
2.3	Historic mining	9
2.4	Previous investigations	10
3.	Summary of Investigations.....	11
3.1	General	11
3.2	Machine boreholes.....	11
3.3	Piezometers	13
3.4	Test pits	13
3.5	Bulk samples.....	14
3.6	Groundwater	15
3.7	Investigation coordinates	15
3.8	Laboratory testing	17
4.	References.....	22
5.	Limitations	23

Table index

Table 1	Summary of known faults	9
Table 2	Summary of machine boreholes	12
Table 3	Summary of piezometer details.....	13
Table 4	Test pit summary	14
Table 5	Bulk sample summary	15
Table 6	Summary of test location positions	16
Table 7	Summary of geotechnical laboratory testing	17
Table 8	Summary of geotechnical laboratory testing for stabilised soils.	18
Table 9	Summary of geotechnical laboratory testing for engineered fill	18
Table 10	Summary of particle size distribution test results (NZS 4402:1986, Test 2.8.1 and 2.8.4)	19
Table 11	Summary of Atterberg limit test results (NZS 4402:1986, Test 2.1, 2.2, 2.3 and 2.4)	19

Table 12 Summary of NZ standard compaction test results (NZS 4402:1986, Test 2.1 and 4.1.1)	19
Table 13 Summary of pinhole dispersion test results (ASTM D4647-13e1)	19
Table 14 Summary of crumb test results (ASTM D6572-13e2 (Method B))	20
Table 15 Summary of triaxial permeability test results (ASTM D5084-16a)	20
Table 16 Summary of Atterberg limit test results (Natural Soils)	20
Table 17 Summary of lime demand test results.....	21
Table 18 Summary of Atterberg limit test results (Henley Breccia Formation)	21
Table 19 Summary of NZ standard compaction test results (Henley Breccia Formation)	21
Table 20 Summary of unconfined compressive strength of re-compacted samples (Henley Breccia Formation).....	21

Figure index

Figure 1 Site location (Updated May 2021).....	3
Figure 2 Site Environs (Updated May 2021)	5
Figure 3 Proposed landfill site (base image sourced from Google Maps) (Updated May 2021)	6
Figure 4 Excerpt from 1:50,000 Geology of the Milton Area (Bishop, 1994)	7

Appendices

- Appendix A – Plans
- Appendix B – Borehole and Test Pit Logs and Photographs
- Appendix C – Laboratory Testing Results

1. Introduction

1.1 Project background

The Dunedin City Council (Council) collects residential waste and manages the disposal of both residential and [most](#) commercial waste [generated from](#) the Dunedin City area and environs.

The Council has embarked on the Waste Futures Project to develop an improved comprehensive waste management and diverted material system for Dunedin, including future kerbside collection and waste disposal options. As part of the project, the Council has confirmed the need to develop a new landfill to replace the Council's current Green Island Landfill, which is [envisaged to reach full capacity in the next few years. Final closure could be around 2028 depending on the closure strategy adopted by the Council. ~~likely to come to the end of its functional life sometime between 2023 and 2028.~~](#)

The Council commenced [siting studies](#) for a new landfill location in the late 1980's and early 1990's and selected the Smooth Hill site in south-west Dunedin, shown in Figure 1 below, as the preferred [location](#). At that time, the site was designated in the Dunedin District Plan, signalling and enabling its future use as a landfill site. The Council also secured an agreement with the [then current](#) landowner, Fulton Hogan Ltd, to purchase the land [and the Council took ownership of the land in September 2020. Since the 1990's the](#) Council extended the life of Green Island Landfill and further development of the Smooth Hill site has been on hold.

Figure 1 Site location [\(Updated May 2021\)](#)



As part of the Waste Future's Project, the Council has reconfirmed the technical suitability of Smooth Hill for the disposal of waste ~~and. The Council has~~ proceeded to develop a concept design for the landfill and associated road upgrades. The concept design (the subject of this report) for the landfill has been developed by GHD Ltd (GHD) with technical input from Boffa Miskell and represents contemporary good practice landfill design that meets adopted New Zealand landfill design standards.

The Council lodged applications for resource consents for Smooth Hill landfill with both the Otago Regional Council and Dunedin City Council in August 2020. The applications included an earlier version of this report. This report has now been revised to reflect both the changes in the design and in response to s92 questions.

While being similar in many ways to the previous design, the key changes are summarised as follows:

- The landfill size has been reduced. The revised landfill lies within the footprint of Stage 1 and Stage 2 of the original design, with the western Stages 3, 4 and 5 no longer included (for comparison see Drawings 12506381-01-C102 and C104). In overall terms:
 - the footprint of the landfill is reduced from 44.5 ha to 18.6 ha
 - landfill (gross) capacity is reduced from approximately 7.9-million m³ to 3.3-million m³
 - net waste capacity is reduced from 6.2-million m³ to 2.9-million m³
 - the predicted landfill life has reduced from 55-years to 40-years
- Practical adjustments to the general construction of the landfill, including:
 - Landfill staging and construction sequencing, to a more typical 'bottom-up' filling methodology, which improves the intermediate and overall landform stability of the new design (Drawing 12506381-01-C210 to C214)
 - Leachate containment and collection systems adjusted to reflect the revised construction sequencing
 - Construction phase systems for stormwater diversion, treatment and control
 - Relocation of the attenuation basin to the west of the revised landfill footprint rather than immediately downstream of the landfill toe.


1.2 Project Overview

The proposal includes the following key components:

- ~~The staged construction, operation, and aftercare of a Class 1 landfill within the existing designated site to accept municipal solid waste. The landfill will have a capacity of approximately 6 million cubic metres (equivalent to 5 million tonnes), and expected life (at current Dunedin disposal rates) of approximately 55 years.~~ The landfill will receive waste only from commercial waste companies or bulk loads.
- Infrastructure to safely collect, manage, and dispose of landfill leachate, gas, groundwater, and stormwater to avoid consequential adverse effects on the receiving environment.
- Facilities supporting the operation of the landfill, including staff and maintenance facilities.
- Environmental monitoring system~~ss~~.
- Landscape and ecological mitigation, including planting.
- Upgrades to McLaren Gully Road including its intersection with State Highway 1, and Big Stone Road, to facilitate vehicle access to the site.

The proposed Smooth Hill landfill site is located approximately 23 km southwest of Dunedin City. The boundary of the proposed site is shown in Figure 2. The waste facility itself will operate within these boundaries.

Figure 2 Site Environs (Updated May 2021)



1.3 Scope of geotechnical investigation

This report presents the factual results of the geotechnical investigation along with published and Client supplied geotechnical data related to the proposed waste site development. The purpose of the investigation was to assess the subsurface geotechnical and hydrogeological conditions at the proposed Smooth Hill landfill site. The hydrogeology is reported separately.

This information in this report has been used to inform and support the landfill design and the Assessment of Environmental Effects (AEE) and resource consent applications.

2. Site Setting

2.1 Site description

The proposed site is bordered by Big Stone Road along its southern boundary. Access from State Highway 1 (SH1) is currently via McLaren Gully Road. The proposed site is bounded to the north and west by forestry land, and to the northeast by farmland. Figure 3 provides a closer view of the proposed site.



Figure 3 Proposed landfill site (base image sourced from Google Maps)
(Updated May 2021)

The proposed site is located in a south to north trending gully, which is fed by smaller gullies from the east, west and south. The flow direction for water exiting the gully is from the south to the north. The slopes around the southern half of the site form a natural “amphitheatre” shape, which is bisected by a larger central ridge, and a smaller ridge in the south-western corner – both trending south to north.

The site was, until recently, covered by a Radiata Pine plantation, the site cover is now a mixture of scrub, bare earth, forestry waste and replanted pine. A number of existing forestry tracks provide access around the site.

The ground is typically wet and boggy in the base of the gullies where there is standing or seeping water.

2.2 Local geology

2.2.1 Published geology

A review of the available geological maps (Bishop [1994], and Bishop and Turnbull [1996]) covering the site shows that the main lithology expected to be encountered is the Henley Breccia unit. Although not shown on the geological map, it is expected that the Henley Breccia unit is overlain by several metres of loess deposits, and locally by alluvium and colluvium.

Figure 4 presents an excerpt from the Bishop (1994) geological map.




Figure 4 Excerpt from 1:50,000 Geology of the Milton Area (Bishop, 1994)

2.2.2 Expected lithologies

The basement rock in the proposed site area is expected to be Caples Terrane schist, textural zone IIIA (map symbol *IIIA*), which comprises well foliated quartzofeldspathic schist with prominent quartz veins. The schist was metamorphosed in the Jurassic period, and the metamorphic grade (textural zone) increases northward.

The schist basement is overlain unconformably by the Upper Cretaceous Henley Breccia (map symbol *he*) – a terrestrial sequence of piedmont breccias and conglomerates up to 1000 m thick. The breccia was derived from a high-standing schist block immediately west of the present-day Titri Fault. Henley Breccia was tilted before the formation of the Otago peneplain, which was cut across both it and the schist basement prior to the deposition of a relatively thin set of transgressive Upper Cretaceous to Tertiary terrestrial and shallow marine sediments (Bishop & Turnbull, 1996).

Taratu Formation (map symbol *ta*) is mapped as outcropping along the tops of several ridgelines to the south and east of the site, [but not on this site](#). The Taratu Formation unconformably overlies the Henley Breccia and comprises yellow quartz sand and pebble conglomerate, with minor clay, carbonaceous siltstone and lignite, and limonite and silica cemented quartz conglomerate.

Bishop (1994), and Bishop & Turnbull (1996) have not mapped surficial materials such as loess, weathered bedrock or organic soils. However, the following description of loess soils in Otago is provided in Bishop & Turnbull (1996): *“In the Dunedin map area, such unmapped surficial materials are dominated by loess which, where remobilised, grades into loess colluvium... Loess forms a widespread blanket across most of eastern Otago, particularly near the coast... Loess typically forms a yellow-brown, massive layer or series of layers, mixed at the base with weathered bedrock and overlain by darker organic-rich soil. Columnar jointing and shrinkage cracks are common. Where loess mantles slopes, down-slope creep and alluvial processes have incorporated clasts of weathered underlying material, upslope material, and organic matter to form ‘loess colluvium’.”*

Loess deposits mantle much of the site, being present predominantly on the slopes and ridges of the site, with loess colluvium predominantly in the valley bases. The thickness of loess varies. In the bottom of the valleys, there is some alluvial material.

2.2.3 Nearby faults

There are a number of mapped faults in the Otago region. The known faults within close proximity to the landfill site are listed in Table 1. Fault data has been gathered from the GNS Active Faults Database website, and from Stirling, McVerry, et al (2012).

Active faults are defined by GNS and NZS 1170:2004 as faults with recurrence periods of less than 2000 years. On the basis of this definition the closest known active fault to the site is the Alpine Fault at a distance of approximately 240 km to the north-west, which is also classified as a ‘Major Fault’ by NZS 1170:2004.

Whilst the Alpine Fault is the closest “active fault” there has been recent research on the recurrence intervals of the Titri and Akatore faults. This new data will be included in the seismic hazard assessment of the site.

Table 1 Summary of known faults

Fault Name	Approximate Distance from Site	Maximum Likely Magnitude, M_w	Average Recurrence Interval (years)
Titri Fault*	3 km NW	unknown	unknown
Akatore Fault	6 km SE	7.4	3,480
Maungatua Fault	10 km NW	unknown	unknown
North Taieri Fault	13 km N	unknown	unknown
Hyde Fault	47 km NNW	7.2	12,810
Billy's Ridge Fault	47 km NNE	7.1	9,470
Taieri Ridge Fault	50 km NNE	7.1	9,750
Fault #8894 (GNS)	50 km SW	unknown	unknown
Tuapeka Fault	56 km NW	unknown	unknown
Clifton Fault	56 km SW	unknown	5,000 – 10,000
Logan Burn Fault	60 km NW	unknown	3,500 – 5,000
Blue Mountain Fault	70 km W	7.3	12,690
Long Valley Fault	75 km NW	6.8	2,810
Gimmerburn Fault Zone	76 km N	7.2	5,850
Old Man Fault	85 km NW	7.4	362,150
Spylaw Fault	89 km W	7.3	12,440
Alpine Fault	240 km NW	8.1	340
* - Stirling et al 2012			

2.3 Historic mining

Anecdotal evidence provided by a local resident indicates historic mining may have occurred in this area of Otago. A review of [publicly](#) available data with regard to historic mining has been carried out. The following sources were consulted:

- Regional geological maps (Benson [1968], McKellar [1990], Bishop [1994], and Bishop & Turnbull [1996])
- Historic aerial photographs, retrieved from the Retrolens historic imagery resource
- Mindat.org: www.mindat.org
- NZ Mine Plans website: <https://mineplans.nzpam.govt.nz>
- Appendices to the Journals of the House of Representatives, 1890 Session I, Section C: <https://atojs.natlib.govt.nz/cgi-bin/atojs?a=d&d=AJHR1890-I&e=10--1-0>

The sources consulted suggest that the geological unit containing a potential valuable commodity in this part of Otago is the Taratu Formation (also known as Taratu Coal Measure on older geological maps). The main commodity mined in the region appears to be coal/lignite. ~~In the vicinity of the proposed landfill, the Taratu Formation only occurs as a relatively thin layer at the top of the higher ridges on the eastern edge of the designation area and away from the proposed landfill footprint or appurtenant structures. Outcrops and boreholes associated with the Taratu Formation at the site do not show any lignite layers within these Taratu materials.~~ It is considered highly unlikely that mining would have occurred within the designation area.

The only known abstraction on the site is a small borrow pit associated with the Taratu Formation deposits on the eastern edge of the designation area. Fulton Hogan have used this as a borrow site for gravel used to form logging tracks in the site vicinity.

2.4 Previous investigations

GHD is not aware of any previous investigations at the proposed landfill site, though an existing piezometer was found adjacent to the north-eastern site entrance.

3. Summary of Investigations

3.1 General

GHD carried out two phases of geotechnical investigations between 27 May to 17 June 2019 (Phase I), and between 24 October to 7 November 2019 (Phase II). McNeill Drilling was the drilling subcontractor used for the first phase, and Speight Drilling Ltd was the drilling subcontractor used for the second phase. The investigations comprised machine boreholes and test pits. All investigation works were carried out under the supervision of a GHD Engineering Geologist.

The second phase of investigations was designed to address gaps in the ground model data that were identified following the end of the first phase. Due to restrictions in place for the second phase (surveys of protected native lizards, and nesting native falcons), there were areas that could not be accessed for investigation and as a consequence a number of planned borehole and test pits were either re-located or not completed. [These areas have since been excluded from the re-designed landfill footprint and therefore the requirement to undertake additional investigation in these areas is removed.](#)

[Shallow test pitting and sampling to confirm the distribution of loess and its properties will be part of the detailed design investigation, should a mineral liner be part of the liner system.](#)

Materials recovered from the investigation were logged following the methods and procedures in the New Zealand Geotechnical Society's (NZGS) "*Guideline for the Field Description of Soil and Rock for Engineering Purposes*" (2005).

Shear vane testing was undertaken in accordance with NZGS's "*Guideline for Hand Held Shear Vane Test*" (2001). The peak and remoulded shear strength values shown on the attached logs (Appendix B) represent dial readings off the vane, adjusted using the BS 1377 calibration.

An investigation location plan is provided in Appendix A.

3.1.1 [Logging Taratu Formation vs Henley Breccia](#)

[The Taratu Formation has not been previously mapped within the designated landfill area. It is known to occur along ridges south-east of the site. However, the presence of rounded quartz conglomerate in the recovered core on site was interpreted in early versions of this report as the presence of the Taratu Formation on the ridges at the site. Upon further review, it is uncertain if what had earlier been logged as Taratu is actually Taratu, or in fact part of the Henley Breccia. On the Dunedin South map, the Henley Breccia does refer to quartz conglomerates which would fit with the logged cores. Given that the geological map does not include Taratu Formation on the ridge tops in the vicinity of the site, this material has been re-classified as Henley Breccia.](#)

[Whilst of interest from a geological point of view, the geotechnical performance of the two units is very similar. For this reason, whether the unit is Taratu Formation or Henley Breccia is academic to the design of the landfill.](#)

3.2 Machine boreholes

McNeill Drilling drilled ten machine boreholes (BH01 to BH10) between 27 May and 16 June 2019, using a truck mounted UDR600 rig. Speight Drilling Ltd drilled five machine boreholes (BH201 to BH203, BH209 and BH211) between 24 October and 7 November 2019, using a tracked, Maruka-mounted rig.

All boreholes were drilled from ground surface, with no hand or hydro-excavation carried out.

Core samples were retrieved by rotary drilling methods using PQ (96 mm diameter) triple tube drilling. BH201 and BH202 were cored to approximately 10.0 m [below ground level \(bgl\)](#), and then wash drilled (no core recovered) to their termination depth.

Where practical, vane shear strengths were measured in the end of the core barrel with a hand held shear vane, using the techniques described in the NZGS guideline.

Table 2 summarises the details of the investigation machine boreholes. Borehole logs are provided in Appendix B.

[The target depth of the boreholes was set during the concept phase and designed to provide a broad understanding of the geology and the intended structure, such that a ground model could be developed. The target depth of the test pits was to establish the depth to rock.](#)

Table 2 Summary of machine boreholes

Test ID	Site Location	Commenced	Completed	Total Depth (m bgl)	Termination Reason	Piezometer
BH01	Attenuation Basin Foundation	6/06/2019	6/06/2019	15.0	Target Depth	Yes, x 2
BH02	Toe Bund Foundation	27/05/2019	28/05/2019	15.0	Target Depth	Yes, x 2
BH03	Toe Bund Foundation	28/05/2019	29/05/2019	20.0	Target Depth	Yes, x 2
BH04	Toe Bund Foundation	6/06/2019	7/06/2019	15.0	Target Depth	Yes, x 2
BH05	Central Ridge	29/05/2019	30/05/2019	30.0	Target Depth	Yes, x 2
BH06	Southwest Ridge	13/06/2019	14/06/2019	30.0	Target Depth	No
BH07	Central Ridge	30/05/2019	4/06/2019	20.0	Target Depth	Yes, x 2
BH08	Southeast Perimeter	11/06/2019	11/06/2019	20.0	Target Depth	No
BH09	Western Perimeter	12/06/2019	12/06/2019	16.5	Target Depth	Yes, x 1
BH10	Northeast Ridge	04/06/2019	05/06/2019	20.0	Target Depth	Yes, x 2
BH201	Southern Perimeter	28/10/2019	01/11/2019	61.0	Target Depth	Yes, x 1
BH202	Southern Perimeter	2/11/2019	4/11/2019	60.6	Target Depth	Yes, x 1
BH203	Southwest Perimeter	7/11/2019	7/11/2019	19.7	Target Depth	No
BH204	Western Ridge	Not completed				
BH209	Western Perimeter	24/10/2019	24/10/2019	10.0	Target Depth	No
BH210	Central gully base	Not completed				
BH211	Eastern Gully Base	4/11/2019	6/11/2019	25.2	Target Depth	Yes, x2

3.3 Piezometers

Piezometers were installed in selected boreholes to allow for permeability testing and follow-up groundwater measurements.

Groundwater was not encountered in BH06, BH08, BH203 or BH209 - therefore, no piezometers were installed.

Piezometers were typically nested, with two 32 mm PVC pipes installed in each borehole (except BH09, BH201 and BH202). The pipe was slotted over the targeted screened zone and surrounded by a coarse sand pack. Bentonite seals were placed above and below each screened zone. [For borehole logs where double piezometers are installed \(a and b\) these are presented as a single log showing the double piezometer installation.](#)

The piezometer details were provided by GHD hydrogeologists to suit the conditions encountered in each borehole. Table 3 summarises the piezometer details.

Table 3 Summary of piezometer details

Borehole ID	Piezometer ID	Screened From (m bgl)	Screened To (m bgl)
BH01	BH01a	2.0	4.0
	BH01b	8.0	9.0
BH02	BH02a	3.0	5.0
	BH02b	7.0	9.0
BH03	BH03a	8.3	10.3
	BH03b	13.0	15.0
BH04	BH04a	4.5	6.5
	BH04b	12.0	16.0
BH05	BH05a	14.0	16.0
	BH05b	19.0	22.0
BH07	BH07a	11.5	14.5
	BH07b	16.8	19.8
BH09	BH09a	14.5	16.5
BH10	BH10a	13.5	15.5
	BH10b	18.0	20.0
BH201	BH201	54.0	60.0
BH202	BH202	54.0	60.0
BH211	BH211a	8.5	11.5
	BH211b	22.0	25.0

3.4 Test pits

Under the supervision of GHD, Fulton Hogan excavated eleven test pits between 27 May 2019 and 12 June 2019, using a 22 tonne excavator.

Where practical and safe, vane shear strengths were measured in the base and sides of the excavation with a hand held shear vane, using the techniques described in the NZGS guideline.

Table 4 summarises the details of the test pits. Test pit logs are provided in Appendix B.

Table 4 Test pit summary

Test Pit ID	Site Location	Excavation Date	Termination Depth (m bgl)	Termination Reason	Materials Encountered
TP01	Manuka gully (stockpile area)	12/06/2019	2.5	Target Depth	Alluvium, HW rock, siltstone
TP02	Manuka gully (stockpile area)	12/06/2019	2.6	Target Depth	Colluvium, alluvium, buried topsoil, siltstone
TP03	Manuka gully (stockpile area)	12/06/2019	2.0	Target Depth	Alluvium, siltstone
TP05	Southwest gully base	13/06/2019	3.3	Target Depth	Colluvium, HW rock, siltstone
TP06	Gully east of central ridge	13/06/2019	2.5	Target Depth	Alluvium, siltstone
TP07	Southwest gully base	28/05/2019	2.5	Target Depth	Loess, siltstone, breccia
TP08	Gully between southern ridges	28/05/2019	4.5	End of reach	Fill, buried topsoil, loess
TP09	Southeast gully outflow	13/06/2019	3.0	Target Depth	Slip debris, buried topsoil, alluvium, sandstone
TP10	Future laydown area	10/06/2019	3.6	Target Depth	Loess, HW siltstone
TP11	Future laydown area	10/06/2019	3.8	Target Depth	Loess, HW siltstone
TP12	Future laydown area	10/06/2019	4.4	Target Depth	Fill, buried topsoil, loess, HW siltstone

*Note: TP04 was deleted from the field programme

3.5 Bulk samples

Bulk samples of loess and completely weathered (CW) rock were collected from shallow test pits on 7 and 13 November 2019. The shallow test pits were excavated by Fulton Hogan, with a 20 tonne excavator. The bulk sample details are summarised in Table 5.

Table 5 Bulk sample summary

Bulk Sample ID	Sample Date	Sample Depth	Sampled Material
BS01	7/11/2019	0.5 m bgl	Loess
BS02	7/11/2019	1.0 m bgl	Loess / CW rock
BS03	7/11/2019	0.7 m bgl	Loess
BS04	7/11/2019	1.5 m bgl	Loess / CW rock
BS05	13/11/2019	0.6 m bgl	Loess
BS06	13/11/2019	1.0 m bgl	Loess / CW rock
BS07	13/11/2019	0.5 m bgl	Loess
BS08	13/11/2019	0.6 m bgl	Loess
BS09	13/11/2019	1.2 m bgl	Loess / CW rock
BS10	13/11/2019	0.7 m bgl	Loess
BS11	13/11/2019	1.3 m bgl	Loess
BS12	13/11/2019	0.4 m bgl	Loess
BS13	13/11/2019	1.2 m bgl	Loess
BS14	13/11/2019	0.5 m bgl	Loess
BS15	13/11/2019	1.1 m bgl	Loess / CW rock

3.6 Groundwater

To monitor whether the groundwater had returned to a static level after drilling, manual groundwater measurements were taken on several occasions during the field investigation programme. This was because, groundwater levels noted during or immediately after drilling are typically in an elevated state due to the use of water during the drilling process, and therefore may not represent a static groundwater level. Groundwater levels may also fluctuate seasonally.

At the completion of drilling BH01, prior to piezometer installation, the drillers observed artesian groundwater, in that groundwater was flowing out of the top of the borehole; the subsequent level measured in [the shallow piezometer in BH01a](#) was also above ground level. However, since installation, the integrity of the shallow piezometer (BH01a) has been compromised and it is no longer possible to record a groundwater level, but groundwater can be observed leaking from around the edge of the installation indicating that artesian groundwater is present.

BH201 and BH202 were wash drilled to approximately 60 m to ensure interception of the groundwater table along the southern boundary.

An existing piezometer (comprising a single 50 mm PVC pipe, in a 100 mm diameter borehole) was discovered adjacent to the northeast site access. No information about this piezometer (drill date, target, etc.) is available. The base of this piezometer was measured at 42.50 m bgl.

[In updating this report in May 2021, it has been decided that the groundwater level data is presented in the Groundwater Report¹ \(GHD, 2021\).](#)

3.7 Investigation coordinates

Positions for machine boreholes and test pits were recorded by Woods Surveying. Coordinates are presented in the North Taieri Circuit (2000) projection, and elevation [Reduced Levels \(RL\)](#) are presented in terms of New Zealand Vertical Datum (2016).

¹ GHD, 2021, *Smooth Hill Landfill Consenting – Groundwater Report*

BH06, BH08 and all test pits were picked up with a cluster of points around the pads. The coordinates for the most central pickup point have been selected to represent the test location. These points are marked with an asterisk (*) in the table below.

TP05, TP07, TP08, and all of the Phase II investigations have not yet been surveyed. Coordinates for these test locations have been estimated from Google Earth and are marked with a double asterisk (**) in the table below. Elevations for these points have been estimated from the Stantec contour map presented in Appendix A.

Table 6 summarises the position coordinates for all test locations.

Table 6 Summary of test location positions

Test Location ID	Easting	Northing	Elevation (m RL)
BH01	396465.49	788214.52	96.01
BH02	396358.59	788022.89	97.41
BH03	396428.38	787998.34	107.48
BH04	396563.60	788063.75	108.15
BH05	396459.76	787862.12	129.50
BH06	396168.25*	787593.98*	149.75*
BH07	396493.65	787671.87	139.73
BH08	396809.71*	787700.67*	143.89*
BH09	395951.84	788050.36	132.80
BH10	396788.26	788118.50	139.07
BH201	396596**	787540**	144**
BH202	396181**	787498**	144**
BH203	395779**	787672**	182**
BH209	395775**	788148**	132**
BH211	396598**	787965**	107**
TP01	395988.85	788077.23	121.20
TP02	396103.50	788056.91	110.40
TP03	396262.16	788048.16	102.61
TP05	396281**	787868**	105**
TP06	396585.70	787800.45	108.24
TP07	396182**	787790**	120**
TP08	396303**	787682**	115**
TP09	396577.97	787947.86	101.04
TP10	396820.11	788079.25	140.74
TP11	396907.03	788032.98	141.24
TP12	396956.93	787986.46	142.28
BS01 / BS02	396149**	787571**	150**
BS03 / BS04	396202**	787994**	135**
BS05 / BS06	396537**	787504**	152**
BS07	396500**	787616**	141**
BS08 / BS09	396490**	787771**	130**
BS10 / BS11	396441**	787922**	119**
BS12 / BS13	396382**	787582**	132**
BS14 / BS15	396366**	787738**	120**

3.8 Laboratory testing

3.8.1 Phase I test schedule

Selected samples obtained from Phase I of the geotechnical investigation were tested at the IANZ accredited Central Testing Services laboratory in Alexandra. Table 7 summarises the laboratory testing programme undertaken.

Table 7 Summary of geotechnical laboratory testing

Sample Source	Depth From (m bgl)	Depth To (m bgl)	Atterberg Limits - NZS 4402:1986, Test 2.2, 2.3 & 2.4	Particle Size Distribution - NZS 4402:1986, Test 2.8.1 & 2.8.4.	NZ Standard Compaction - NZS 4402:1986, Test 4.1.1	Pinhole Dispersion and Crumb Test - ASTM D4647 & ASTM D6572	Triaxial Permeability ⁺ - ASTM D5084
TP10	2.2	3.6	x	x	x	x	x
BH05	0.0	1.2					
BH07 (combined)	0.0	1.4	x	x	x	x	x
* - using de-aired tap water							

3.8.2 Phase II test schedule

On completion of Phase I of the geotechnical investigation a further suite of samples were tested by Central Testing Services in Alexandra. Two suites of lab testing were undertaken with the following purposes:

- To determine the suitability of the Loess soils for either lime or bentonite stabilisation as a method of reducing [erodibility](#)/ dispersivity. Eight (8) bulk samples were combined and divided into four sub-samples. The four sub-samples were then tested as outlined in Table 8.
- To determine suitability of CW-HW Henley Breccia Soils for use as engineered fill beneath the landfill liner. Two samples were tested as outlined in Table 9.

Table 8 Summary of geotechnical laboratory testing for stabilised soils.

Sample Source	Sub-sample Number	Atterberg Limits - NZS 4402:1986, Test 2.2, 2.3 & 2.4	Lime demand test (NSW Transport; Roads & Maritime Services Test Method T144 (Not IANZ Accredited))	Atterberg Limits - NZS 4402:1986, Test 2.2, 2.3 & 2.4 (Stabilised Soil)	NZ Standard Compaction - NZS 4402:1986, Test 4.1.1	Shear Strength – Shear Vane – NZGS 2001	Pinhole Dispersion and Crumb Test - ASTM D4647 & ASTM
BS01 (0.5m) BS03 (0.7m)	Sub-sample #1	X	X	X (Lime Stabilised – 1 day curing)	X	X	X
BS07 (0.5m) BS08 (0.6m)	Sub-sample #2	X	X	X (Lime Stabilised – 7 day curing)	X	X	X
BS10 (0.7m) BS11 (1.3m)	Sub-sample #3	X		X (Bentonite Stabilised – 1 day curing)	X	X	X
BS12 (0.4m) BS13 (1.2m)	Sub-sample #4	X		X (Bentonite Stabilised- 7 day curing)	X	X	X

Table 9 Summary of geotechnical laboratory testing for engineered fill

Sample Source	Depth From (m bgl)	Depth To (m bgl)	Atterberg Limits - NZS 4402:1986, Test 2.2, 2.3 & 2.4	NZ Standard Compaction - NZS 4402:1986, Test 4.1.1	Unconfined Compressive Strength of Soil, NZS 4402:1986: Test 6.3.1
BH05	2.7	7.2	X	X	X
BH10	2.4	7.0	X	X	X

3.8.3 Phase III test schedule

A third round of laboratory testing will be undertaken on the performance of the loess, should a mineral liner be included in the detailed design of the liner system. This will require fresh samples to be taken of the loess.

3.8.3.4 Phase I test results

Table 10 to Table 15 summarise the results of the laboratory testing outlined in Section 3.8.1. Detailed laboratory test results are presented in Appendix C.

Table 10 Summary of particle size distribution test results (NZS 4402:1986, Test 2.8.1 and 2.8.4)

Sample Source	Geological Unit	Percent Passing (%)			
		Gravel (2 to 60 mm)	Sand (0.06 to 2 mm)	Silt (0.002 to 0.06 mm)	Clay (<0.002 mm)
TP10	Loess	6	13	72	9
BH05/BH07	Loess	1	10	60	29

Table 11 Summary of Atterberg limit test results (NZS 4402:1986, Test 2.1, 2.2, 2.3 and 2.4)

Sample Source	Geological Unit	Water Content (%)	Liquid Limit	Plastic Limit	Plasticity Index
TP10	Loess	15.5	39	28	11
BH05/BH07	Loess	23.6	42	23	19

Table 12 Summary of NZ standard compaction test results (NZS 4402:1986, Test 2.1 and 4.1.1)

Sample Source	Geological Unit	Water Content – As Received (%)	Maximum Dry Density (t/m ³)	Optimum Water Content (%)
TP10	Loess	15.5	1.71	16.0
BH05/BH07	Loess	23.6	1.70	17.5

Table 13 Summary of pinhole dispersion test results (ASTM D4647-13e1)

Sample Source	Geological Unit	Elapsed Time (min)	Flow Rate (ml/s)	Outflow Colour	Hole Diameter Pre-test	Hole Diameter Post-test	Classification
TP10	Loess	1	0.25	Slightly dark	1.0 mm	~2.0 mm (4 mm at exit)	Dispersive (D)
		5	0.27	Moderately dark			
		10	0.31	Dark			
BH05 / BH07	Loess	1	0.25	Barely visible	1.0 mm	~2.0 mm	Dispersive (D)
		5	0.27	Moderately dark			
		10	0.49	Very dark			

Table 14 Summary of crumb test results (ASTM D6572-13e2 (Method B))

Sample Source	Geological Unit	Elapsed Time	Estimated Slaking	Observations	Crumb Test Classification
TP10	Loess	2 min	~50%	No colloidal cloud	Grade 4 (Highly Dispersive)
		1 hr	~100%	Dense colloidal cloud over	
		6 hr	~100%	Moderate colloidal	
BH05/BH07	Loess	2 min	~20%	No colloidal cloud	Grade 4 (Highly Dispersive)
		1 hr	~100%	Dense colloidal cloud over	
		6 hr	~100%	Dense colloidal cloud over	

Table 15 Summary of triaxial permeability test results (ASTM D5084-16a)

Sample Source	Geological Unit	Cell Pressure (kPa)	Initial Permeability (m/s)	Final Permeability (m/s)
TP10	Loess	610	2.9×10^{-8}	3.2×10^{-8}
TP10	Loess	727	2.7×10^{-8}	2.8×10^{-8}
BH05/BH07	Loess	460	1.7×10^{-9}	2.1×10^{-9}
BH05/BH07	Loess	527	5.6×10^{-10}	5.3×10^{-10}

3.8.43.8.5 Phase II test results

Table 16 to Table 20 summarise the results of the laboratory testing outlined in Section 3.8.2. Detailed laboratory test results are presented in Appendix C.

Table 16 Summary of Atterberg limit test results (Natural Soils)

Sample	Geological Unit	Water Content (%)	Liquid Limit	Plastic Limit	Plasticity Index
Sub-sample #1	Loess (untreated)	25	41	25	16
Sub-sample #2	Loess (untreated)	25	41	25	16
Sub-sample #3	Loess (untreated)	25	41	25	16
Sub-sample #4	Loess (untreated)	25	41	25	16

Table 17 Summary of lime demand test results

Sample	Geological Unit	pH 0 % added Lime	pH 1 % added Lime	pH 2 % added Lime	pH 3 % added Lime	pH 4 % added Lime	pH 5 % added Lime	pH 6 % added Lime	pH 7 % added Lime
Sub sample #1	Loess (untreated)	5.12	10.15	12.12	12.42	12.46	12.49	12.48	12.42
Sub-sample #1	Loess (untreated)	5.16	10.31	12.08	12.5	12.55	12.56	12.55	12.55

Table 18 Summary of Atterberg limit test results (Henley Breccia Formation)

Sample	Geological Unit	Liquid Limit	Plastic Limit	Plasticity Index
BH05 2.7 – 7.2 m	Henley Breccia – CW Siltstone	41	25	16
BH10 2.4 – 7.0 m	Henley Breccia – CW Siltstone / Sandstone	37	23	14

Table 19 Summary of NZ standard compaction test results (Henley Breccia Formation)

Sample Source	Geological Unit	Maximum Dry Density (t/m3)	Optimum Water Content (%)
BH05 2.7 – 7.2 m	Henley Breccia – CW Siltstone	1.76	16.0
BH10 2.4 – 7.0 m	Henley Breccia – CW Siltstone / Sandstone	1.85	14.0

Table 20 Summary of unconfined compressive strength of re-compacted samples (Henley Breccia Formation)

Sample Source	Geological Unit	Unconfined Compressive Strength (kPa)
BH05 2.7 – 7.2 m	Henley Breccia – CW Siltstone	100
BH10 2.4 – 7.0 m	Henley Breccia – CW Siltstone / Sandstone	93

4. References

The following documents have been consulted in preparation of the guideline:

- Bishop, D.G. 1994, *Geology of the Milton area. Scale 1:50,000, Institute of Geological & Nuclear Sciences geological map 9. 1 sheet + 32 p*, Institute of Geological & Nuclear Sciences Ltd, Lower Hutt, New Zealand
- Bishop, D.G. Turnbull, I.M. (compilers) 1996, *Geology of the Dunedin Area. Institute of Geological and Nuclear Sciences 1:250,000 geological map 21. 1 sheet + 52 p*, Lower Hutt, New Zealand: Institute of Geological and Nuclear Sciences Limited
- GNS Active Faults Database, <http://maps.gns.cri.nz/website/af/viewer.htm>
- New Zealand Geotechnical Society, 2001, *Guideline for Handheld Shear Vane Test*
- New Zealand Geotechnical Society, 2005, *Guideline for the Field Classification and Description of Soil and Rock for Engineering Purposes*
- Stantec (not dated), *Smooth Hill Site – Plan*, Reference 80510415-01-001-S10, Revision A
- Stirling, McVerry, et al, 2010, *National Seismic Hazard Model for New Zealand: 2010 Update*. Bulletin of the Seismological Society of America, Vol. 102, No. 4, pp. 1514-1542, August 2012

5. Limitations

This report has been prepared by GHD for Dunedin City Council) and may only be used and relied on by the Client for the purpose agreed between GHD and the Client as set out in Section 1 of this report.

GHD otherwise disclaims responsibility to any person other than the Client and Council officers, consultants, the hearings panel and submitters associated with the resource consent and notice of requirement process for the Smooth Hill Landfill Project arising in connection with this report. GHD also excludes implied warranties and conditions, to the extent legally permissible.

The services undertaken by GHD in connection with preparing this report were limited to those specifically detailed in the report and are subject to the scope limitations set out in the report.

The opinions, conclusions and any recommendations in this report are based on conditions encountered and information reviewed at the date of preparation of the report. GHD has no responsibility or obligation to update this report to account for events or changes occurring subsequent to the date that the report was prepared.

The opinions, conclusions and any recommendations in this report are based on assumptions made by GHD described in this report. GHD disclaims liability arising from any of the assumptions being incorrect.

GHD has prepared this report on the basis of information provided by Client and others who provided information to GHD (including Government authorities)], which GHD has not independently verified or checked beyond the agreed scope of work. GHD does not accept liability in connection with such unverified information, including errors and omissions in the report which were caused by errors or omissions in that information.


The opinions, conclusions and any recommendations in this report are based on information obtained from, and testing undertaken at or in connection with, specific sample points. Site conditions at other parts of the site may be different from the site conditions found at the specific sample points.

Investigations undertaken in respect of this report are constrained by the particular site conditions, such as the location of vegetation and topography. As a result, not all relevant site features and conditions may have been identified in this report.



















Site conditions (including the presence of hazardous substances and/or site contamination) may change after the date of this Report. GHD does not accept responsibility arising from, or in connection with, any change to the site conditions. GHD is also not responsible for updating this report if the site conditions change.


Appendices

Appendix A – Plans



Appendix B – Borehole and Test Pit Logs and Photographs

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Dam foundation Job Number: 12506381 Commenced: 6/06/2019 Completed: 6/06/2019					Hole No. : BH01 Sheet : 1 of 2 Hole Length : 15.00m Scale @ A4 : 1:50									
Easting: 396465.49 Northing: 788214.52 System: TAIETM2000 RL: 96.01 Datum: NZVD2016								Logged : MF Processed : HB Checked : JS									
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
	0		0.00 - 1.20 Fine to medium gravelly SILT, trace fine to coarse sand, trace clay; light yellow brown & orange brown. Stiff, moist, low plasticity. (COLLUVIUM?). Gravel clasts comprise quartz and schist, sub angular to sub rounded.	COLLUVIUM	M	St				PQTT				77			
	1.2		1.20 - 2.70 Inferred CORELOSS. Possible slip base & stream alluvium lost? Driller said it "was so soft, it was like drilling nothing". Tried pushing down with no water or rotation, but still could not retrieve core. Same for next coreloss zone at 3.0 m to 3.9 m.	ALLUVIUM		"				PQTT				20			
	2.7		2.70 - 2.90 Silty CLAY, trace fine sand; grey & orange brown. Soft to firm, moist, high plasticity. (ALLUVIUM?).		M	S-F				PQTT				0			
	2.9		2.90 - 3.00 Silty fine to coarse SAND, trace organics; grey. Poorly graded. (ALLUVIUM?). Note no moisture condition or density determined and logged.			"				PQTT							
	3.0		3.00 - 3.90 Inferred CORELOSS. Possible alluvium loss?							PQTT							
	3.9		3.90 - 4.40 Slightly weathered, light grey fine to coarse SANDSTONE; moderately strong to strong; well indurated, no defects. (HENLEY BRECCIA).							PQTT		SW		100			
	4.4		4.40 - 4.80 Slightly weathered, grey SILTSTONE; very weak to weak; poorly indurated, no defects.							PQTT		SW		22			
	4.8		4.80 - 5.28 Slightly weathered, light grey fine to coarse SANDSTONE; very weak to weak; poorly indurated, no defects.							PQTT		SW		98			
	5.28		5.28 - 5.38 From 5.28 m, becomes moderately strong to strong, well indurated.							PQTT		SW		80			
	5.38		5.38 - 6.00 From 5.38 m, becomes very weak to weak, poorly indurated.							PQTT		SW					
	6.00		6.00 - 6.25 From 6.00 m, becomes moderately strong to strong, well indurated.							PQTT		SW					
	6.25		6.25 - 6.80 From 6.25 m, becomes very weak to weak, poorly indurated.							PQTT		SW		100			
	6.8		6.80 - 7.80 Slightly weathered, light yellow brown & reddish brown SILTSTONE; very weak to weak; poorly indurated, no defects. From 6.9 m, becomes light grey & reddish brown. From 7.05m, becomes light grey with purple-brown layers. From 7.3 m to 7.4 m, becomes fin	HENLEY BRECCIA						PQTT		SW		97			
	7.8		7.80 - 8.30 Slightly weathered, light grey with purple-brown layers fine to medium SANDSTONE; very weak to weak; poorly indurated, no defects.							PQTT		SW		53			
	8.3		8.30 - 9.00 Inferred CORELOSS in gravel layer. Gravel present on ends of core abutting this zone. Fine to medium gravel, quartz and schist clasts, sub angular to sub rounded.			"				PQTT				53			
	9.0		9.00 - 9.50 Slightly weathered, grey and brown SILTSTONE; very weak to weak; poorly indurated, no defects.							PQTT		SW		100			
	9.5		9.50 - 11.30 Slightly weathered, light grey with purple-brown layers fine to medium SANDSTONE; very weak to weak; poorly indurated, no defects.							PQTT		SW		100			
Notes and Comments:				Inclination: Vertical		Orientation:		Ground Water Level		Date		Time		Reading (mbgl)		Hole depth (mbgl)	
End of Hole @ 15.00m, Target Depth.				Contractor: McNiels		Equipment: Mounted Rig											
Looks like drill pad on slip debris pile. Scarp above (east) of pad. Ground stripped ~0.6 m, including all topsoil. Piezo installed 10/06/2019. As of end of 07/06/2019, driller has been unable to recover core from last run. keeps returning empty core. Return explanation sheets to sub contractor on 10/06/2019.				Shear Vane Id:													

		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Dam foundation Job Number: 12506381 Commenced: 6/06/2019 Completed: 6/06/2019						Hole No. : BH01 Sheet : 2 of 2 Hole Length : 15.00m Scale @ A4 : 1:50										
		Easting: 396465.49 Northing: 788214.52 System: TAIETM2000 RL: 96.01 Datum: NZVD2016						Logged : MF Processed : HB Checked : JS										
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Number / Type	Result	Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect mm Spacing (mm)	Instrumentation Installation	Water level	
			From 10.5 m: 10 mm thick bedding visible.	HENLEY BRECCIA					122mm	PQTT		SW		100 100				
11	11.3		11.30 - 13.10 Unweathered, grey BRECCIA; moderately strong to strong; fine to medium gravel size clasts, coarse sand matrix, matrix supported, well indurated, no defects. Clasts are quartz and schist, angular to sub rounded, 300-600 mm bedding.							PQTT			UW		97 97			
12	12.2		From 11.7 m: very few							PQTT					100 100			
13	12.8		13.10 - 15.00 From 13.1 m, becomes weak to moderately strong, fine to coarse gravel clasts, clast supported, moderate to well indurated.							PQTT								
14	13.1		Note - As of end of 07/06/2019, driller has been unable to recover core from last run. keeps slipping out of barrel. Will try aga							PQTT		UW						
15			End of Hole @ 15.00m, Target Depth.															
16																		
17																		
18																		
19																		
20																		

Notes and Comments: End of Hole @ 15.00m, Target Depth. Looks like drill pad on slip debris pile. Scarp above (east) of pad. Ground stripped ~0.6 m, including all topsoil. Piezo installed 10/06/2019. As of end of 07/06/2019, driller has been unable to recover core from last run. keeps slipping out of barrel. Will try aga. Return explanation sheets to sub contractor on 10/06/2019.				Inclination: Vertical		Orientation:		Ground Water Level			
				Contractor: McNiells		Equipment: Mounted Rig		Date	Time	Reading (mbgl)	Hole depth (mbgl)
				Shear Vane Id:							




CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 3
Borehole ID	BH01	



Box 1 of 5: 0.00 m to 4.80 m



Box 2 of 5: 4.80 m to 7.20 m




CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 3
Borehole ID	BH01	



Box 3 of 5: 8.20 m to 10.20 m




Box 4 of 5: 10.20 m to 12.40 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 3 of 3
Borehole ID	BH01	



Box 5 of 5: 12.40 m to 15.00 m (EOH)

		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Toe bund Job Number: 12506381 Commenced: 27/05/2019 Completed: 28/05/2019						Hole No. : BH02 Sheet : 1 of 2 Hole Length : 15.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JS																					
Easting: 396358.59 RL: 97.41		Northing: 788022.89 Datum: NZVD2016		System: TAIETM2000																									
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level												
							Number / Type	Result																					
	0		0.00 - 0.50 Inferred CORELOSS			"											0												
	0.5	x	0.50 - 1.50 SILT, minor clay, trace to minor fine sand; light grey & brown. Stiff to very stiff, moist, non plastic. Contains Fe weathered spots & small (<50mm) lenses of Fe staining. (LOESS)	LOESS	M	St-VSt	SV@1.5m 42/5			PQTT				67			1												
	1	x																											
	1.5	x	1.50 - 2.15 Inferred CORELOSS			"																					2		
	2	x	2.15 - 2.45 Fine sandy SILT, trace clay; light grey. Firm, moist, non plastic (transitions into) 2.45 - 2.60 Silty fine SAND; grey. 'Very loose to loose', saturated, poorly graded (ALLUVIUM?). Moisture content may be influenced by drilling fluid in loose materials. 2.60 - 2.90 Fine sandy SILT; grey. Firm, moist, non plastic. Rootball at 2.8-2.9 m 2.90 - 3.35 Inferred CORELOSS (Likely gravel that got washed away)	HISTORIC [PRE GLACIAL] ALLUVIUM	M	F												SV@2.8m 7			PQTT			50			3		
	2.15	x																										S	VL-L
	2.45	x																										M	F
	2.62	x																											"
	2.9	x	3.35 - 3.70 GRAVEL; light grey. 'Very loose to loose', saturated, gravel is fine, angular to subangular quartz & schist. Fines matrix washed away. Moisture content may be influenced by drilling fluid in loose materials. (ALLUVIUM? TOP OF BRECCIA?) End of day 27/05/19.	HISTORIC [PRE GLACIAL] ALLUVIUM	S	VL-L															PQTT			70			4		
	3.35	x																										D	VD
	3.7	x	3.70 - 3.95 Fine to coarse SAND, minor to some fine gravel; grey. 'Very dense' soil or extremely weathered to very weathered rock (BRECCIA), dry, non plastic; gravel is fine quartz & schist, angular to subangular. 3.95 - 5.30 Unweathered, bedded, alternating grey fine SANDSTONE & SILTSTONE; very weak; bedding 300 to 500 mm thick, uniform grainsize within layers. Quartz vein noted at 4.6 m at 60 degrees to core axis, (bedding horizontal?). 5.30 - 5.70 Unweathered, grey SANDSTONE (BOULDER); strong; lithified fine angular gravel layers, no defects (BRECCIA). 5.70 - 5.90 Silty CLAY; dark grey. Firm to stiff, moist, high plasticity (not lithified). 5.90 - 6.40 Unweathered, bedded, alternating grey fine SANDSTONE & SILTSTONE; very weak; bedding 300 to 500 mm thick, uniform grainsize within layers. 10 mm coal lense at 6.11 - 6.12 m. 6.40 - 6.55 Unweathered, grey silty fine SANDSTONE; weak to moderately strong. 6.55 - 9.10 Unweathered, grey BRECCIA; weak to moderately strong; semi distinct bedding, no defects. Clasts are quartz & schist, fine to medium gravel size, angular to subrounded. Coarse SAND matrix.	HENLEY BRECCIA	M	F-St												SV@4.3m UTP			PQTT				109			5	
	3.95	x																											
	4	x																											
	5.3	x																											
	5.7	x																											
	5.9	x																											
	6	x	9.10 - 9.20 SILT; grey. Very stiff to hard, dry, non plastic (not lithified). 9.20 - 9.80 Unweathered, grey BRECCIA; weak to moderately strong; semi distinct bedding, no defects. Clasts are quartz & schist, fine to medium gravel size, angular to subrounded. Coarse SAND matrix. Lithified solid.	HENLEY BRECCIA	D	VSt-H				PQTT			96			9													
	6.55	x																											
	6.4	x															6												
	6.56	x															7												
	7	x															8												
	8	x															9												
	9	x															10												
	9.1	x																											
	9.8	x																											
Notes and Comments: End of Hole @ 15.00m, Target Depth. Groundwater SWL at 0.23 mbgl (31/05/2019). Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level				Date	Time	Reading (mbgl)	Hole depth (mbgl)														
				Contractor: McNeills		Equipment: Mounted Rig																							
				Shear Vane Id: GEO1826																									



CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 3
Borehole ID	BH02	



Box 1 of 6: 0.0 m to 3.7 m




Box 2 of 6: 3.7 m to 5.8 m




CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 3
Borehole ID	BH02	



Box 3 of 6: 5.8 m to 8.25 m



Box 4 of 6: 8.25 m to 10.3 m




CLIENTS | PEOPLE | PERFORMANCE


Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 3 of 3
Borehole ID	BH02	




Box 5 of 6: 10.3 m to 12.55 m



Box 6 of 6: 12.55 m to 15.0 m (EOH)

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Toe bund/central ridge Job Number: 12506381 Commenced: 28/05/2019 Completed: 29/05/2019						Hole No. : BH03 Sheet : 1 of 2 Hole Length : 20.00m Scale @ A4 : 1:50								
Easting: 396428.38 Northing: 787998.34 System: TAIETM2000 RL: 107.48 Datum: NZVD2016									Logged : MF Processed : HB Checked : JS								
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
			0.00 - 0.20 TOPSOIL SILT, minor clay; light brown & grey. Very stiff, moist, low plasticity; organics mixed in soil.	TOPSOIL	M	VSt											
			0.20 - 1.90 Clayey SILT, trace fine sand, trace fine gravel; yellow brown & light grey. Very stiff to hard, moist, high plasticity. (LOESS).	LOESS	M	VSt-H				PQTT				73			
			1.90 - 2.30 SILT, minor clay, minor fine sand; light grey & light orange brown. Very stiff to hard, dry to moist, low plasticity.		D-M	VSt-H				PQTT				100			
			2.30 - 2.60 SILT, minor fine sand, trace clay; light grey and orange brown. Hard, dry, non plastic. Variable Fe staining throughout core.		D	'H'											
			2.60 - 3.20 Inferred CORELOSS			"											
			3.20 - 3.65 Silty, coarse sandy GRAVEL; brown. 'Very loose to loose', moist, well graded (completely weathered rock? never lithified?), clasts angular to sub angular; quartz & schist. Moisture content may be influenced by drilling fluid in loose materials.		M	VL-L				PQTT				60			
			3.65 - 5.70 Fine to coarse GRAVEL, some silt, minor fine to coarse sand; purple. 'Dense', dry, well graded (highly weathered rock?), sub angular to angular clasts; quartz & schist. End of shift 28/05/19 at 17:16.		D	D				PQTT				27			
			5.70 - 6.05 Highly weathered, reddish grey BRECCIA Boulder; strength undetermined.														
			6.05 - 6.20 Fine to coarse GRAVEL, some silt, minor fine to coarse sand; purple. 'Dense', dry, well graded (highly weathered rock?), sub angular to angular clasts; quartz & schist.	HENLEY BRECCIA	D	D				PQTT				100			
			6.20 - 6.60 SILT, minor fine to medium sand, trace to minor fine gravel; grey & yellow brown. Very stiff, moist, non plastic.		M	'VL-L'				PQTT				38			
			6.60 - 7.50 (800 mm coreloss assumed this unit) Fine to medium GRAVEL; white & grey. 'Very loose to loose', moist, well graded. Clasts are angular to sub angular quartz & schist. Any matrix has been washed away. Moisture content may be influenced by drilling fluid in loose materials.		D	H											
			7.50 - 7.90 SILT, trace fine gravel; brown, grey, light purple. Hard, dry, non plastic. (Transitions from hard silt to siltstone).							PQTT				100			
			7.90 - 8.45 Unweathered, dark grey SILTSTONE; weak to moderately strong; no obvious small scale bedding, no defects.			"								100			
			8.45 - 8.90 Unweathered, grey fine SANDSTONE; weak to moderately strong; no obvious small scale bedding, no defects.														
			8.90 - 9.20 Inferred CORELOSS (loose sand layer washed away?).							PQTT				73			
			9.20 - 10.10 Unweathered, bedded, alternating dark grey & grey SILTSTONE & SANDSTONE; weak to moderately strong, no obvious small scale bedding, no defects. ~300-400 mm alternating SILTS.											69			
Notes and Comments: End of Hole @ 20.00m, Target Depth. Groundwater SWL at 3.9 mbgl during piezo install. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level									
				Contractor: McNeills				Date	Time	Reading (mbgl)	Hole depth (mbgl)						
				Equipment: Mounted Rig													
				Shear Vane Id: GEO1826													

Groundwater level at the end of drilling

<div></div> <div>Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Toe bund/central ridge Job Number: 12506381 Commenced: 28/05/2019 Completed: 29/05/2019</div>										<div>Hole No. : BH03 Sheet : 2 of 2 Hole Length : 20.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JS</div>													
Easting: 396428.38 RL: 107.48					Northing: 787998.34 Datum: NZVD2016					System: TAIETM2000													
Material Description										Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
													Number / Type	Result									
RL (m)	Depth (m)	Graphic																					
	10.1		10.10 - 10.70 Unweathered, grey fine to medium SANDSTONE; very weak to weak; no defects.																				
11	11.000	x	10.70 - 10.90 SILT, minor clay; brown. Very stiff to hard, dry to moist, non plastic; looks organic in origin. (Buried topsoil?).																				
	10.7	x	10.90 - 11.05 Unweathered, light grey SILTSTONE; very weak to weak; no defects.																				
	11.0	x	11.05 - 13.65 Unweathered, light grey & white BRECCIA; moderately strong to strong; Clasts; quartz & schist, fine to medium gravel size, angular to sub angular. Matrix supported, coarse sand matrix.																				
12	12.000	△																					
	10.7	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					
	11.0	△																					



CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 4
Borehole ID	BH03	



Box 1 of 8: 0.0 m to 2.6 m



Box 2 of 8: 2.6 m to 6.25 m



CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 4
Borehole ID	BH03	



Box 3 of 8: 6.25 m to 9.25 m



Box 4 of 8: 9.25 m to 11.05 m




CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 3 of 4
Borehole ID	BH03	



Box 5 of 8: 11.05 m to 13.3 m



Box 6 of 8: 13.3 m to 15.6 m




CLIENTS | PEOPLE | PERFORMANCE


Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 4 of 4
Borehole ID	BH03	




Box 7 of 8: 15.6 m to 17.7 m



Box 8 of 8: 17.7 m to 20.0 m (EOH)


			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Toe bund foundation Job Number: 12506381 Commenced: 6/06/2019 Completed: 7/06/2019						Hole No. : BH04 Sheet : 1 of 2 Hole Length : 15.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JS								
Easting: 396563.6 RL: 108.15			Northing: 788063.75 Datum: NZVD2016			System: TAIETM2000											
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
	0		0.00 - 0.25 SILT, minor clay; dark grey. Firm, moist, low plasticity. (TOPSOIL/FILL). From 0.2 m: some intermixing with underlying soil.	FILL	M	F											
	0.25		0.25 - 0.60 SILT, minor clay, trace fine sand, trace organics (roots); orange brown. Stiff, moist, low plasticity. (LOESS). 0.60 - 0.90 From 0.6m, becomes light grey with orange-brown streaks, stiff to very stiff.	TOPSOIL	M	St											
	0.9		0.90 - 1.40 Silty fine to medium SAND; grey with orange streaks. Density undetermined, moist, poorly graded. from 1.1 m, becomes trace fine gravel, sub angular to sub rounded quartz and schist.	LOESS	M	St-VSt				PQTT				100			
	1.31		1.40 - 1.50 (BURIED TOPSOIL) SILT with roots; grey. Stiff to very stiff, moist, non plastic.	BURIED TOPSOIL	M	St-VSt											
	1.51		1.50 - 2.45 Silty, fine to coarse sandy, fine to medium GRAVEL; orange brown. Density undetermined, moisture content undetermined, well graded, quartz and schist clasts, sub angular to sub rounded. (Heavily weathered rock?). 2.45 - 2.80 Inferred CORELOSS.			"				PQTT		HW		73			
	2.45		2.80 - 4.40 Moderately weathered, light grey & orange brown fine to medium SANDSTONE; very weak to weak; poorly indurated, no defects. Fe banding throughout. Fe bands change angle downhole from sub horizontal to sub vertical & back & back. Bedding 1-20 mm thick. (HENLEY BRECCIA).														
	2.8		4.40 - 4.70 Moderately weathered, CONGLOMERATE; extremely weak to very weak; poorly indurated, well graded, fine to coarse quartz and schist clasts, sub angular to rounded, silt matrix, matrix supported. 4.70 - 5.90 Inferred CORELOSS from this run.			"				PQTT		MW		100			
	4.4		5.90 - 6.40 Inferred CORELOSS from this run.			"								100			
	4.7		6.40 - 7.00 Slightly weathered, grey with purple-brown layers fine to medium SANDSTONE; very weak to weak; poorly indurated, poorly graded.							PQTT		MW					
	5.9		7.00 - 7.40 From 7.0 m, becomes moderately strong to strong, well indurated.														
	6.4		7.40 - 8.40 From 7.4 m, becomes very weak to weak, poorly indurated.														
	6.4		8.40 - 8.70 From 8.40 m, becomes moderately strong to strong, well indurated.							PQTT		SW		69			
	7		8.70 - 8.85 Slightly weathered, BRECCIA; moderately strong to strong; fine to medium gravel clasts, fine to coarse sand matrix.														
	8		8.85 - 9.60 Slightly weathered, light grey fine to coarse SANDSTONE; very weak to weak; poorly indurated, poorly graded, no defects.														
	8.58		9.60 - 10.10 From 9.6 m, becomes moderately strong to strong, well indurated.							PQTT		SW		83			
	9													63			
Notes and Comments: End of Hole @ 15.00m, Target Depth. Groundwater at 2.52 mbtoc (TOC 0.53 m agl) - corrected groundwater at 1.99 mbgl 07/06/2019. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level									
				Contractor: McNiells				Date	Time	Reading (mbgl)	Hole depth (mbgl)						
				Equipment: Mounted Rig													
				Shear Vane Id:													

<div></div> <div>Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Toe bund foundation Job Number: 12506381 Commenced: 6/06/2019 Completed: 7/06/2019</div>										<div>Hole No. : BH04 Sheet : 2 of 2 Hole Length : 15.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JS</div>									
Easting: 396563.6 RL: 108.15					Northing: 788063.75 Datum: NZVD2016					System: TAIETM2000									
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect mm Spacing (mm)	Instrumentation Installation	Water level		
							Number / Type	Result											
	10.1	△	10.10 - 10.60 Slightly weathered, grey BRECCIA; moderately strong to strong; well indurated, fine to medium gravel clasts, fine to coarse sand matrix, matrix supported. Clasts are quartz & schist, sub rounded to angular. Very wide spaced defects.	HENLEY BRECCIA						PQTT				83					
	10.6	△	10.60 - 10.80 Slightly weathered, light grey fine to coarse SANDSTONE; very weak to weak; poorly indurated, no defects.							PQTT					63				
11	11.1	△	10.80 - 11.10 Slightly weathered, brown SILTSTONE; very weak to weak; poorly indurated, no defects. From 11.0 m, becomes light grey.							PQTT					97				
	11.1	△	11.10 - 11.50 Slightly weathered, light grey & pinkish grey BRECCIA; weak to moderately strong; moderate to well indurated, no defects, fine to coarse gravel clasts, fine to coarse sand matrix, clast supported. Clasts are quartz and schist sub angular to angular. Note: clast size decreases with depth.							PQTT					97				
12	12.1	△	11.50 - 12.20 From 11.5 m, becomes moderately strong to strong, well indurated, fine to medium gravel clasts.							PQTT					88				
	12.1	△	12.20 - 15.00 From 12.2 m, becomes weak to moderately strong, moderate to well indurated, fine to coarse gravel clasts.							PQTT					56				
13	13.1	△	From 13.9sm: clasts mostly medium to coarse gravel.							PQTT									
	14.1	△								PQTT					100				
	14.1	△								PQTT					73				
15	15.0		End of Hole @ 15.00m, Target Depth.																
16																			
17																			
18																			
19																			
Notes and Comments: End of Hole @ 15.00m, Target Depth. Groundwater at 2.52 mbtoc (TOC 0.53 m agl) - corrected groundwater at 1.99 mbgl 07/06/2019. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation: Contractor: McNiels Equipment: Mounted Rig Shear Vane Id:								Ground Water Level Date Time Reading (mbgl) Hole depth (mbgl)							
												07/06/19 00:00 1.99 15							



CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 3
Borehole ID	BH04	



Box 1 of 6: 0.0 m to 2.7 m




Box 2 of 6: 2.7 m to 5.9 m



CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 3
Borehole ID	BH04	



Box 3 of 6: 5.9 m to 8.7 m



Box 4 of 6: 8.7 m to 11.1 m




Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 3 of 3
Borehole ID	BH04	





Box 5 of 6: 11.1 m to 13.5 m



Box 6 of 6: 13.5 m to 15.0 m (EOH)


<div></div> <div>Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Central ridge Job Number: 12506381 Commenced: 29/05/2019 Completed: 30/05/2019</div>				<div>Hole No. : BH05 Sheet : 1 of 3 Hole Length : 30.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JS</div>													
Easting: 396459.76		Northing: 787862.12		System: TAIETM2000													
RL: 129.5		Datum: NZVD2016															
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
			0.00 - 0.80 Clayey SILT; grey & dark orange brown. Very stiff, moist, high plasticity. (LOESS).		M	VSt											
			0.80 - 1.00 SILT, minor clay, trace fine sand; orange brown with some grey. Very stiff, moist, low plasticity.		M	VSt				PQTT				100			
			1.00 - 1.50 Fine to medium gravelly SILT, trace clay; orange brown & white. Very stiff, moist, low plasticity.		M	VSt											
			1.50 - 2.70 Inferred CORELOSS Catcher did not grip sample. Note: No shear vane undertaken at 2.7 m due to no core.			"	SV@1.5m UTP			PQTT				0			
			2.70 - 2.80 Fine to medium gravelly SILT, trace clay; orange brown & white. Very stiff, moist, low plasticity.		M	VSt											
			2.80 - 3.50 Inferred CORELOSS (Washed away?).			"				PQTT				53			
			3.50 - 3.70 Fine to medium GRAVEL; creamy white. Undetermined density, undetermined moisture condition, well graded, quartz & schist gravel, angular to sub angular.		M	VSt											
			3.70 - 3.80 Fine to medium gravelly SILT, trace clay; orange brown & white. Very stiff, moist, low plasticity. Fe staining on upper contact.		D-M	H											
			3.80 - 4.00 SILT, trace organics; light grey. Hard, dry to moist, non plastic.		M	VSt											
			4.00 - 4.45 Fine gravelly SILT, trace clay, trace organics; orange brown & light grey. Very stiff, moist, non plastic. Note no shear vane at 4.2 m due to material being too gravelly.		D-M	H				PQTT				103			
			4.45 - 5.70 SILT, trace clay, trace organics; light grey with orange brown streaks. Hard, dry to moist, non plastic. From 5.1 m, becomes orange brown with some light grey. From 5.35 m, 2-3 mm Fe "gravel" beds. From 5.6 m, becomes very thinly laminated (2-3mm).		M	St-VSt	SV@5.7m UTP										
			5.70 - 5.90 Silty CLAY, trace fine sand, trace organics; brown to grey. Stiff to very stiff, moist, high plasticity.		M	H				PQTT				100			
			5.90 - 6.50 SILT, trace clay, trace organics; light grey with black flecks. Hard, moist, non plastic, Fe staining. Note: Fe stained contact at 6.50 m.		M	H											
			6.50 - 6.80 SILT, trace medium gravel (schist), brown to grey. Hard, moist, non plastic. Note: dark orange brown Fe stained contact at 6.80 m.		D	H											
			6.80 - 7.20 SILT, trace organics; light grey & orange brown, with black flecks. Hard, dry, non plastic, thin (<1mm) 'rusty' laminations.							PQTT				100			
			7.20 - 7.75 Moderately weathered, dark grey with black streaks SILTSTONE; very weak to weak; thinly bedded, contains organic rich layers, defects 500-1000 mm spacing.											87			
			7.75 - 7.80 Moderately weathered, grey SANDSTONE; very weak; 50 mm bedded layer within siltstone.														
			7.80 - 8.50 Moderately weathered, dark grey with black streaks SILTSTONE; very weak to weak; thinly bedded, contains organic rich layers, defects 500-1000 mm spacing. From 7.9 m: 2-5 mm thick lignite layers. At 8.2 m: 20 mm lignite layer. At 8.32 m to 8.37 m: 50 mm lignite layer. At 8.42 m to 8.44 m: 20 mm lignite layer.							PQTT				93			
			8.50 - 8.70 From 8.5 m, becomes slightly weathered, lignite											93			
Notes and Comments: End of Hole @ 30.00m, Target Depth. ~ 0.5 m topsoil stripped to make drill pad Groundwater SWL at 16.4 mbgl during piezo install. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level									
				Contractor: McNeills				Date	Time	Reading (mbgl)	Hole depth (mbgl)						
				Equipment: Mounted Rig													
				Shear Vane Id: GEO1826													








Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 7
Borehole ID	BH05	




Box 1 of 14: 0.0 m to 3.8 m



Box 2 of 14: 3.8 m to 5.8 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 7
Borehole ID	BH05	



Box 3 of 14: 5.8 m to 7.88 m



Box 4 of 14: 7.88 m to 9.93 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 3 of 7
Borehole ID	BH05	




Box 5 of 14: 9.93 m to 11.87 m




Box 6 of 14: 11.87 m to 13.9 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 4 of 7
Borehole ID	BH05	



Box 7 of 14: 13.9 m to 15.87 m



Box 8 of 14: 15.87 m to 18.45 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 5 of 7
Borehole ID	BH05	




Box 9 of 14: 18.45 m to 20.1 m




Box 10 of 14: 20.1 m to 22.08 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 6 of 7
Borehole ID	BH05	



Box 11 of 14: 22.08 m to 24.5 m



Box 12 of 14: 24.5 m to 26.8 m




Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 7 of 7
Borehole ID	BH05	





Box 13 of 14: 26.8 m to 29.0 m




Box 14 of 14: 29.0 m to 30.0 m (EOH)

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southwest Ridge Job Number: 12506381 Commenced: 13/06/2019 Completed: 14/06/2019						Hole No. : BH06 Sheet : 1 of 3 Hole Length : 30.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JHS									
Easting: 396168.25 RL: 149.75			Northing: 787593.98 Datum: NZVD2016			System: TAIETM2000												
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level	
							Number / Type	Result										
			Top 250 mm dug out for drill pad (TOPSOIL)	TS														
			SILT, trace to minor clay, trace fine to medium sand, trace fine gravel; grey and orange-brown. Very stiff, moist, low plasticity (LOESS)	LOESS	M	VSt				PQTT				83 17				
			Highly weathered, yellow-brown SILTSTONE; extremely weak; no defects (HENLEY BRECCIA)	HENLEY BRECCIA														
			Highly weathered, thinly bedded, yellow-brown silty fine SANDSTONE; extremely weak; no defects; iron-staining in layers and spots; trace organics throughout;							PQTT					100 89			
			2.70 m: 170 mm layer gravelly SANDSTONE								PQTT							
					</													

		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southwest Ridge Job Number: 12506381 Commenced: 13/06/2019 Completed: 14/06/2019						Hole No. : BH06 Sheet : 3 of 3 Hole Length : 30.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JHS											
Easting: 396168.25 Northing: 787593.98 System: TAIETM2000 RL: 149.75 Datum: NZVD2016																			
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Number / Type	Result	Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect	Spacing (mm)	Instrumentation Installation	Water level	
129	21		of lignite and widely spaced moderately thin siltstone beds Unweathered, light grey and black fine to medium SANDSTONE; very weak to weak; very widely spaced defects; with moderately widely spaced laminated very thin to thin beds of lignite and widely spaced moderately thin siltstone beds (continued from layer starting at 19.4m) 20.20 m: fine to coarse sand 20.70 m: fine to medium sand 21.06 m: 230 mm siltstone interbed 21.70 m: very thinly bedded (2-10 mm) 22.20 m: moderately thickly bedded (~ 300 mm) 22.40 m: 150 mm siltstone interbed 22.75 m: laminated (2-10 mm)	HENLEY BRECCIA						PQTT				93 65 47					20
128	22								PQTT				100 100 100					21	
127	23								PQTT				87 87 87					22	
126	24								PQTT				100 100 100					23	
125	25								PQTT				88 88 88					24	
124	26								PQTT				100 32 32					25	
123	27								PQTT				76 76 76					26	
122	28								PQTT									27	
121	29		27.50 - 28.50 m: very closey spaced fractures, possibly drilling induced 28.40 - 28.50 m: dark grey-brown for 100 mm 28.70 - 28.80 m: dark brown layer - looks like lithified topsoil Unweathered, light grey BRECCIA; weak to moderately strong; no defects; moderately well indurated; clasts: quartz and schist, fine gravel size, sub-angular to sub-rounded; matrix supported; matrix: fine to coarse sand						PQTT									28	
120	30																	29	
End of Hole @ 30.00m, Target Depth. End of Hole @ 30.00m, Target Depth. Groundwater not encountered. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation: Contractor: McNeills Equipment: UDR600 (truck mounted) Shear Vane Id:						Ground Water Level Date: 14/06/19 Time: 00:00 Reading (mbgl): Hole depth (mbgl): 30									



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 7
Borehole ID	BH06	



Box 1 of 13: 0.0 m to 2.4 m



Box 2 of 13: 2.4 m to 4.6 m



CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 7
Borehole ID	BH06	



Box 3 of 13: 4.6 m to 7.2 m



Box 4 of 13: 7.2 m to 10.0 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 3 of 7
Borehole ID	BH06	



Box 5 of 13: 10.0 m to 13.2 m



Box 6 of 13: 13.2 m to 15.6 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 4 of 7
Borehole ID	BH06	



Box 7 of 13: 15.6 m to 17.7 m




Box 8 of 13: 17.7 m to 20.2 m




CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 5 of 7
Borehole ID	BH06	



Box 9 of 13: 20.2 m to 22.2 m



Box 10 of 13: 22.2 m to 24.7 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 6 of 7
Borehole ID	BH06	



Box 11 of 13: 24.7 m to 27.0 m




Box 12 of 13: 27.0 m to 29.3 m



CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 7 of 7
Borehole ID	BH06	



Box 13 of 13: 29.3 m to 30.0 m (EOH)



CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 4
Borehole ID	BH07	



Box 1 of 8: 0.0 m to 2.7 m



Box 2 of 8: 2.7 m to 4.8 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 4
Borehole ID	BH07	



Box 3 of 8: 4.8 m to 7.0 m



Box 4 of 8: 7.0 m to 9.1 m




CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 3 of 4
Borehole ID	BH07	



Box 5 of 8: 9.1 m to 11.2 m




Box 6 of 8: 11.2 m to 13.2 m



CLIENTS | PEOPLE | PERFORMANCE

























Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 4 of 4
Borehole ID	BH07	



Box 7 of 8: 13.2 m to 15.8 m



Box 8 of 8: 15.8 m to 20.0 m (EOH)


		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Big Stone Road Job Number: 12506381 Commenced: 11/06/2019						Hole No. : BH08 Sheet : 1 of 2 Hole Length : 20.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JHS									
Easting: 396809.71 RL: 143.89		Northing: 787700.67 Datum: NZVD2016		System: TAIETM2000													
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
143.89 1 142 2 141 3 140 4 139 5 138 6 137 7 136 8 135 9 134	0		TOPSOIL; silt, trace to minor clay, trace fine sand; dark grey and yellow-brown. Very stiff, moist, low plasticity; trace roots	TS	M	VSt											0
	0.25		SILT, trace clay, trace fine sand; grey mottled orange-brown. Very stiff, moist, low plasticity (LOESS) 0.60 m: more orange-brown mottled grey		M	VSt											
	1		1.50 m: grey and brown mottled orange iron stained inclusions														
	1.84		1.84 - 2.86 m: CORE LOSS	LOESS													
	2																
	2.86		Fine sandy SILT, trace clay; light grey-brown. Very stiff, dry, low plasticity 3.00 m: light grey and orange; iron stained laminations		D	VSt											
	3																
	3.75		SILT, trace to minor clay, trace coarse sand (rusty); light grey and orange-brown. Very stiff to hard, moist, low plasticity		M	VSt-H											
	4		SILT, minor to some clay; brown with black flecks and streaks. Very stiff to hard, dry to moist, high plasticity; trace to minor organics (BURIED TOPSOIL)	BTS	D-M	VSt-H											
	4.4		Highly weathered, grey, orange-brown and yellow-brown BRECCIA; very weak to weak; no defects; clasts: quartz and schist, sub-angular to sub-rounded, fine gravel size; matrix: fine to coarse sand; matrix supported														
	5		Highly weathered, grey and orange-brown SILTSTONE; extremely weak to very weak; no defects														
	5.2		Highly weathered, grey, orange-brown and yellow-brown BRECCIA; very weak to weak; no defects; clasts: quartz and schist, sub-angular to sub-rounded, fine to medium gravel, matrix: fine to coarse sand; matrix supported														
	6		6.20 - 6.90 m: CORELOSS (inferred silty GRAVEL)														
	6.2																
	7		Fine to medium GRAVEL; orange-brown, white, yellow-brown and grey. Poorly graded; inferred silt matrix from minimal matrix recovery; gravel, quartz and schist, angular to sub-rounded.	HENLEY BRECCIA													
	7.1		Moderately weathered, grey, orange-brown and white BRECCIA; weak; gravel quartz and schist, angular to sub-rounded, fine to medium gravel; matrix: fine to coarse sand; matrix supported														
	8		Slightly weathered, light grey SILTSTONE; very weak to weak; no defects (grades into next unit)														
8.1		Slightly weathered, light grey fine to coarse SANDSTONE; very weak to weak; no defects															
9		Slightly weathered, light grey and grey BRECCIA; weak to moderately strong; no defects; no visible bedding; matrix: fine to coarse sand, matrix supported; clasts: quartz and schist, sub-rounded to angular, fine to medium gravel size															
9.0		9.00 - 14.10 m: unweathered, fine to coarse gravel size clasts, clast supported															
9.3																	
9.6																	
10																	
Notes and Comments: End of Hole @ 20.00m, Target Depth. Groundwater not encountered. No piezos were installed. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level									
				Contractor: McNeills				Date	Time	Reading (mbgl)	Hole depth (mbgl)						
				Equipment: UDR600 (truck mounted)													
				Shear Vane Id: GEO2288													





CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 4
Borehole ID	BH08	




Box 1 of 8: 0.0 m to 3.7 m




Box 2 of 8: 3.7 m to 5.7 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 4
Borehole ID	BH08	



Box 3 of 8: 5.7 m to 8.7 m




Box 4 of 8: 8.7 m to 11.1 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 3 of 4
Borehole ID	BH08	




Box 5 of 8: 11.1 m to 13.25 m



Box 6 of 8: 13.25 m to 15.9 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 4 of 4
Borehole ID	BH08	



Box 7 of 8: 15.9 m to 18.0 m



Box 8 of 8: 18.0 m to 20.0 m (EOH)







CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 2
Borehole ID	BH09	



Box 1 of 3: 0.0 m to 9.6 m




Box 2 of 3: 9.6 m to 11.7 m





Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 2
Borehole ID	BH09	



Box 3 of 3: 11.7 m to 16.5 m (EOH)

		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Eastern ridge Job Number: 12506381 Commenced: 4/06/2019 Completed: 5/06/2019						Hole No. : BH10 Sheet : 1 of 3 Hole Length : 20.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JS											
Easting: 396788.26 RL: 139.07		Northing: 788118.5 Datum: NZVD2016		System: TAIETM2000															
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level		
							Number / Type	Result											
	0.25		0.00 - 0.25 SILT, trace fine sand, trace clay; brown. Firm to stiff, moist, low plasticity. (TOPSOIL).	TOPSOIL	M	F-St													
	0.25		0.25 - 1.60 CORELOSS																
	1.6		1.60 - 2.40 Fine sandy SILT; light grey& yellow brown. Stiff, moist, low plasticity.	LOESS	M	St				PQTT				12					
	2.4		2.40 - 2.60 Completely weathered to residual soil, fine to coarse SAND, minor silt; colour unspecified. Density unspecified, moist, poorly graded. (HENLEY BRECCIA).									PQTT				136			
	2.6		2.60 - 3.30 High weathered, pebbly coarse SAND; colour unspecified. Density unspecified, moist, poorly graded. (Heavily weathered, very weak to weak rock?).									PQTT				93			
	3.3		3.30 - 4.90 Moderately weathered, grey, orange brown & yellow brown SILTSTONE; very weak to weak, no defects. (HENLEY BRECCIA).									PQTT				93			
	4.3		At 4.3 m, 300 mm SANDSTONE layer.	Henley Breccia															
	4.9		4.90 - 6.60 Moderately weathered, light grey & organge brown fine SANDSTONE; very weak to weak; no defects. Occasional lignite inclusions.							PQTT				86					
	5.5		At 5.5 m: 140 mm SILTSTONE layer.																
	6.6		6.60 - 7.05 Moderately weathered, orange brown, white & grey, fine to medium pebbly CONGLOMERATE; very weak to weak; coarse sand matrix, matrix supported. Clasts are quartz & schist, sub angular to rounded.							PQTT				93					
	7.05		7.05 - 7.60 Moderately weathered, light grey & orange brown SILTSTONE; very weak to weak; no defects noted.																
	7.6		7.60 - 7.72 Moderately weathered, orange brown, white & grey, fine to medium pebbly CONGLOMERATE; very weak to weak; coarse sand matrix, matrix supported. Clasts are quartz & schist, sub angular to rounded.							PQTT				28					
	7.72		7.72 - 8.80 Inferred CORELOSS.																
	8.8		Offsiders dropped rod & bent end & it did not pick up core.																
	8.8		8.80 - 9.10 Inferred CORELOSS depth.																
	9.1		9.10 - 9.55 Moderately weathered, orange brown, white & grey, fine to medium pebbly CONGLOMERATE; very weak to weak; coarse sand matrix, matrix supported. Clasts are quartz & schist, sub angular to rounded.							PQTT				75					
	9.55		9.55 - 11.40 Slightly weathered, grey SANDSTONE; very weak											75					
Notes and Comments: End of Hole @ 20.00m, Target Depth. Hole extended to find groundwater. Groundwater at 10.17 mbgl 07/06/2019. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level											
				Contractor: McNeills		Equipment: Mounted Rig		Shear Vane Id:		Date	Time	Reading (mbgl)	Hole depth (mbgl)						

<div></div> <div>Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Eastern ridge Job Number: 12506381 Commenced: 4/06/2019 Completed: 5/06/2019</div>										<div>Hole No. : BH10 Sheet : 2 of 3 Hole Length : 20.00m Scale @ A4 : 1:50</div> <div>Logged : MF Processed : HB Checked : JS</div>																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
Easting: 396788.26 RL: 139.07										Northing: 788118.5 Datum: NZVD2016										System:																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
Material Description										Geological Unit										Moisture condition										Consistency / Relative density										Sample										Casing										Method										Flush Return (%)										Weathering										Estimated Strength (MPa)										TCR RQR (%)										Defect Spacing (mm)										Instrumentation Installation										Water level																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
to weak; thinly bedded (1-10 mm). Only artificial breaks. Occasional lignite. From 10.4 m, becomes yellow brown, fine to coarse SANDSTONE. 11.40 - 11.60 From 11.4 m, becomes weak to moderately strong. 11.60 - 17.40 From 11.6 m, becomes very weak to weak. Note: From 15.5 m: lignite content increases. From 15.6 m: 40 mm lignite. From 15.8 m: 100 mm lignite rich layer. 17.40 - 17.65 From 17.4 m, becomes moderately strong to strong, well indurated. 17.65 - 19.20 From 17.65 m, becomes very weak to weak, poorly indurated. 19.20 - 19.80 From 19.2 m, becomes weak to moderately strong, moderate to well indurated. 19.80 - 20.00 From 19.8 m, becomes moderately strong to										Henley Breccia																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Smooth Hill Eastern ridge Job Number: 12506381 Commenced: 4/06/2019 Completed: 5/06/2019						Hole No. : BH10 Sheet : 3 of 3 Hole Length : 20.00m Scale @ A4 : 1:50 Logged : MF Processed : HB Checked : JS								
Easting: 396788.26 Northing: 788118.5 System: RL: 139.07 Datum: NZVD2016																	
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Unconfined Strength (MPa)	TCR SCR RQR (%)	Defect Hole Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
			strong, well indurated. End of Hole @ 20.00m, Target Depth.														
20																	
21																	
22																	
23																	
24																	
25																	
26																	
27																	
28																	
29																	
30																	

Notes and Comments: End of Hole @ 20.00m, Target Depth. Hole extended to find groundwater. Groundwater at 10.17 mbgl 07/06/2019. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level			
				Contractor: McNeills		Equipment: Mounted Rig		Date	Time	Reading (mbgl)	Hole depth (mbgl)
				Shear Vane Id:							



CLIENTS | PEOPLE | PERFORMANCE

Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 1 of 4
Borehole ID	BH10	




Box 1 of 8: 0.0 m to 3.2 m



Box 2 of 8: 3.2 m to 5.8 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 2 of 4
Borehole ID	BH10	



Box 3 of 8: 5.8 m to 9.2 m



Box 4 of 8: 9.2 m to 11.6 m



Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 3 of 4
Borehole ID	BH10	




Box 5 of 8: 11.6 m to 13.8 m



Box 6 of 8: 13.8 m to 16.0 m




Project	Smooth Hill Landfill Consenting	
Client	Dunedin City Council	
Job number	12506381	Page 4 of 4
Borehole ID	BH10	









Box 7 of 8: 16.0 m to 18.4 m





Box 8 of 8: 18.4 m to 20.0 m (EOH)

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Manuka Gully (Stockpile Area) Job Number: 12506381 Commenced: 12/06/2019 Completed: 12/06/2019						Hole No. : TP01 Sheet : 1 of 1 Hole Length : 2.50m Scale @ A4 : 1:25 Logged : MF Processed : HB Checked : MF								
Easting: 395988.85 Northing: 788077.23 System: TAIETM2000 RL: 121.2 Datum: NZVD2016																	
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
121	0.2		SILT, trace to minor clay; dark grey-brown. Firm, wet, low plasticity; minor to some organics/roots (TOPSOIL)	TS	W	F											
	0.7		SILT, trace clay, trace fine to medium sand; light grey with orange streaks. Stiff to very stiff, moist, low plasticity; iron-stained organics throughout (ALLUVIUM)	ALLUVIUM	M	St-VSt											
120	1.0		Gravelly SILT, minor clay, minor fine to coarse sand; orange-brown. Very stiff, moist to wet, low plasticity; gravel: fine to medium, quartz and schist, sub-angular to rounded; highly weathered rock (HENLEY BRECCIA)		M-W	VSt											
	1.10		1.10 m: grey with some orange-brown														
119	1.9		Slightly weathered, grey with black streaks SILTSTONE; very weak; ripped easily with toothed excavator bucket	HENLEY BRECCIA													
	2.50		End of Hole @ 2.50m, Target Depth.														
118	3.0																
117	4.0																
	5.0																

Notes and Comments: End of Hole @ 2.50m, Target Depth. Soils too gravelly for shear vane. Groundwater seepage into test pit at 1.0 mbgl Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation: Contractor: Fulton Hogan Equipment: 22t excavator - toothed bucket Shear Vane Id:				Ground Water Level <table border="1"> <tr> <th>Date</th> <th>Time</th> <th>Reading (mbgl)</th> <th>Hole depth (mbgl)</th> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </table>				Date	Time	Reading (mbgl)	Hole depth (mbgl)				
Date	Time	Reading (mbgl)	Hole depth (mbgl)																

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Manuka Gully (Stockpile Area) Job Number: 12506381 Commenced: 12/06/2019 Completed: 12/06/2019						Hole No. : TP02 Sheet : 1 of 1 Hole Length : 2.60m Scale @ A4 : 1:25 Logged : MF Processed : HB Checked : MF								
Easting: 396103.5 RL: 110.4			Northing: 788056.91 Datum: NZVD2016			System: TAIETM2000											
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
110	0.6		SILT, trace to minor fine sand, trace to minor clay; brown. Firm, moist, low plasticity; minor organics/roots (TOPSOIL)	TOPSOIL	M	F		SV@0.3m 65/17 kPa									
	1		Silty SAND, trace clay; light grey with orange-brown streaks. 'Loose to medium dense', poorly graded; sand: fine (COLLUVIUM)	COLLUVIUM		L-MD											
109	1.4		SILT, minor clay, trace to minor fine sand; brown. Firm, moist, low plasticity; wood fragments throughout layer, most at top (BURIED TOPSOIL)	BURIED TOPSOIL	M	F		SV@1.8m 90/33 kPa									
	2.1		Gravelly SILT; grey. Wet, well graded; gravel: fine to coarse (ALLUVIUM)	ALLUVIUM		W											
108	2.4		Slightly weathered, grey SILTSTONE; ripped easily with toothed bucket (HENLEY BRECCIA)	HB							SW						
	3		End of Hole @ 2.60m, Target Depth.														
	4																
	5																

Notes and Comments: End of Hole @ 2.60m, Target Depth. Groundwater seepage into test pit at 0.4 mbgl. Refer to explanation sheets for abbreviation and symbols		Inclination: Vertical		Orientation:		Ground Water Level			
		Contractor: Fulton Hogan		Equipment: 22t excavator - toothed bucket		Date	Time	Reading (mbgl)	Hole depth (mbgl)
		Shear Vane Id: GEO2288		12/06/19	00:00	0.4	2.6		

		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Manuka Gully (Stockpile Area) Job Number: 12506381 Commenced: 12/06/2019 Completed: 12/06/2019						Hole No. : TP03 Sheet : 1 of 1 Hole Length : 2.00m Scale @ A4 : 1:25										
		Easting: 396262.16 Northing: 788048.16 System: TAIETM2000 RL: 102.61 Datum: NZVD2016						Logged : MF Processed : HB Checked : MF										
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect	Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result										
102	0		SILT, trace to minor fine sand, trace to minor clay; brown. Soft, moist to wet, low plasticity; minor organics/roots (TOPSOIL)	TOPSOIL	M-W	S												
1	0.7		Silty SAND, trace clay; light grey with brown streaks. Moist, poorly graded; sand is fine (ALLUVIUM)	ALLUVIUM	M													
101	1.2		Gravelly SILT; grey. Wet to saturated, well graded; gravel: fine to coarse	ALLUVIUM	W - S													
2	1.7		Slightly weathered, grey SILTSTONE; extremely to very weak; no defects - ripped easily (HENLEY BRECCIA)	HB								SW						
	2		End of Hole @ 2.00m, Target Depth.															
100	3																	
99	4																	
98	5																	

Notes and Comments:

End of Hole @ 2.00m, Target Depth.

Test pit sides too soft to get shear vane readings.
Groundwater encountered at 1.2 mbgl.

Refer to explanation sheets for abbreviation and symbols

Inclination: Vertical

Orientation:

Contractor: Fulton Hogan


Equipment: 22t excavator - toothed bucket


Shear Vane Id:


Ground Water Level

Date	Time	Reading (mbgl)	Hole depth (mbgl)
12/06/19	00:00	1.2	2


Groundwater encountered at 1.2 mbgl.


		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southwest Gully Base Job Number: 12506381 Commenced: 13/06/2019						Hole No. : TP05 Sheet : 1 of 1 Hole Length : 3.30m Scale @ A4 : 1:25 Logged : MF Processed : HB Checked : MF									
Easting: 396281		Northing: 787868		System: TAIETM2000													
RL: 125		Datum: NZVD2016															
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
			SILT, minor clay; brown. Soft, wet to saturated, low plasticity; minor organics throughout (TOPSOIL)	TOPSOIL	W-S	S											
			Silty fine to medium SAND; grey and yellow-brown. 'Loose', wet, poorly graded (COLLUVIUM)	COLLUVIUM	W	'L'											
			Fine to coarse SAND, minor to some silt; grey with black streaks. 'Loose', saturated, poorly graded; organics throughout		S	'L'											
			Tree trunks and branches with some gravel. Groundwater outflow from base of layer														
			SILT, minor clay, trace fine sand; grey with yellow-brown streaks. Stiff, moist, low plasticity; highly weathered rock (HENLEY BRECCIA)	HENLEY BRECCIA	M	St											
			Slightly weathered, SILTSTONE; ripped easily														
			End of Hole @ 3.30m, Target Depth.														
													</				




			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southwest Gully Base Job Number: 12506381 Commenced: 28/05/2019 Completed: 28/05/2019						Hole No. : TP07 Sheet : 1 of 1 Hole Length : 2.50m Scale @ A4 : 1:25 Logged : MF Processed : HB Checked : MF										
Easting: 396182 Northing: 787790 System: TAIETM2000 RL: 120 Datum: NZVD2016																			
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level		
							Number / Type	Result											
119	0		SILT/organic matter, brown. Soft, moist to saturated, fibrous, non plastic (TOPSOIL)	TOPSOIL	M-W	S													
119	0.5		SILT, minor clay, trace fine sand; light grey and yellow-brown. Stiff to very stiff, moist, low plasticity (LOESS)	LOESS	M	St-VS				TP									
118	1.4		Slightly weathered, grey SILTSTONE; weak to moderately strong; no defects (HENLEY BRECCIA)	HENLEY BRECCIA							SW								
117	2.4		BRECCIA																
117			End of Hole @ 2.50m, Target Depth.																
116	4																		
115																			
Notes and Comments: End of Hole @ 2.50m, Target Depth. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation: Contractor: Fulton Hogan Equipment: 22t excavator - smooth bucket Shear Vane Id:				Ground Water Level <table border="1"> <tr> <th>Date</th> <th>Time</th> <th>Reading (mbgl)</th> <th>Hole depth (mbgl)</th> </tr> <tr> <td>28/05/19</td> <td>00:00</td> <td>1.4</td> <td>2.5</td> </tr> </table>				Date	Time	Reading (mbgl)	Hole depth (mbgl)	28/05/19	00:00	1.4	2.5
Date	Time	Reading (mbgl)	Hole depth (mbgl)																
28/05/19	00:00	1.4	2.5																


Water level on SILTSTONE








			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Gully Between Southern Ridges Job Number: 12506381 Commenced: 28/05/2019 Completed: 28/05/2019						Hole No. : TP08 Sheet : 1 of 1 Hole Length : 4.50m Scale @ A4 : 1:25 Logged : MF Processed : HB Checked : MF								
Easting: 396303 Northing: 787682 System: TAIETM2000 RL: 115 Datum: NZVD2016																	
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
114	0.6		SILT, minor clay, trace fine sand; dark grey. Firm to stiff, moist, low plasticity; minor organic matter (FILL)	FILL	M	F-St											
	0.50 m		grass and trees - buried surface, saturated		S												
1	1.2		SILT, minor clay, trace fine sand; dark grey. Firm to stiff, wet, low plasticity; trace to minor organics (BURIED TOPSOIL)	BURIED TOPSOIL	W	F-St											
2			SILT, minor to some clay, trace fine sand; light grey and yellow-brown. Stiff to very stiff, moist, low plasticity; trace organics (LOESS)	LOESS	M	St-VSt											
3																	
4			SILT, some coarse sand, minor fine gravel; light grey. Stiff to very stiff, moist, non-plastic; gravel comprises quartz and schist; highly weathered rock (HENLEY BRECCIA)	HENLEY BRECCIA	M	St-VSt											
5			End of Hole @ 4.50m, End of Reach.														
Notes and Comments: End of Hole @ 4.50m, End of Reach. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation: Contractor: Fulton Hogan Equipment: 22t excavator - smooth bucket Shear Vane Id:				Ground Water Level Date: 28/05/19 Time: 00:00 Reading (mbgl): Hole depth (mbgl): 4.5									








		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : South East Gully Outflow Job Number: 12506381 Commenced: 13/06/2019 Completed: 13/06/2019				Hole No. : TP09 Sheet : 1 of 1 Hole Length : 3.00m Scale @ A4 : 1:25											
		Easting: 396577.97 Northing: 787947.86 System: TAIETM2000 RL: 101.04 Datum: NZVD2016				Logged : MF Processed : MF Checked : MF											
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
101.04	0		SILT, minor fine to coarse gravel; yellow-brown and grey. Stiff, moist, low plasticity; minor organic content (SLIP DEBRIS)	SLIP DEBRIS	M	St											
	0.5		Branches and grass (BURIED VEGETATION)														
	0.7		SILT, minor clay; brown. Firm to stiff, moist, low plasticity (BURIED TOPSOIL)	BTS	M	F-St											
	1.00		Gravelly silty SAND; orange-brown. Moist, poorly graded; gravel is fine; sand is fine to coarse (ALLUVIUM)		M												
	1.30		1.00 m: light grey and orange-brown 1.30 m: light grey with orange-brown streaks	ALLUVIUM													
	2.7		Fine SANDSTONE; easily ripped (HENLEY BRECCIA)	HB													
	3.00		End of Hole @ 3.00m, Target Depth.														
	4.0																
	5.0																


Notes and Comments: End of Hole @ 3.00m, Target Depth. Test pit dug to side of gully base - too boggy in gully base to excavate Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level			
				Contractor:		Equipment: 22t Excavator		Shear Vane Id:		Date	Time

<div></div> <div>Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Future Laydown Area Job Number: 12506381 Commenced: 10/06/2019 Completed: 10/06/2019</div>										<div>Hole No. : TP10</div> <div>Sheet : 1 of 1 Hole Length : 3.60m Scale @ A4 : 1:25</div> <div>Logged : MF Processed : HB Checked : MF</div>									
Easting: 396820.11 RL: 140.74					Northing: 788079.25 Datum: NZVD2016					System: TAIETM2000									
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level		
			SILT, trace to minor clay, trace fine sand; dark grey. Very stiff, moist, low plasticity; tree roots throughout (TOPSOIL)	TOPSOIL	M	VSt													
	0.4		SILT, minor clay; light grey and yellow-brown. Very stiff, moist, low plasticity; root webs throughout (LOESS)		M	VSt	SV@0.5m 136/62 kPa												
	1						SV@1m 194 kPa												
	1.2		SILT, minor fine sand, trace clay; orange-brown and light grey. Very stiff, dry, low plasticity	LOESS	D	VSt	SV@1.5m 194 kPa												
	2		SILT, minor fine sand, trace clay; orange-brown. Very stiff, dry, low plasticity; iron-stained horizon		D	VSt	SV@2m 194 kPa												
	2.2		SILT; orange-brown and grey alternating. Very stiff, dry, non-plastic		D	VSt	SV@2.5m UTP												
	3		Highly weathered SILTSTONE (HENLEY BRECCIA) 3.00 - 3.60 m: hard, root webs visible in places	HENLEY BRECCIA		H	SV@3m UTP					HW							
							SV@3.5m UTP												
	3.60		End of Hole @ 3.60m, Target Depth.																
	4																		
Notes and Comments:				Inclination: Vertical				Orientation:				Ground Water Level							
End of Hole @ 3.60m, Target Depth.				Contractor: Fulton Hogan				Date				Time							
EOH at 3.6 mbgl, too hard to dig/end of reach. Groundwater not encountered.				Equipment: 22t excavator				Reading (mbgl)				Hole depth (mbgl)							
Refer to explanation sheets for abbreviation and symbols				Shear Vane Id: GEO2288															




		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Future Laydown Area Job Number: 12506381 Commenced: 10/06/2019 Completed: 10/06/2019						Hole No. : TP12 Sheet : 1 of 1 Hole Length : 4.40m Scale @ A4 : 1:25 Logged : MF Processed : HB Checked : MF									
Easting: 396596.93 RL: 142.28		Northing: 787986.46 Datum: NZVD2016		System: TAIETM2000													
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
142	0		SILT, minor clay, trace fine sand, dark grey and brown. Stiff to very stiff, moist, low plasticity. Trace to minor roots (FILL)	FILL	M	St-VSt		SV@0.4m 139/44 kPa									
	0.7		Sandy SILT, grey. Very stiff, dry, non-plastic; some large roots extend to approximately 1.2 m bgl; trace organics; sand is fine (BURIED TOPSOIL).	BTS	D	VSt		SV@1m UTP									
141	1		Sandy SILT; light grey, light yellow-brown and orange-brown. Very stiff, dry, non-plastic; sand is fine; occasional roots to 1.2 m bgl; strength increases with depth (LOESS)	LOESS	D	VSt		SV@2m UTP									
	2		2.50 m: 50-100 mm iron-stained layer					SV@2.9m UTP									
140	3		3.60 m: 50-100 mm iron-stained layer														
	4		Highly weathered, SILTSTONE (HENLEY BRECCIA)	HB				SV@4.4m UTP				HW					
138			End of Hole @ 4.40m, Target Depth.														
Notes and Comments: End of Hole @ 4.40m, Target Depth. EOH at 4.4 mbgl, deepest excavator could excavate soil. Groundwater not encountered. Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level									
				Contractor: Fulton Hogan		Equipment: 22t excavator		Shear Vane Id: GEO2288		Date	Time	Reading (mbgl)	Hole depth (mbgl)				
										10/06/19	00:00		4.4				


			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 29/10/2019 Completed: 1/11/2019						Hole No. : BH201 Sheet : 1 of 7 Hole Length : 61.00m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS											
Easting: 396596 Northing: 787540 System: TAIETM2000 RL: 144 Datum: NZVD2016																				
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SQR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level			
							Number / Type	Result												
143 1 142 2 141 3 140 4 139 5 138 6 137 7 136 8 135 9 134	0		Clayey SILT, trace fine sand; dark grey. Soft, moist to wet, high plasticity; minor to some organic matter, reducing with depth (TOPSOIL)	TS	M-W	S														
	0.35		SILT, minor clay, trace fine sand; grey and orange-brown. Very stiff, moist, low plasticity (LOESS)	LOESS	M	VSt				PQTT				100						
	1.00 - 1.90 m		1.00 - 1.90 m: grey and brown																	
	1.9		SILT, trace clay; light grey with orange-brown streaks. Very stiff, moist, non-plastic; completely weathered (HENLEY BRECCIA)		M	VSt				PQTT				96						
	2.65		SILT, some clay to clayey; red-brown, orange-brown and grey. Firm to stiff, moist, high plasticity; minor rock fragments; completely weathered		M	F-St						CW								
	3		SILT, trace to minor clay; red-brown. Very stiff to hard, moist, low plasticity; completely weathered		M	VSt-H				PQTT				100						
	3.4		Moderately weathered, grey and yellow-brown, moderately thickly bedded, fine to medium grained SANDSTONE; very weak; very widely spaced defects							PQTT				62						
	4		4.20 - 5.00 m: fine to coarse sand																	
	5		4.60 BP, 10°, pl, r, Fe-stained, black 4.90 - 5.00 m: grades into breccia							PQTT		MW		88						
	6		Moderately weathered, brown, grey, orange-brown and red-brown BRECCIA; extremely to very weak; very widely spaced defects; matrix supported; fine sandy silt matrix; clasts are angular to subrounded, quartz and schist, fine to coarse gravel. Soil description: fine to coarse gravelly, fine sandy silt	HENLEY BRECCIA										34						
7		6.12 JT, 15°, pl, r, clean 6.15 JT, 85°, pl, r, clean 6.17 JT, 20°, pl, r, clean 6.30 - 6.45 m: transition from moderately to slightly weathered							PQTT				100							
8		Slightly weathered, grey and light grey BRECCIA; very weak to weak; no defects; matrix supported; fine sand matrix; clasts are angular to subrounded, quartz and schist, fine to coarse gravel																		
9		7.00 - 7.90 m: weak to moderately strong 7.20 - 7.90 m: clast supported 7.50 - 7.90 m: medium to coarse gravel							PQTT			SW		100						
		Slightly weathered, grey and light grey BRECCIA; extremely to very weak; no defects; matrix supported; fine to medium sand matrix; clasts are angular to subrounded, quartz and schist, fine to coarse gravel. Soil description: fine to coarse gravelly, fine sandy silt											48							
		Slightly weathered, grey and light grey BRECCIA; weak to moderately strong; no defects; matrix supported; fine to medium sand matrix; clasts are angular to subrounded, quartz and schist, fine to coarse gravel							PQTT					100						
		9.10 - 9.35 m: 250 mm light grey, fine grained SANDSTONE												29						
Notes and Comments: End of Hole @ 61.00m, Target Depth. 0.0 - 10.8 m PQTT coring 10.8 - 61.0 m wash drilling Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level												
				Contractor: Speight Drilling						Date	Time	Reading (mbgl)	Hole depth (mbgl)							
				Equipment: Track Mounted Rig																
				Shear Vane Id:																


		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 29/10/2019 Completed: 1/11/2019						Hole No. : BH201 Sheet : 2 of 7 Hole Length : 61.00m Scale @ A4 : 1:50									
		Easting: 396596 Northing: 787540 System: TAIETM2000 RL: 144 Datum: NZVD2016						Logged : MF Processed : MF Checked : JHS									
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect	Instrumentation	Water level
							Number / Type	Result									
10.8	10.8	△	Slightly weathered, grey and light grey BRECCIA; weak to moderately strong; no defects; matrix supported; fine to medium sand matrix; clasts are angular to subrounded, quartz and schist, fine to coarse gravel (<i>continued from layer starting at 8.6m</i>)							PQTT		SW		100			
			10.8 m to 61.0 m: Wash drilling											29			
11																	
12																	
13																	
14																	
15																	
16																	
17																	
18																	
19																	
20																	


Notes and Comments: End of Hole @ 61.00m, Target Depth. 0.0 - 10.8 m PQTT coring 10.8 - 61.0 m wash drilling Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation:		Ground Water Level			
				Contractor: Speight Drilling Equipment: Track Mounted Rig Shear Vane Id:		Date	Time	Reading (mbgl)	Hole depth (mbgl)

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 29/10/2019 Completed: 1/11/2019						Hole No. : BH201 Sheet : 3 of 7 Hole Length : 61.00m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS								
Easting: 396596 Northing: 787540 System: TAIETM2000 RL: 144 Datum: NZVD2016																	
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR / SCR / RQR (%)	Defect / Spacing (mm)	Instrumentation	Water level
			10.8 m to 61.0 m: Wash drilling (continued from layer starting at 10.8m)				Number / Type	Result		Wash drilled							
123	21																20
122	22																21
121	23																22
120	24																23
119	25																24
118	26																25
117	27																26
116	28																27
115	29																28
114																	29
																	30



Notes and Comments: End of Hole @ 61.00m, Target Depth. 0.0 - 10.8 m PQTT coring 10.8 - 61.0 m wash drilling Refer to explanation sheets for abbreviation and symbols			Inclination: Vertical Orientation:		Ground Water Level			
			Contractor: Speight Drilling		Date	Time	Reading (mbgl)	Hole depth (mbgl)
			Equipment: Track Mounted Rig					
		Shear Vane Id:						

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 29/10/2019 Completed: 1/11/2019						Hole No. : BH201 Sheet : 4 of 7 Hole Length : 61.00m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS											
Easting: 396596 RL: 144			Northing: 787540 Datum: NZVD2016			System: TAIETM2000														
RL (m)	Depth (m)	Graphic	Material Description				Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
			10.8 m to 61.0 m: Wash drilling (continued from layer starting at 10.8m)																	
113	31																			30
112	32																			31
111	33																			32
110	34																			33
109	35																			34
108	36																			35
107	37																			36
106	38																			37
105	39																			38
104	40																			39
Notes and Comments: End of Hole @ 61.00m, Target Depth. 0.0 - 10.8 m PQTT coring 10.8 - 61.0 m wash drilling Refer to explanation sheets for abbreviation and symbols			Inclination: Vertical			Orientation:			Ground Water Level											
			Contractor: Speight Drilling			Equipment: Track Mounted Rig			Date											
			Shear Vane Id:						Time											
									Reading (mbgl)											
									Hole depth (mbgl)											

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 29/10/2019 Completed: 1/11/2019						Hole No. : BH201 Sheet : 5 of 7 Hole Length : 61.00m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS										
Easting: 396596 Northing: 787540 System: TAIETM2000 RL: 144 Datum: NZVD2016																			
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR / SCR / RQR (%)	Defect / Spacing (mm)	Instrumentation	Water level		
			10.8 m to 61.0 m: Wash drilling (continued from layer starting at 10.8m)							Wash drilled									
103	41																41		
102	42																42		
101	43																43		
100	44																44		
99	45																45		
98	46																46		
97	47																47		
96	48																48		
95	49																49		
94																	50		
Notes and Comments: End of Hole @ 61.00m, Target Depth. 0.0 - 10.8 m PQTT coring 10.8 - 61.0 m wash drilling Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation:				Ground Water Level											
				Contractor: Speight Drilling Equipment: Track Mounted Rig Shear Vane Id:				<table border="1"> <tr> <th>Date</th> <th>Time</th> <th>Reading (mbgl)</th> <th>Hole depth (mbgl)</th> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </table>				Date	Time	Reading (mbgl)	Hole depth (mbgl)				
Date	Time	Reading (mbgl)	Hole depth (mbgl)																

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 29/10/2019 Completed: 1/11/2019						Hole No. : BH201 Sheet : 6 of 7 Hole Length : 61.00m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS											
Easting: 396596 RL: 144			Northing: 787540 Datum: NZVD2016			System: TAIETM2000														
RL (m)	Depth (m)	Graphic	Material Description				Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
			10.8 m to 61.0 m: Wash drilling (continued from layer starting at 10.8m)																	
51																				
52																				
53																				
54																				
55																				
56																				
57																				
58																				
59																				
60																				

Notes and Comments:		Inclination: Vertical		Orientation:		Ground Water Level	
End of Hole @ 61.00m, Target Depth.		Contractor: Speight Drilling		Equipment: Track Mounted Rig		Date	Time
0.0 - 10.8 m PQTT coring 10.8 - 61.0 m wash drilling		Shear Vane Id:				Reading (mbgl)	Hole depth (mbgl)
Refer to explanation sheets for abbreviation and symbols							

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 29/10/2019 Completed: 1/11/2019						Hole No. : BH201 Sheet : 7 of 7 Hole Length : 61.00m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS								
Easting: 396596 RL: 144			Northing: 787540 Datum: NZVD2016			System: TAIETM2000											
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
							Number / Type	Result									
63	61		10.8 m to 61.0 m: Wash drilling (continued from layer starting at 10.8m)							Wash drilled							
61			End of Hole @ 61.00m, Target Depth.														
62																	
63																	
64																	
65																	
66																	
67																	
68																	
69																	
70																	

Notes and Comments: End of Hole @ 61.00m, Target Depth. 0.0 - 10.8 m PQTT coring 10.8 - 61.0 m wash drilling Refer to explanation sheets for abbreviation and symbols			Inclination: Vertical		Orientation:		Ground Water Level			
			Contractor: Speight Drilling		Equipment: Track Mounted Rig		Shear Vane Id:		Date	Time

Report of Photographs

Site Identification: BH201

Project	Waste Futures WS3 – Smooth Hill	Commenced	28/10/2019	Completed	01/11/2019
Site	Southern Boundary	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 10.8 m		



Box 1 of 5: 0.00 m to 2.30 m



Box 2 of 5: 2.30 m to 4.50 m

Report of Photographs

Site Identification: BH201

Project	Waste Futures WS3 – Smooth Hill	Commenced	28/10/2019	Completed	01/11/2019
Site	Southern Boundary	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 10.8 m		



Box 3 of 5: 4.50 m to 6.80 m



Box 4 of 5: 6.80 m to 9.00 m



Report of Photographs


Site Identification: BH201


Project	Waste Futures WS3 – Smooth Hill	Commenced	28/10/2019	Completed	01/11/2019
Site	Southern Boundary	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 10.8 m		



Box 5 of 5: 9.00 m to 10.80 m

10.80 m to 61.00 m (EOH) – Wash drilled, no core recovered

		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 2/11/2019 Completed: 4/11/2019						Hole No. : BH202 Sheet : 1 of 7 Hole Length : 60.60m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS										
Easting: 396181 RL: 144		Northing: 787498 Datum: NZVD2016		System: TAIETM2000														
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level	
			SILT, trace to minor clay; grey and orange-brown. Firm to stiff, moist, low plasticity (FILL/COLLUVIUM?) 0.30 - 0.80 m: brown and grey, very stiff	FILL/COLLUVIUM?	M	F-St												
			0.80 - 0.90 m: trace clay, grey, stiff, minor to some organic matter (roots) 0.90 - 1.20 m: grey and brown, very stiff, trace iron-oxide nodules, "chaotic" texture 1.20 - 1.60 minor iron-oxide nodules			VSt				PQTT				100				
			SILT, trace to minor clay; dark brown. Very stiff, moist, low plasticity; small branches (BURIED TOPSOIL) SILT, trace clay; orange-brown and grey; Very stiff to hard, moist, non-plastic; trace iron-oxide nodules; completely weathered (HENLEY BRECCIA) 2.60 - 2.80 m: minor to some iron-oxide nodules - increases with depth		M	VSt-H				PQTT				100				
			Gravelly, sandy SILT; orange-brown, brown and grey; Very stiff to hard, moist, non-plastic; sand is medium to coarse; gravel is fine to medium, angular to subrounded, quartz and schist; completely weathered 4.10 - 4.50 m: CORE LOSS 4.50 - 5.70 m: CORE LOSS	HENLEY BRECCIA	M	VSt-H				PQTT				94	0			
			Gravelly, sandy SILT; orange-brown, brown and grey; Very stiff to hard, moist, non-plastic; sand is medium to coarse; gravel is fine to medium, angular to subrounded, quartz and schist; completely weathered SILT, trace to minor clay; grey and brown. Very stiff to hard, moist, non-plastic; completely weathered			VSt-H				PQTT				100				
			Gravelly, silty SAND; orange-brown. Moist; well sorted; sand is fine to coarse; gravel is fine to medium, angular to subrounded, quartz and schist; completely weathered Gravelly, sandy SILT; orange-brown and grey. Firm, moist, non-plastic; sand is fine to coarse; gravel is fine to medium, angular to subrounded, quartz and schist; completely weathered		M	F				PQTT				95				
			Highly weathered, light brown, thinly to moderately thickly bedded SILTSTONE; extremely weak; no defects. Soil description: SILT, minor clay; hard Moderately weathered, dark grey, thinly bedded SILTSTONE; extremely to very weak; no defects; trace to minor lignite Moderately weathered, light grey, fine to coarse grained SANDSTONE; very weak; no defects Moderately weathered, black, LIGNITE; very weak, no defects Slightly weathered, light grey and grey, thinly to moderately thickly bedded, fine to medium grained SANDSTONE; very weak; no defects; occasional lignite layers 8.60 - 8.85 m: fine to coarse sand 8.99 - 9.02 m: 30 mm lignite							PQTT				100	83			
										PQTT				100	90			
										PQTT								
Notes and Comments: End of Hole @ 60.60m, Target Depth. 0.0 - 10.6 m PQTT coring 10.6 - 60.6 m wash drilling Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level										
				Contractor: Speight Drilling		Equipment: Track mounted rig		Date						Time	Reading (mbgl)	Hole depth (mbgl)		
				Shear Vane Id:														

<div></div> <div>Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 2/11/2019 Completed: 4/11/2019</div>										Hole No. : BH202 Sheet : 2 of 7 Hole Length : 60.60m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS									
Easting: 396181 RL: 144					Northing: 787498 Datum: NZVD2016					System: TAIETM2000									
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SQR RQR (%)	Defect Spacing (mm)	Instrumentation Installation	Water level		
			9.84 - 9.89 m: 50 mm lignite Slightly weathered, light grey and grey, thinly to moderately thickly bedded, fine to medium grained SANDSTONE; very weak; no defects; occasional lignite layers (<i>continued from layer starting at 8.5m</i>) 10.30 - 10.45 m: 150 mm lignite 10.60 m to 60.60 m: Wash drilled	HENLEY BRECCIA						PQTT		SW		100 90					
10.6																			
11																			
11.33																			
12																			
12.132																			
13																			
13.131																			
14																			
14.130																			
15																			
15.129																			
16																			
16.128																			
17																			
17.127																			
18																			
18.126																			
19																			
19.125																			
20																			
20.124																			

Notes and Comments:				Inclination: Vertical		Orientation:		Ground Water Level			
End of Hole @ 60.60m, Target Depth.				Contractor: Speight Drilling				Date	Time	Reading (mbgl)	Hole depth (mbgl)
0.0 - 10.6 m PQTT coring				Equipment: Track mounted rig							
10.6 - 60.6 m wash drilling				Shear Vane Id:							
Refer to explanation sheets for abbreviation and symbols											

Notes and Comments:

End of Hole @ 60.60m, Target Depth.

0.0 - 10.6 m PQTT coring
10.6 - 60.6 m wash drilling

Refer to explanation sheets for abbreviation and symbols

Inclination: Vertical

Orientation:

Ground Water Level

Contractor: Speight Drilling

Equipment: Track mounted rig


Shear Vane Id:

Date


Time


Reading (mbgl)

Hole depth (mbgl)


			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 2/11/2019 Completed: 4/11/2019						Hole No. : BH202 Sheet : 3 of 7 Hole Length : 60.60m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS								
Easting: 396181 Northing: 787498 System: TAIETM2000 RL: 144 Datum: NZVD2016																	
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR / SCR / RQR (%)	Defect / Spacing (mm)	Instrumentation	Water level
			10.60 m to 60.60 m: Wash drilled (continued from layer starting at 10.6m)	HENLEY BRECCIA						Wash drilling							
123	21																20
122	22																21
121	23																22
120	24																23
119	25																24
118	26																25
117	27																26
116	28																27
115	29																28
114																	29
																	30

Notes and Comments: End of Hole @ 60.60m, Target Depth. 0.0 - 10.6 m PQTT coring 10.6 - 60.6 m wash drilling Refer to explanation sheets for abbreviation and symbols			Inclination: Vertical Orientation:		Ground Water Level			
			Contractor: Speight Drilling		Date	Time	Reading (mbgl)	Hole depth (mbgl)
			Equipment: Track mounted rig					
Shear Vane Id:								


			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 2/11/2019 Completed: 4/11/2019						Hole No. : BH202 Sheet : 4 of 7 Hole Length : 60.60m Scale @ A4 : 1:50								
Easting: 396181 Northing: 787498 System: TAIETM2000 RL: 144 Datum: NZVD2016									Logged : MF Processed : MF Checked : JHS								
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR / SCR / RQR (%)	Defect	Instrumentation	Water level
			10.60 m to 60.60 m: Wash drilled (continued from layer starting at 10.6m)	HENLEY BRECCIA						Wash drilling							
113	31																30
112	32																31
111	33																32
110	34																33
109	35																34
108	36																35
107	37																36
106	38																37
105	39																38
104	40																39
Notes and Comments: End of Hole @ 60.60m, Target Depth. 0.0 - 10.6 m PQTT coring 10.6 - 60.6 m wash drilling Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation: Contractor: Speight Drilling Equipment: Track mounted rig Shear Vane Id:				Ground Water Level Date Time Reading (mbgl) Hole depth (mbgl)									

		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 2/11/2019 Completed: 4/11/2019						Hole No. : BH202 Sheet : 5 of 7 Hole Length : 60.60m Scale @ A4 : 1:50										
		Easting: 396181 Northing: 787498 System: TAIETM2000 RL: 144 Datum: NZVD2016						Logged : MF Processed : MF Checked : JHS										
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR / SCR / RQR (%)	Defect	Spacing (mm)	Instrumentation	Water level
			10.60 m to 60.60 m: Wash drilled (continued from layer starting at 10.6m)	HENLEY BRECCIA						Wash drilling								
103	41																	40
																		41
102	42																	42
																		43
101	43																	44
																		45
100	44																	46
																		47
99	45																	48
																		49
98	46																	50
97	47																	
96	48																	
95	49																	
94	50																	

Notes and Comments: End of Hole @ 60.60m, Target Depth. 0.0 - 10.6 m PQTT coring 10.6 - 60.6 m wash drilling Refer to explanation sheets for abbreviation and symbols		Inclination: Vertical Orientation:		Ground Water Level							
		Contractor: Speight Drilling Equipment: Track mounted rig Shear Vane Id:		<table border="1"> <tr> <th>Date</th> <th>Time</th> <th>Reading (mbgl)</th> <th>Hole depth (mbgl)</th> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </table>		Date	Time	Reading (mbgl)	Hole depth (mbgl)		
Date	Time	Reading (mbgl)	Hole depth (mbgl)								

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 2/11/2019 Completed: 4/11/2019						Hole No. : BH202 Sheet : 6 of 7 Hole Length : 60.60m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS								
Easting: 396181 Northing: 787498 System: TAIETM2000 RL: 144 Datum: NZVD2016																	
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR / SCR / RQR (%)	Defect	Instrumentation	Water level
			10.60 m to 60.60 m: Wash drilled (continued from layer starting at 10.6m)	HENLEY BRECCIA						Wash drilling							
51																	51
52																	52
53																	53
54																	54
55																	55
56																	56
57																	57
58																	58
59																	59
60																	60

Notes and Comments: End of Hole @ 60.60m, Target Depth. 0.0 - 10.6 m PQTT coring 10.6 - 60.6 m wash drilling Refer to explanation sheets for abbreviation and symbols		Inclination: Vertical Orientation:		Ground Water Level			
		Contractor: Speight Drilling		Date	Time	Reading (mbgl)	Hole depth (mbgl)
		Equipment: Track mounted rig					
		Shear Vane Id:					


		Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southern Boundary Job Number: 12506381 Commenced: 2/11/2019 Completed: 4/11/2019						Hole No. : BH202 Sheet : 7 of 7 Hole Length : 60.60m Scale @ A4 : 1:50									
		Easting: 396181 Northing: 787498 System: TAIETM2000 RL: 144 Datum: NZVD2016						Logged : MF Processed : MF Checked : JHS									
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
			10.60 m to 60.60 m: Wash drilled (<i>continued from layer starting at 10.6m</i>)														
			End of Hole @ 60.60m, Target Depth.														
61																	61
62																	62
63																	63
64																	64
65																	65
66																	66
67																	67
68																	68
69																	69
70																	70

Notes and Comments: End of Hole @ 60.60m, Target Depth. 0.0 - 10.6 m PQTT coring 10.6 - 60.6 m wash drilling Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation:		Ground Water Level			
				Contractor: Speight Drilling Equipment: Track mounted rig Shear Vane Id:		Date	Time	Reading (mbgl)	Hole depth (mbgl)

Report of Photographs

Site Identification: BH202

Project	Waste Futures WS3 – Smooth Hill	Commenced	02/11/2019	Completed	04/11/2019
Site	Southern Boundary	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 10.6 m		



Box 1 of 4: 0.00 m to 2.30 m



Box 2 of 4: 2.30 m to 6.10 m


Report of Photographs

Site Identification: BH202

Project	Waste Futures WS3 – Smooth Hill	Commenced	02/11/2019	Completed	04/11/2019
Site	Southern Boundary	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 10.6 m		



Box 3 of 4: 6.10 m to 8.30 m



Box 4 of 4: 8.30 m to 10.60 m





Report of Photographs

Site Identification: BH202

Project	Waste Futures WS3 – Smooth Hill	Commenced	02/11/2019	Completed	04/11/2019
Site	Southern Boundary	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 10.6 m		

10.60 m to 60.60 m (EOH) – Wash drilled, no core recovered



<div></div> <div>Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Southwest Boundary Job Number: 12506381 Commenced: 7/11/2019 Completed: 7/11/2019</div>				<div>Hole No. : BH203 Sheet : 2 of 2 Hole Length : 19.70m Scale @ A4 : 1:50</div> <div>Logged : MF Processed : MF Checked : JHS</div>													
Easting: 395779 RL: 182		Northing: 787672 Datum: NZVD2009		System: TAIETM2000													
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
			Moderately weathered, orange-brown, very thinly to moderately thickly bedded SILTSTONE; very weak; no defects; moderately widely spaced lignite layers 5-20 mm thick (continued from layer starting at 7.5m) 10.00 - 10.10 m: fine SANDSTONE	HENLEY BRECCIA						PQTT		SW		100 87			
			Unweathered, light grey, laminated to moderately thickly bedded, fine grained SANDSTONE; very weak; no defects; moderately widely spaced lignite layers 5-30 mm thick							PQTT				100 53			
										PQTT				100 100			
			14.45 - 14.55 m: grades into BRECCIA Unweathered, light grey, BRECCIA; weak to moderately strong; no defects; clast supported; matrix is fine to coarse sand; clasts are fine, quartz and schist, angular to subangular gravel							PQTT		UW		100 81			
			Unweathered, light grey, laminated to moderately thickly bedded, fine grained SANDSTONE; very weak to weak; no defects 16.00 - 16.15 m: moderately strong							PQTT				100 92			
			17.30 - 17.60 m: grades into BRECCIA							PQTT			97 75				
			Slightly weathered, light grey and white, BRECCIA; moderately strong to strong; no defects; clast supported; matrix is fine to coarse sand; clasts are fine to coarse, angular to subrounded, quartz and schist gravel							PQTT		SW		83 19			
			End of Hole @ 19.70m, Target Depth.														
Notes and Comments: End of Hole @ 19.70m, Target Depth. Groundwater not encountered Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical Orientation: Contractor: Speight Drilling Equipment: Track mounted rig Shear Vane Id:				Ground Water Level Date Time Reading (mbgl) Hole depth (mbgl)									

Report of Photographs

Site Identification: BH203

Project	Waste Futures WS3 – Smooth Hill	Commenced	07/11/2019	Completed	07/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 19.7 m		



0.00 m to 2.30 m



2.30 m to 4.60 m

Report of Photographs

Site Identification: BH203

Project	Waste Futures WS3 – Smooth Hill	Commenced	07/11/2019	Completed	07/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m to 19.7 m		



4.60 m to 6.90 m




6.90 m to 9.20 m

Report of Photographs

Site Identification: BH203

Project	Waste Futures WS3 – Smooth Hill	Commenced	07/11/2019	Completed	07/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m to 19.7 m		



9.20 m to 11.30 m




11.30 m to 13.40 m

Report of Photographs

Site Identification: BH203

Project	Waste Futures WS3 – Smooth Hill	Commenced	07/11/2019	Completed	07/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m to 19.7 m		



13.40 m to 15.60 m



15.60 m to 17.90 m


Report of Photographs

Site Identification: BH203

Project	Waste Futures WS3 – Smooth Hill	Commenced	07/11/2019	Completed	07/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m to 19.7 m		



17.90 m to 19.70 m (EOH)

			Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Western Boundary Job Number: 12506381 Commenced: 24/10/2019 Completed: 24/10/2019						Hole No. : BH209 Sheet : 1 of 1 Hole Length : 10.00m Scale @ A4 : 1:50 Logged : MF Processed : MF Checked : JHS								
Easting: 395775 Northing: 788148 System: RL: 132 Datum:																	
RL (m)	Depth (m)	Graphic	Material Description	Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect	Instrumentation	Water level
							Number / Type	Result									
	0		Intermixed: clayey SILT, sandy SILT, and SILT with minor clay; grey and brown. Soft to firm, moist to wet, low to high plasticity; wood fragments throughout (FILL)	FILL	M-W	S-F											
	0.8		SILT, minor clay, trace fine sand; light grey and orange-brown. Very stiff, moist, low plasticity; trace fine gravel sized iron oxide nodules (LOESS) 0.80 - 3.15 m: grey-brown and orange-brown	LOESS	M	VSt				PQTT				92			
	1																
	2													100			
	3																
	3.15		Gravelly SILT; grey, cream and brown. Very stiff to hard, dry to moist, non-plastic; gravel is fine to medium, rounded to subangular quartz and schist; highly weathered (Henley Breccia)		D-M	VSt-H				PQTT				96			
	3.6		SILT, minor to some clay; grey with orange-brown streaks. Firm to stiff, moist, high plasticity		M	F-St						HW					
	4		Moderately weathered, orange-brown, very thinly to moderately thickly bedded fine-grained SANDSTONE; very weak; no defects							PQTT				100			
	4.80		4.80 - 5.30 m: light grey											86			
	5																
	5.3		Moderately weathered, brown and orange-brown CONGLOMERATE; extremely weak; no defects; matrix supported; clasts are fine to medium, rounded to subangular, quartz and schist gravel; silty sand matrix. Soil description: gravelly silty sand							PQTT		MW		100			
	5.9		Moderately weathered, orange-brown, very thinly to moderately thickly bedded fine-grained SANDSTONE; very weak; no defects											60			
	6																
	6.65		Slightly weathered, grey, laminated to moderately thinly bedded fine-grained SANDSTONE; very weak; no defects							PQTT				100			
	7													100			
	7.3		Slightly weathered, brown with occasional orange-brown and white, moderately thinly to moderately thickly bedded, fine to medium-grained SANDSTONE; very weak; no defects; minor fine quartz and schist gravel														
	7.8		Slightly weathered, brown and orange-brown CONGLOMERATE; extremely weak; no defects; clast supported; silty sand matrix; clasts are fine to coarse, rounded to subangular, quartz and schist gravel. Soil description: silty, sandy, fine to coarse gravel							PQTT		SW		100			
	8													0			
	9																
	9.4													94			
	10		End of Hole @ 10.00m, Target Depth.														
Notes and Comments: End of Hole @ 10.00m, Target Depth. Groundwater not encountered Refer to explanation sheets for abbreviation and symbols				Inclination: Vertical		Orientation:		Ground Water Level									
				Contractor: Speight Drilling				Date	Time	Reading (mbgl)	Hole depth (mbgl)						
				Equipment: Tracked Rig													
				Shear Vane Id:													

Report of Photographs

Site Identification: BH209

Project	Waste Futures WS3 – Smooth Hill	Commenced	24/10/2019	Completed	24/10/2019
Site	Western Boundary	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 10.0 m		



Box 1 of 5: 0.00 m to 2.40 m



Box 2 of 5: 2.40 m to 4.70 m

Report of Photographs

Site Identification: BH209

Project	Waste Futures WS3 – Smooth Hill	Commenced	24/10/2019	Completed	24/10/2019
Site	Southern Boundary	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 10.0 m		



Box 3 of 5: 4.70 m to 7.15 m




Box 4 of 5: 7.15 m to 9.20 m




Report of Photographs

Site Identification: BH209


Project	Waste Futures WS3 – Smooth Hill	Commenced	24/10/2019	Completed	24/10/2019
Site	Southern Boundary	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 10.0 m		



Box 5 of 5: 9.20 m to 10.0 m (EOH)

<div></div> <div>Project : Smooth Hill Landfill Consenting Client : Dunedin City Council Site : Eastern gully base Job Number: 12506381 Commenced: 4/11/2019 Completed: 6/11/2019</div>										<div>Hole No. : BH211</div> <div>Sheet : 1 of 3 Hole Length : 25.20m Scale @ A4 : 1:50</div> <div>Logged : MF Processed : MF Checked : JHS</div>															
Easting: 396598 RL: 107					Northing: 787965 Datum: NZVD2009					System: TAIETM2000															
<div><div>RL (m)</div><div>Depth (m)</div><div>Graphic</div></div>										Material Description		Geological Unit	Moisture condition	Consistency / Relative density	Sample		Casing	Method	Flush Return (%)	Weathering	Estimated Strength (MPa)	TCR SCR RQD (%)	Defect Spacing (mm)	Instrumentation Installation	Water level
															Number / Type	Result									
0.00 - 0.35 m: CORE LOSS (inferred at top of run)										FILL	M	St-VSt													
SILT, minor fine to medium sand, trace clay; grey, orange-brown and dark grey intermixed. Stiff to very stiff, moist, low plasticity (FILL)										LOESS	M	VSt		PQTT				78							
SILT, trace to minor fine to medium sand; grey and orange-brown. Very stiff, moist, low plasticity; trace to minor iron-oxide nodules (LOESS)																									
1.60 - 1.80 m: CORE LOSS (inferred depth)																									
SILT (continued from 0.7 m)																									
Sandy SILT, minor fine gravel; orange-brown and grey. Very stiff to hard, moist, non-plastic; sand is fine to medium; gravel is angular to rounded quartz and schist; completely weathered breccia (HENLEY BRECCIA)										HENLEY BRECCIA	M	VSt-H		PQTT				75							
2.40 - 2.80 m: firm to stiff												F-St													
2.80 - 3.20 m: very stiff												VSt		PQTT				62							
3.20 - 3.70 m: CORE LOSS																									
SILT; dark grey. Firm to stiff, moist, low plasticity; completely weathered siltstone										M	F-St		PQTT					100							
Gravelly SAND; grey. Moist; sand is fine to coarse; gravel is fine, angular to subrounded, quartz and schist; completely weathered breccia										M	VSt-H														
4.60 - 5.20 m: CORE LOSS																									
Gravelly SAND (continued from 4.2 m)										M	VSt-H		PQTT					59							
Highly weathered, orange-brown and grey, moderately thickly bedded BRECCIA; extremely weak; no defects; matrix supported; matrix is fine to coarse sand; clasts are fine to medium, angular to rounded, quartz and schist gravel. Soil description: gravelly sand																	25								
Slightly weathered, light grey and white, moderately thickly bedded SILTSTONE; very weak to weak; no defects																									
Slightly weathered, light grey and white BRECCIA; weak to moderately strong; no defects; clast supported; matrix is fine to coarse sand; clasts are fine to coarse, angular to subrounded, quartz and schist gravel													PQTT				100								
																	93								
													PQTT				100								
																	70								
																</									






Report of Photographs

Site Identification: BH211

Project	Waste Futures WS3 – Smooth Hill	Commenced	04/11/2019	Completed	06/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m – 25.2 m		



0.00 m to 2.80 m



2.80 m to 6.20 m

Report of Photographs

Site Identification: BH211

Project	Waste Futures WS3 – Smooth Hill	Commenced	04/11/2019	Completed	06/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m to 25.2 m		



6.20 m to 8.50 m



8.50 m to 10.70 m

Report of Photographs

Site Identification: BH211

Project	Waste Futures WS3 – Smooth Hill	Commenced	04/11/2019	Completed	06/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m to 25.2 m		



10.70 m to 12.80 m




12.80 m to 14.90 m


Report of Photographs

Site Identification: BH211

Project	Waste Futures WS3 – Smooth Hill	Commenced	04/11/2019	Completed	06/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m to 25.2 m		



14.90 m to 17.20 m




17.20 m to 19.50 m


Report of Photographs

Site Identification: BH211

Project	Waste Futures WS3 – Smooth Hill	Commenced	04/11/2019	Completed	06/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m to 25.2 m		



19.50 m to 21.70 m



21.70 m to 23.90 m



Report of Photographs

Site Identification: BH211

Project	Waste Futures WS3 – Smooth Hill	Commenced	04/11/2019	Completed	06/11/2019
Site	Smooth Hill	Logged By	MF		
Job #	12506381	Checked By			
Client	Dunedin City Council	Core Depth	0.0 m to 25.2 m		




23.90 m to 25.20 m (EOH)

Appendix C – Laboratory Testing Results



TEST REPORT: DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – SILT with some sand, minor gravel and minor clay	Client Job No:	12506381
Sample Source:	TP10/01	Sample Depth:	2.2m to 3.6m
Date & Time Sampled:	10-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Test Pit / Borehole *	Date Received:	26-Jun-19



PARTICLE SIZE ANALYSIS & HYDROMETER ANALYSIS RESULTS - NZS 4402:1986, Test 2.8.1 & 2.8.4					
Description	Fraction Range	% Within Range	Description	Fraction Range	% Within Range
Coarse Gravel	60.0mm to 20.0mm	2	Fine Sand	200 µm to 60 µm	9
Medium Gravel	20.0mm to 6.0mm	1	Coarse Silt	60 µm to 20 µm	26
Fine Gravel	6.0mm to 2.00 mm	3	Medium Silt	20 µm to 6 µm	32
Coarse Sand	2.00mm to 600 µm	3	Fine Silt	6 µm to 2 µm	14
Medium Sand	600 µm to 200 µm	1	Clay	< 2 µm	9

WATER CONTENT & PLASTICITY INDEX RESULTS - NZS 4402:1986, Test 2.1, 2.2, 2.3 & 2.4	
Water Content: ("All In" As Received)	15.5 %
Liquid Limit: (LL)	39
Plastic Limit: (PL)	28
Plasticity Index: (PI)	11
Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.	

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 4 to 15-Jul-19

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434

Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing


"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT: DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – SILT with some sand, minor gravel and minor clay	Client Job No:	12506381
Sample Source:	TP10/01	Sample Depth:	2.2m to 3.6m
Date & Time Sampled:	10-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Test Pit / Borehole *	Date Received:	26-Jun-19

WATER CONTENT & NZ STANDARD COMPACTION - NZS 4402:1986, Test 2.1 & 4.1.1



Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 4 to 15-Jul-19

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434



TEST REPORT: DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – SILT with some sand, minor gravel and minor clay	Client Job No:	12506381
Sample Source:	TP10/01	Sample Depth:	2.2m to 3.6m
Date & Time Sampled:	10-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Test Pit / Borehole *	Date Received:	26-Jun-19

PINHOLE DISPERSION TEST: ASTM D4647-13e1			
Head (mm)	Elapsed Time (min)	Flow Rate (ml/s)	Colour of Outflow (Cloudiness)
50	1	0.25	Slightly Dark
50	5	0.27	Moderately Dark
50	10	0.31	Dark
Diameter of Hole at Start of Test:			1.0mm
Diameter of Hole at End of Test:			≈ 2.0mm (4.0mm at exit)
Water Content Prior to Test:			16.2 %
Dry Density of Sample Tested:			1.63 t/m ³
Pinhole Dispersion Classification – Method B:			Dispersive (D)
CRUMB TEST: ASTM D6572-13e2 (Method B)			
Elapsed Time	Estimated Slaking	Observations Recorded	
2 min	≈ 50 %	No colloidal cloud	
1 hr	≈ 100%	Dense colloidal cloud over	
6 hr	≈ 100 %	Moderate colloidal cloud over	
Crumb Test Classification:		Grade 4 (Highly Dispersive)	
<i>Note:</i>			
<ul style="list-style-type: none">Distilled water was used in the pinhole dispersion and crumb test. Both tests were carried out on remoulded samples.The pinhole dispersion sample was compacted to 95% NZ standard compaction.Photograph at completion of the crumb test.The sample tested was the fraction passing the 2.00mm sieve.			

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 4 to 15-Jul-19

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434


Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT: DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – Silty CLAY with minor sand and trace of gravel	Client Job No:	12506381
Sample Source:	BH5 @ 0.0m to 1.2m & BH7 @ 0.0m to 1.4m	Sample Depth:	Combined (0.0m to 1.4m)
Date & Time Sampled:	21-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Test Pit / Borehole *	Date Received:	26-Jun-19



PARTICLE SIZE ANALYSIS & HYDROMETER ANALYSIS RESULTS - NZS 4402:1986, Test 2.8.1 & 2.8.4					
Description	Fraction Range	% Within Range	Description	Fraction Range	% Within Range
Coarse Gravel	60.0mm to 20.0mm	-	Fine Sand	200 µm to 60 µm	8
Medium Gravel	20.0mm to 6.0mm	-	Coarse Silt	60 µm to 20 µm	27
Fine Gravel	6.0mm to 2.00 mm	1	Medium Silt	20 µm to 6 µm	23
Coarse Sand	2.00mm to 600 µm	1	Fine Silt	6 µm to 2 µm	10
Medium Sand	600 µm to 200 µm	1	Clay	< 2 µm	29

WATER CONTENT & PLASTICITY INDEX RESULTS - NZS 4402:1986, Test 2.1, 2.2, 2.3 & 2.4	
Water Content: ("All In" As Received)	23.6 %
Liquid Limit: (LL)	42
Plastic Limit: (PL)	23
Plasticity Index: (PI)	19
Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.	

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 4 to 15-Jul-19

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation




Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT: DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – Silty CLAY with minor sand and trace of gravel	Client Job No:	12506381
Sample Source:	BH5 @ 0.0m to 1.2m & BH7 @ 0.0m to 1.4m	Sample Depth:	Combined (0.0m to 1.4m)
Date & Time Sampled:	21-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Test Pit / Borehole *	Date Received:	26-Jun-19



Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 4 to 15-Jul-19

Checked By:


Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434



TEST REPORT: DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – Silty CLAY with minor sand and trace of gravel	Client Job No:	12506381
Sample Source:	BH5 @ 0.0m to 1.2m & BH7 @ 0.0m to 1.4m	Sample Depth:	Combined (0.0m to 1.4m)
Date & Time Sampled:	21-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Test Pit / Borehole *	Date Received:	26-Jun-19

PINHOLE DISPERSION TEST: ASTM D4647-13e1			
Head (mm)	Elapsed Time (min)	Flow Rate (ml/s)	Colour of Outflow (Cloudiness)
50	1	0.25	Barely Visible
50	5	0.27	Moderately Dark
50	10	0.49	Very Dark
Diameter of Hole at Start of Test:			1.0mm
Diameter of Hole at End of Test:			≈ 2.0mm
Water Content Prior to Test:			17.8 %
Dry Density of Sample Tested:			1.62 t/m ³
Pinhole Dispersion Classification – Method A:			Dispersive (D)
CRUMB TEST: ASTM D6572-13e2 (Method B)			
Elapsed Time	Estimated Slaking	Observations Recorded	
2 min	≈ 20 %	No colloidal cloud	
1 hr	≈ 100%	Dense colloidal cloud over	
6 hr	≈ 100 %	Dense colloidal cloud over	
Crumb Test Classification:		Grade 4 (Highly Dispersive)	
Note: <ul style="list-style-type: none">Distilled water was used in the pinhole dispersion and crumb test. Both tests were carried out on remoulded samples.The pinhole dispersion sample was compacted to 95% NZ standard compaction.Photograph at completion of the crumb test.The sample tested was the fraction passing the 2.00mm sieve.			

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 4 to 15-Jul-19

Checked By: 

Approved Signatory


A.P. Julius
Laboratory Manager

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434

Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT – SMOOTH HILL LANDFILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – SILT with some sand, minor gravel and minor clay	Client Job No:	12506381
Sample Source:	TP10/01	Sample Depth:	2.2m to 3.6m
Date & Time Sampled:	10-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Test Pit	Date Received:	26-Jun-19

CONSTANT HEAD PERMEABILITY TEST IN A TRIAXIAL CELL – ASTM D5084-16a			
Cell Pressure: (kPa)	610	Compaction:	95% NZ Standard
Saturation Back Pressure: (kPa)	600	Solid Density: (t/m ³)	2.67
Effective Confining Pressure: (kPa)	10	Temperature During Test: (°C)	20.5
Saturation by Pore Pressure Response: (B Value)	0.98	Permeant Liquid Used:	De-aired Tap Water
Sample Status:	Initial	Final	
Sample Dimensions: (mm)	105.02 ϕ x 115.29	106.02 ϕ x 117.05	
Bulk Density: (t/m ³)	1.92	1.98	
Water Content: (%)	18.0	26.3	
Dry Density: (t/m ³)	1.62	1.57	
Saturation By Calculation: (%)	75	100	
Void Ratio: (e)	0.65	0.70	
Constant Head: (kPa)	3.0	5.0	
Hydraulic Conductivity: (k ₂₀)	2.9 x 10 ⁻⁸ m/s	3.2 x 10 ⁻⁸ m/s	

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample description based on NZ Geotechnical Society Guidelines 2005 and sampling.
- This report may not be reproduced except in full.

Tested By: N.P. Danischewski

Date: 11-Jul-19 to 3-Aug-19

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434

Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT – SMOOTH HILL LANDFILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – SILT with some sand, minor gravel and minor clay	Client Job No:	12506381
Sample Source:	TP10/01	Sample Depth:	2.2m to 3.6m
Date & Time Sampled:	10-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Test Pit	Date Received:	26-Jun-19

CONSTANT HEAD PERMEABILITY TEST IN A TRIAXIAL CELL – ASTM D5084-16a			
Cell Pressure: (kPa)	727	Compaction:	95% NZ Standard
Saturation Back Pressure: (kPa)	650	Solid Density: (t/m ³)	2.67
Effective Confining Pressure: (kPa)	77	Temperature During Test: (°C)	18.0
Saturation by Pore Pressure Response: (B Value)	0.99	Permeant Liquid Used:	De-aired Tap Water
Sample Status:	Initial	Final	
Sample Dimensions: (mm)	105.04 ϕ x 115.72	105.27 ϕ x 116.26	
Bulk Density: (t/m ³)	1.89	1.99	
Water Content: (%)	17.8	24.0	
Dry Density: (t/m ³)	1.60	1.61	
Saturation By Calculation: (%)	71	97	
Void Ratio: (e)	0.67	0.66	
Constant Head: (kPa)	3.0	10.0	
Hydraulic Conductivity: (k ₂₀)	2.7 x 10 ⁻⁸ m/s	2.8 x 10 ⁻⁸ m/s	

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample description based on NZ Geotechnical Society Guidelines 2005 and sampling.
- This report may not be reproduced except in full.

Tested By: N.P. Danischewski

Date: 11-Jul-19 to 3-Aug-19

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434

Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT – SMOOTH HILL LANDFILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – Silty CLAY with minor sand and trace of gravel	Client Job No:	12506381
Sample Source:	BH5 @ 0.0m to 1.2m & BH7 @ 0.0m to 1.4m	Sample Depth:	Combined (0.0m to 1.4m)
Date & Time Sampled:	21-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Borehole	Date Received:	26-Jun-19

CONSTANT HEAD PERMEABILITY TEST IN A TRIAXIAL CELL – ASTM D5084-16a			
Cell Pressure: (kPa)	460	Compaction:	95% NZ Standard
Saturation Back Pressure: (kPa)	450	Solid Density: (t/m ³)	2.71
Effective Confining Pressure: (kPa)	10	Temperature During Test: (°C)	20.0
Saturation by Pore Pressure Response: (B Value)	0.97	Permeant Liquid Used:	De-aired Tap Water
Sample Status:	Initial	Final	
Sample Dimensions: (mm)	105.01 ϕ x 115.08	106.2 ϕ x 117.40	
Bulk Density: (t/m ³)	1.94	1.96	
Water Content: (%)	18.7	25.9	
Dry Density: (t/m ³)	1.63	1.56	
Saturation By Calculation: (%)	77	95	
Void Ratio: (e)	0.66	0.74	
Constant Head: (kPa)	3.0	5.0	
Hydraulic Conductivity: (k ₂₀)	1.7 x 10 ⁻⁹ m/s	2.1 x 10 ⁻⁹ m/s	

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample description based on NZ Geotechnical Society Guidelines 2005 and sampling.
- This report may not be reproduced except in full.

Tested By: N.P. Danischewski

Date: 11-Jul-19 to 3-Aug-19

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation





TEST REPORT – SMOOTH HILL LANDFILL INVESTIGATIONS

Client Details:	GHD, Level 3, 138 Victoria Street, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess – Silty CLAY with minor sand and trace of gravel	Client Job No:	12506381
Sample Source:	BH5 @ 0.0m to 1.2m & BH7 @ 0.0m to 1.4m	Sample Depth:	Combined (0.0m to 1.4m)
Date & Time Sampled:	21-Jun-19	Sampled By:	M. Fitzmaurice
Sample Method:	Borehole	Date Received:	26-Jun-19

CONSTANT HEAD PERMEABILITY TEST IN A TRIAXIAL CELL – ASTM D5084-16a			
Cell Pressure: (kPa)	527	Compaction:	95% NZ Standard
Saturation Back Pressure: (kPa)	450	Solid Density: (t/m ³)	2.71
Effective Confining Pressure: (kPa)	77	Temperature During Test: (°C)	19.5
Saturation by Pore Pressure Response: (B Value)	0.97	Permeant Liquid Used:	De-aired Tap Water
Sample Status:	Initial	Final	
Sample Dimensions: (mm)	104.96 ϕ x 114.97	104.52 ϕ x 115.45	
Bulk Density: (t/m ³)	1.94	2.03	
Water Content: (%)	18.7	24.3	
Dry Density: (t/m ³)	1.63	1.64	
Saturation By Calculation: (%)	77	100	
Void Ratio: (e)	0.66	0.66	
Constant Head: (kPa)	3.0	5.0	
Hydraulic Conductivity: (k ₂₀)	5.6 x 10 ⁻¹⁰ m/s	5.3 x 10 ⁻¹⁰ m/s	

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample description based on NZ Geotechnical Society Guidelines 2005 and sampling.
- This report may not be reproduced except in full.

Tested By: N.P. Danischewski

Date: 11-Jul-19 to 3-Aug-19

Checked By:

Approved Signatory

A.P. Julius
Laboratory Manager

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation






TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Client Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Received:	6-Dec-19

LIME DEMAND TEST – NSW Transport; Roads & Maritime Services Test Method T144 (Not IANZ Accredited)								
Sample Description:	Loess - Natural Soil Sub-sample #1				Loess - Natural Soil Sub-sample #2			
% Passing 2.36mm Test Sieve:	99.5%				99.5%			
Lime Type:	Taylors Hydrated Lime				Taylors Hydrated Lime			
pH of Lime Solution	12.60				12.63			
% Added Lime: (by dry mass)	0%	1%	2%	3%	4%	5%	6%	7%
pH Sub-sample #1:	5.12	10.15	12.12	12.42	12.46	12.49	12.48	12.42
pH Sub-sample #2:	5.16	10.31	12.08	12.50	12.55	12.56	12.55	12.55



Note:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 9 to 17-Dec-19

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation



Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Client Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Received:	6-Dec-19

WATER CONTENT & PLASTICITY INDEX RESULTS - NZS 4402:1986, Test 2.1, 2.2, 2.3 & 2.4				
Sample Description:	Loess - Natural Soil			
Water Content: (As Received)	25.0 %			
Sub-sample ID	#1	#2	#3	#4
Liquid Limit: (LL)	41	41	41	41
Plastic Limit: (PL)	25	25	25	25
Plasticity Index: (PI)	16	16	16	16
Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.				

Note:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 9 to 17-Dec-19

Checked By:

Approved Signatory

A.P. Julius
Laboratory Manager

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation





TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Client Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Received:	6-Dec-19

PLASTICITY INDEX RESULTS - NZS 4402:1986, Tests 2.2, 2.3 & 2.4				
Sample Description:	Loess - Natural Soil			
Sub-sample ID:	#1	#2	#3	#4
Sample Additive (By Dry Mass)	2.5% Lime	2.5% Lime	3.0% Bentonite	3.0% Bentonite
Time Cured For:	1 day	7 days	1 day	7 days
Liquid Limit: (LL)	54	55	42	40
Plastic Limit: (PL)	30	32	23	23
Plasticity Index: (PI)	24	23	19	17
Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.				

Note:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 9 to 17-Jan-20

Checked By:

Approved Signatory

A.P. Julius
Laboratory Manager

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434

Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined – 2.5% Added Hydrated Lime (by dry mass)		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Received:	6-Dec-19

NZ STANDARD COMPACTION - NZS 4402:1986, Test 4.1.1 SHEAR STRENGTH RESULTS - NZGS 2001


% Retained: (+19.0mm Test Sieve)		0.0 %	
Maximum Dry Density:		1.64 t/m ³	
Optimum Water Content:		20.0 %	
Individual Results			
Water Content (%)	Dry Density (t/m ³)	Shear Strength (kPa)	
		Shear Strength	Residual Strength
15.0	1.599	UTP	UTP
17.2	1.622	UTP	UTP
18.7	1.636	UTP	UTP
20.8	1.637	UTP	UTP
22.2	1.621	> 210	-

Notes:

- The material was received in a natural state.
- The air voids lines were calculated from an assumed solid density of 2.70 t/m³.
- UTP = unable to penetrate.
- The material tested was whole soil.

The graph plots Dry Density (t/m³) on the y-axis (1.58 to 1.66) against Water Content (%) on the x-axis (12 to 28). A red dashed compaction curve peaks at 20.0% water content and 1.64 t/m³ dry density. A green line represents the 10% air voids line, and a blue dashed line represents the 5% air voids line. A black solid line represents the 0% air voids line. A box labeled '2.5% Added Lime' is positioned near the peak of the compaction curve. Shear strength data points are marked with open circles along the compaction curve.

Water Content (%)	Dry Density (t/m³)	Shear Strength (kPa)
15.0	1.599	UTP
17.2	1.622	UTP
18.7	1.636	UTP
20.8	1.637	UTP
22.2	1.621	> 210



General Notes:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: C. Fisher

Date: 24 to 29-Jan-20

Checked By:

All tests reported herein
have been performed in
accordance with the
scope of the
laboratory's
accreditation



Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined – 2.5% Added Hydrated Lime (by dry mass)		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Received:	6-Dec-19

NZ STANDARD COMPACTION - NZS 4402:1986, Test 4.1.1 SHEAR STRENGTH RESULTS - NZGS 2001


% Retained: (+19.0mm Test Sieve)		0.0 %	
Maximum Dry Density:		1.64 t/m ³	
Optimum Water Content:		20.0 %	
Individual Results			
Water Content (%)	Dry Density (t/m ³)	Shear Strength (kPa)	
		Shear Strength	Residual Strength
15.3	1.632	UTP	UTP
16.5	1.635	UTP	UTP
18.3	1.640	UTP	UTP
20.3	1.643	> 210	-
21.1	1.623	183	71

Notes:

- The material was received in a natural state.
- The air voids lines were calculated from an assumed solid density of 2.70 t/m³.
- UTP = unable to penetrate.
- The material tested was whole soil.

The graph plots Dry Density (t/m³) on the y-axis (1.61 to 1.65) against Water Content (%) on the x-axis (12 to 28). It features a red dashed compaction curve peaking at 20.3% water content (1.643 t/m³), a green line for 10% air voids, a blue dashed line for 5% air voids, and a black line for 0% air voids. A box labeled '2.5% Added Lime' is positioned near the peak of the compaction curve.

Water Content (%)	Dry Density (t/m³)	Curve Type
15.3	1.632	Compaction
16.5	1.635	Compaction
18.3	1.640	Compaction
20.3	1.643	Compaction (Peak)
21.1	1.623	Compaction
17.5	1.650	10% Air Voids
19.0	1.615	10% Air Voids
20.5	1.645	5% Air Voids
21.5	1.615	5% Air Voids
23.5	1.650	0% Air Voids
24.8	1.615	0% Air Voids



General Notes:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: C. Fisher

Date: 24 to 29-Jan-20

Checked By:

All tests reported herein have been performed in accordance with the scope of the laboratory's accreditation



Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined – 3.0% Added Bentonite (by dry mass)		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Received:	6-Dec-19


NZ STANDARD COMPACTION - NZS 4402:1986, Test 4.1.1 SHEAR STRENGTH RESULTS - NZGS 2001			
% Retained: (+19.0mm Test Sieve)		0.0 %	
Maximum Dry Density:		1.67 t/m ³	
Optimum Water Content:		18.0 %	
Individual Results			
Water Content (%)	Dry Density (t/m ³)	Shear Strength (kPa)	
		Shear Strength	Residual Strength
14.6	1.637	UTP	UTP
17.1	1.669	> 210	-
18.2	1.675	> 210	-
19.7	1.668	> 210	-
20.7	1.661	183	123

Notes:

- The material was received in a natural state.
- The air voids lines were calculated from an assumed solid density of 2.70 t/m³.
- UTP = unable to penetrate.
- The material tested was whole soil.

The graph plots Dry Density (t/m³) on the y-axis (1.62 to 1.69) against Water Content (%) on the x-axis (10 to 27). A red dashed curve represents the compaction data, peaking at 18.2% water content and 1.675 t/m³. A green line marks the 10% air voids limit, a blue dashed line marks the 5% air voids limit, and a black line marks the 0% air voids limit. Shear strength data points are plotted as open circles, with a red dashed line connecting the peak and a green line connecting the base. A box labeled '3.0% Added Bentonite' is positioned near the peak of the compaction curve.

Water Content (%)	Dry Density (t/m³)	Shear Strength (kPa)	Residual Strength (kPa)
14.6	1.637	UTP	UTP
17.1	1.669	> 210	-
18.2	1.675	> 210	-
19.7	1.668	> 210	-
20.7	1.661	183	123



General Notes:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: C. Fisher

Date: 24 to 29-Jan-20

Checked By:

All tests reported herein
have been performed in
accordance with the
scope of the
laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434

Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."




TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined – 3.0% Added Bentonite (by dry mass)		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Received:	6-Dec-19

NZ STANDARD COMPACTION - NZS 4402:1986, Test 4.1.1 SHEAR STRENGTH RESULTS - NZGS 2001			
% Retained: (+19.0mm Test Sieve)		0.0 %	
Maximum Dry Density:		1.69 t/m ³	
Optimum Water Content:		19.0 %	
Individual Results			
Water Content (%)	Dry Density (t/m ³)	Shear Strength (kPa)	
		Shear Strength	Residual Strength
16.5	1.646	UTP	UTP
18.0	1.679	> 210	-
18.9	1.686	> 210	-
20.0	1.671	186	87
22.0	1.656	147	81
Notes:			
<ul style="list-style-type: none">• The material was received in a natural state.• The air voids lines were calculated from an assumed solid density of 2.70 t/m³.• UTP = unable to penetrate.• The material tested was whole soil.			

The graph plots Dry Density (t/m³) on the y-axis (ranging from 1.63 to 1.70) against Water Content (%) on the x-axis (ranging from 13 to 26). It features three compaction curves: a solid green line for 10% air voids, a dashed red line for 3.0% added bentonite, and a dashed blue line for 5% air voids. A solid black line represents the 0% air voids line. Shear strength data points are plotted as open circles: green circles for the 10% air voids curve, red circles for the 3.0% bentonite curve, and blue circles for the 5% air voids curve. A text box labeled '3.0% Added Bentonite' is positioned near the peak of the red dashed curve.

Water Content (%)	Dry Density (t/m³)	Shear Strength (kPa)	Residual Strength (kPa)
16.5	1.646	UTP	UTP
18.0	1.679	> 210	-
18.9	1.686	> 210	-
20.0	1.671	186	87
22.0	1.656	147	81



General Notes:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: C. Fisher

Date: 24 to 29-Jan-20

Checked By:

Approved Signatory

A.P. Julius
Laboratory Manager

All tests reported herein
have been performed in
accordance with the
scope of the
laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434



TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined – 2.5% Added Hydrated Lime (by dry mass) – 1 day curing		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Requested:	20-Jan-20

PINHOLE DISPERSION TEST: ASTM D4647-13e1


Head (mm)	Elapsed Time (min)	Flow Rate (ml/s)	Colour of Outflow (Cloudiness)
50	5	0.43	Completely Clear
50	10	0.44	Completely Clear
180	15	0.67	Completely Clear
380	20	0.95	Completely Clear
1020	25	1.82	Completely Clear

Diameter of Hole at Start of Test:	1.0 mm
Diameter of Hole at End of Test:	1.0 mm
Water Content Prior to Test:	20.0 %
Dry Density of Sample Tested:	1.56 t/m ³

Pinhole Dispersion Classification – Method A: (1 Day Curing)	ND1 (Non-Dispersive)
--------------------------------------------------------------	----------------------

CRUMB TEST: ASTM D6572-13e2 (Method B)

Elapsed Time	Estimated Slaking	Observations Recorded
2 min	< 2%	Clear – no colloidal cloud evident
1 hr	≈ 5%	Clear – no colloidal cloud evident
6 hr	≈ 5% - 10%	Clear – no colloidal cloud evident
Crumb Test Classification: (1 Day Curing)		Grade 1 (Non-Dispersive)



Note:

- Distilled water was used in the pinhole dispersion and crumb test. Both tests were carried out on remoulded samples.
- The pinhole dispersion sample was compacted to 95% NZ standard compaction.
- Photograph at completion of the crumb test.
- The sample tested was the fraction passing the 2.00mm sieve.

General Notes:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 25-Jan-20 to 7-Feb-20

Checked By:

All tests reported herein have been performed in accordance with the scope of the laboratory's accreditation




Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined – 2.5% Added Hydrated Lime (by dry mass) – 7 days curing		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Requested:	20-Jan-20

PINHOLE DISPERSION TEST: ASTM D4647-13e1			
Head (mm)	Elapsed Time (min)	Flow Rate (ml/s)	Colour of Outflow (Cloudiness)
50	5	0.30	Completely Clear
50	10	0.30	Completely Clear
180	15	0.60	Completely Clear
380	20	0.94	Completely Clear
1020	25	1.73	Completely Clear
Diameter of Hole at Start of Test:			1.0 mm
Diameter of Hole at End of Test:			1.0 mm
Water Content Prior to Test:			19.7 %
Dry Density of Sample Tested:			1.56 t/m ³
Pinhole Dispersion Classification – Method A: (7 Day Curing)			ND1 (Non-Dispersive)
CRUMB TEST: ASTM D6572-13e2 (Method B)			
Elapsed Time	Estimated Slaking	Observations Recorded	
2 min	< 1%	Clear – no colloidal cloud evident	
1 hr	≈ 30%	Clear – no colloidal cloud evident	
6 hr	≈ 60%	Clear – no colloidal cloud evident	
Crumb Test Classification: (7 Day Curing)		Grade 1 (Non-Dispersive)	
Note: <ul style="list-style-type: none">Distilled water was used in the pinhole dispersion and crumb test. Both tests were carried out on remoulded samples.The pinhole dispersion sample was compacted to 95% NZ standard compaction.Photograph at completion of the crumb test.The sample tested was the fraction passing the 2.00mm sieve.			

General Notes:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 25-Jan-20 to 7-Feb-20

Checked By:

All tests reported herein have been performed in accordance with the scope of the laboratory's accreditation



Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing


“Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee.”



TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined – 3.0% Added Bentonite (by dry mass) – 1 day curing		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Requested:	20-Jan-20

PINHOLE DISPERSION TEST: ASTM D4647-13e1			
Head (mm)	Elapsed Time (min)	Flow Rate (ml/s)	Colour of Outflow (Cloudiness)
50	1	0.50	Dark
50	3	1.23	Very Dark
50	5	2.23	Very Dark
Diameter of Hole at Start of Test:		1.0 mm	
Diameter of Hole at End of Test:		3.0 mm	
Water Content Prior to Test:		17.6 %	
Dry Density of Sample Tested:		1.60 t/m ³	
Pinhole Dispersion Classification – Method B: (1 Day Curing)		D (Dispersive)	

CRUMB TEST: ASTM D6572-13e2 (Method B)			
Elapsed Time	Estimated Slaking	Observations Recorded	
2 min	< 2%	Colloidal cloud evident around cube	
1 hr	≈ 55%	Heavy colloidal cloud ≈ 20mm deep covering entire bottom	
6 hr	≈ 80%	Heavy colloidal cloud ≈ 20mm deep covering entire bottom	
Crumb Test Classification: (1 Day Curing)		Grade 4 (Dispersive)	

Note:

- Distilled water was used in the pinhole dispersion and crumb test. Both tests were carried out on remoulded samples.
- The pinhole dispersion sample was compacted to 95% NZ standard compaction.
- Photograph at completion of the crumb test.
- The sample tested was the fraction passing the 2.00mm sieve.

General Notes:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 25-Jan-20 to 7-Feb-20

Checked By:

All tests reported herein have been performed in accordance with the scope of the laboratory's accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434

Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

“Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee.”



TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined – 3.0% Added Bentonite (by dry mass) – 7 days curing		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Requested:	20-Jan-20

PINHOLE DISPERSION TEST: ASTM D4647-13e1

Head (mm)	Elapsed Time (min)	Flow Rate (ml/s)	Colour of Outflow (Cloudiness)
50	1	1.43	Very Dark
50	3	2.33	Very Dark
50	5	2.58	Very Dark


Diameter of Hole at Start of Test:	1.0 mm
Diameter of Hole at End of Test:	4.0 mm
Water Content Prior to Test:	17.9 %
Dry Density of Sample Tested:	1.60 t/m ³

Pinhole Dispersion Classification – Method B: (7 Day Curing)	D (Dispersive)
--------------------------------------------------------------	----------------

CRUMB TEST: ASTM D6572-13e2 (Method B)

Elapsed Time	Estimated Slaking	Observations Recorded
2 min	< 1%	Colloidal cloud evident around cube
1 hr	≈ 40%	Heavy colloidal cloud ≈ 20mm deep covering entire bottom
6 hr	≈ 95% - 100%	Heavy colloidal cloud ≈ 20mm deep covering entire bottom

Crumb Test Classification: (7 Day Curing)	Grade 4 (Dispersive)
-------------------------------------------	----------------------



Note:

- Distilled water was used in the pinhole dispersion and crumb test. Both tests were carried out on remoulded samples.
- The pinhole dispersion sample was compacted to 95% NZ standard compaction.
- Photograph at completion of the crumb test.
- The sample tested was the fraction passing the 2.00mm sieve.

General Notes:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 25-Jan-20 to 7-Feb-20

Checked By:

All tests reported herein have been performed in accordance with the scope of the laboratory's accreditation





TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Loess	Order No:	N/A
Sample Source:	BS01 @ 0.5m, BS03 @ 0.7m, BS07 @ 0.5m, BS08 @ 0.6m, BS010 @ 0.7m, BS011 @ 1.3m, BS012 @ 0.4m and BS013 @ 1.2m combined – 2.5% Added Hydrated Lime (by dry mass)		
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Unknown	Date Requested:	20-Jan-20

PLASTICITY INDEX RESULTS - NZS 4402:1986, Test 2.2, 2.3 & 2.4	
Sample Description:	Loess - 2.5% Added Hydrated Lime (by dry mass)
Time Cured For:	28 days
Liquid Limit: (LL)	53
Plastic Limit: (PL)	30
Plasticity Index: (PI)	23
<i>Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.</i>	

General Notes:

- IANZ endorsement of this report applies to the samples as received.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 25-Jan-20 to 7-Feb-20

Checked By:

Approved Signatory

A.P. Julius
Laboratory Manager

All tests reported herein
have been performed in
accordance with the
scope of the
laboratory's
accreditation






TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Siltstone – Sandy SILT with minor clay	Client Order No:	Not Stated
Sample Source:	BH05 @ 2.7m - 7.2m	Sample Label No:	N/A
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Borehole *	Date Received:	December 2019

WATER CONTENT & NZ STANDARD COMPACTION - NZS 4402:1986, Test 2.1 & 4.1.1

% Retained (+19.0mm Fraction)	0.0 %
Water Content: ("All In" As Received)	13.7 %
Maximum Dry Density:	1.76 t/m ³
Optimum Water Content:	16.0 %
Notes: <ul style="list-style-type: none"> The sample was received in a natural state. The material tested in the NZ Standard Compaction test was whole soil. The air voids lines were calculated from an assumed solid density of 2.70 t/m³. 	



PLASTICITY INDEX RESULTS - NZS 4402:1986, Test 2.2, 2.3 & 2.4

Liquid Limit: (LL)	41
Plastic Limit: (PL)	25
Plasticity Index: (PI)	16
<i>Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.</i>	

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith, N.P. Danischewski, C. Fisher & C. Pearson

Date: 10-Jan-20 to 4-Mar-20

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434

Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."




TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS

Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Siltstone – Sandy SILT with minor clay	Client Order No:	Not Stated
Sample Source:	BH05 @ 2.7m - 7.2m	Sample Label No:	N/A
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Borehole *	Date Received:	December 2019

UNCONFINED COMPRESSIVE STRENGTH - NZS 4402:1986, Test 6.3.1

Sample Diameter: (mm)	101.50
Sample Length: (mm)	202.68
Length / Diameter Ratio:	2.00
Bulk Density: (t/m ³)	1.94
Water Content: (%)	15.9
Dry Density (t/m ³)	1.67
Mode of Failure:	Plastic / Plastic Brittle
Strain @ Failure:	2.0 %
Load @ Failure:	0.840 kN
Unconfined Compressive Strength:	100 kPa
Notes: 1. Dry density rounded to the nearest 0.01 t/m ³ . 2. The rate of axial compression was 0.40 mm/min.	



Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith, N.P. Danischewski, C. Fisher & C. Pearson

Date: 10-Jan-20 to 4-Mar-20

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation





TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS


Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Sands & Sandstone; SILT & SAND with minor clay	Client Order No:	Not Stated
Sample Source:	BH10 @ 2.4m - 7.0m	Sample Label No:	N/A
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Borehole *	Date Received:	December 2019

WATER CONTENT & NZ STANDARD COMPACTION - NZS 4402:1986, Test 2.1 & 4.1.1 DRY DENSITY & ABSORPTION - NZS 3111:1986, Test 12

% Retained (+19.0mm Fraction)	8.0 %
Water Content: ("All In" As Received)	11.9 %
Dry Density: (+19.0mm Fraction)	2.45 t/m ³
Absorption (+19.0mm Fraction)	3.7 %
Maximum Dry Density: (-19.0mm Fraction)	1.85 t/m ³
Optimum Water Content: (-19.0mm Fraction)	14.0 %

Notes:

- The sample was received in a natural state.
- The material tested in the NZ Standard Compaction test was the fraction passing a 19.0mm test sieve.
- The air voids lines were calculated from an assumed solid density of 2.70 t/m³.



PLASTICITY INDEX RESULTS - NZS 4402:1986, Test 2.2, 2.3 & 2.4

Liquid Limit: (LL)	37
Plastic Limit: (PL)	23
Plasticity Index: (PI)	14
Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.	

Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith, N.P. Danischewski, C. Fisher & C. Pearson

Date: 10-Jan-20 to 4-Mar-20

Checked By:

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation





TEST REPORT – DCC SMOOTH HILL INVESTIGATIONS


Client Details:	GHD Ltd, P.O. Box 13468, Christchurch	Attention:	J. Southworth
Job Description:	DCC Smooth Hill Landfill Investigations		
Sample Description:	Sands & Sandstone; SILT & SAND with minor clay	Client Order No:	Not Stated
Sample Source:	BH10 @ 2.4m - 7.0m	Sample Label No:	N/A
Date & Time Sampled:	Unknown	Sampled By:	GHD Ltd Staff
Sample Method:	Borehole *	Date Received:	December 2019

UNCONFINED COMPRESSIVE STRENGTH - NZS 4402:1986, Test 6.3.1

Sample Diameter: (mm)	101.49
Sample Length: (mm)	202.66
Length / Diameter Ratio:	2.00
Bulk Density: (t/m ³)	2.00
Water Content: (%)	13.9
Dry Density (t/m ³)	1.76
Mode of Failure:	Plastic / Plastic Brittle
Strain @ Failure:	1.7 %
Load @ Failure:	0.767 kN
Unconfined Compressive Strength:	93 kPa

Notes:

1. Dry density rounded to the nearest 0.01 t/m³.
2. The rate of axial compression was 0.40 mm/min.



Note:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method * and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith, N.P. Danischewski, C. Fisher & C. Pearson

Date: 10-Jan-20 to 4-Mar-20

Checked By:

Approved Signatory

A.P. Julius
Laboratory Manager

Tests indicated as
Not Accredited are
outside the scope of
the laboratory's
accreditation

IANZ
ACCREDITED LABORATORY
Accreditation No: 434

Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing

"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."

This report has been prepared by Matt Fitzmaurice, John Southworth and Dhugal McQuistan under the direction of Samantha Webb, a Technical Director and Engineering Geologist with GHD Ltd. Matt has 9 years as an engineering geologist, John has 23 years experience as an engineering geologist and Dhugal has 4 years experience as a geotechnical engineer. Samantha has 30 years in all aspects of engineering geology including a number of landfill projects and has the following qualifications BSc (Hons) Earth Sciences and MSc Engineering Geology.

GHD





Level 4 Security Building
115 Stuart Street
T: 64 3 378 0991 F: E:

© GHD 2021

This document is and shall remain the property of GHD. The document may only be used for the purpose for which it was commissioned and in accordance with the Terms of Engagement for the commission. Unauthorised use of this document in any form whatsoever is prohibited.

https://ghdnet-my.sharepoint.com/personal/mette_vanlith_ghd_com/Documents/Desktop/Smooth Hill/20210427 Technical Report E - Geotechnical Factual Report_20052021.docx

Document Status

Revision	Author	Reviewer		Approved for Issue		
		Name	Signature	Name	Signature	Date
Rev01	M. Fitzmaurice/ J. Southworth	S.Webb		S.Douglass		17-8-20
Rev02	J.Southworth	S.Webb		S.Douglass		24-05-21

www.ghd.com

